

| | | A0.01 | GENERAL CONDITIONS AND DRAWING INDEX |
|--------------------------|-----------------------|-------------------|--------------------------------------|
| SITE DEVELOPME | NT | A0.02 | EXISTING SURVEY |
| INFORMATION | | A0.03 | SITE PLAN |
| Occupancy Type: | (R) Residential | A0.04 | BUILDING DEMOLITION PLAN |
| Construction Type: | V | A1.01 | FIRST FLOOR PLAN |
| Sq. Footage Allowed: | 2,800 | A1.02 | SECOND FLOOR PLAN |
| Sq. Footage Actual: | 2,721 | A1.03 | ROOF PLAN |
| Imp. Cover Allowed: | 3,150 sq. ft. | A2.01 | EAST AND NORTH BUILDING ELEVATIONS |
| Imp. Cover Actual: | 2,662 sf. (38%) | A2.02 | WEST AND SOUTH BUILDING ELEVATIONS |
| Site Square Footage: | 7,000 sq. ft. | A3.01 | BUILDING SECTION AND DETAILS |
| Parking Reqd / Provided: | 4 / 4 | A4.01 | FIRST FLOOR POWER AND LIGHTING PLAN |
| Zoning: | SF-3 | A4.02 | SECOND FLOOR POWER AND LIGHTING PLAN |
| Gross Site Area: | 7,000 sq. ft. | 6.4 | 50,000,47,000, 80,000 |
| | | S1 | FOUNDATION PLAN |
| | | S2 | FOUNDATION NOTES AND DETAILS |
| | | S3.1 | FLOOR AND ROOF FRAMING PLANS |
| | | S3.2 | UPPER ROOF FRAMING PLAN |
| | | S3.3 | FIRST FLOOR BRACING PLAN |
| | | S3.4 | SECOND FLOOR BRACING PLAN |
| | | S4 | STRUCTURAL GENERAL NOTES |
| | * * * | · · · | |
| (| AL NOTE: | | |
| \ ALL OU | JTSTANDING PERMITS HA | AVE BEEN RESOLVEI | O PRIOR TO COMMENCEMENT |

GENERAL CONDITIONS

ALL WORK SHALL COMPLY WITH APPLICABLE NATIONAL STATE AND LOCAL ORDINANCES AND WITH THE APPLICATION EDITION OF THE UBC. DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE. CONTRACTOR SHALL BE RESPONSIBLE FOR MEANS AND METHODS OF CONSTRUCTION, INCLUDING BUT NOT LIMITED TO SHORING AND TEMPORARY BRACING.
CONTRACTOR SHALL UNDERTAKE ALL NECESSARY MEASURES TO INSURE SAFETY OF ALL PERSONS AND STRUCTURES AT THE JOB SITE AND ADJACENT TO THE SITE. OBSERVATION VISITS TO THE SITE BY THE DESIGNER OR ENGINEER DOES NOT INCLUDE REVIEW OF THESE MEASURES OR ANY OF THE CONTRACTOR'S WORK. THE CONTRACTOR IS RESPONSIBLE FOR VERIFICATION OF ON-SITE DIMENSIONS AND CONDITIONS AND SHALL REPORT DISCREPANCIES IMMEDIATELY TO THE DESIGNER (ODOM TURNER STUDIO). WHEN APPLICABLE, THE SOIL REPORT, THE STRUCTURAL CALCULATIONS AND THE ENERGY CALCULATIONS AS WELL AS THE RECOMMENDATIONS CONTAINED THEREIN, ARE AN INTEGRAL PART OF THE CONTRACT

THE INTENTION OF THESE DOCUMENTS IS TO INCLUDE LABOR, MATERIALS, SERVICE, EQUIPMENT, TRANSPORTATION NECESSARY FOR COMPLETE AND PROPER EXECUTION OF THE WORK INDICATED ON THE DRAWINGS AND THE WORK THAT CAN BE REASONABLY INFERRED THEREFROM AS BEING NECESSARY TO PRODUCE THE INTENDED RESULTS. THE DRAWINGS SHALL NOT BE SCALED FOR MEASUREMENTS.

THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS REQUIRED FOR EXECUTION OF THIS PROJECT. PERMITTING FEES ARE TO BE INCLUDED IN THE CONTRACTORS FINAL BID PACKAGE. THE OWNER IS RESPONSIBLE FOR PROVIDING THE CONTRACTOR WITH ALL NECESSARY DRAWINGS AND SPECIFICATIONS IN A TIMELY MANNER, FOR THE PERMITTING

CLEAN-UP THE CONTRACTOR AT ALL TIMES SHALL KEEP THE PREMISES FREE FROM ACCUMULATION OF WASTE MATERIALS AND RUBBISH. AT THE COMPLETION OF THE WORK THE CONTRACTOR SHALL REMOVE ALL WASTE MATERIALS AND RUBBISH FROM THE SITE AS WELL AS ALL TOOLS, CONSTRUCTION EQUIPMENT, MACHINERY AND SURPLUS MATERIALS. FINAL CLEANING SHALL INCLUDE: BROOM CLEAN ALL PAVED AREAS ON THE SITE AND ADJACENT AREAS. REMOVE ALL TRACES OF SOIL, WASTE MATERIAL, SMUDGES AND OTHER FOREIGN MATTER FROM ALL INTERIOR AND EXTERIOR SURFACES, CLEAN ALL GLASS SURFACES AND MIRRORS, INSIDE AND OUTSIDE.

TAKE ALL NECESSARY MEASURES TO FULLY PROTECT ADJACENT PROPERTIES AND THE LINDERGROUND AND OVERHEAD LITHLITY LINES EXCAVATIONS SHALL BE KEPT FREE OF STANDING WATER. WHERE EXCAVATIONS ARE MADE TO DEPTHS GREATER THAN INDICATED. THEY SHALL BE FILLED WITH CONCRETE AS SPECIFIED FOR FOOTINGS, UNDER FOOTINGS AND FOUNDATIONS, AND WITH PROPERLY COMPACTED SOIL IN ALL OTHER AREAS. BACK FILL SHALL BE COMPACTED TO A MINIMUM 90 PERCENT DENSITY AND SHALL BE DONE IN LAYERS OF I'-O" MAX.

SANDBLAST CONCRETE RETAINING WALLS FOLLOWING COMPLETE CURING. REMOVE ALL EXPOSED AND LOOSE PAPER BAG RUBBISH FROM SITE AND DISPOSE OF PROPERLY.

MINIMUM COMPRESSION STRENGTH AT 28 DAYS FROM INITIAL DATE OF POLIR-2,000 PSI

FOOTINGS ALL OTHER CONCRETE 3,000 PSI

THE CONCRETE SHALL BE SUPPLIED BY AN APPROVED READY MIX PLANT, THE SLUMP SHALL NOT EXCEED 4"

REINFORCING STEEL SHALL BE DEFORMED BAR STEEL, GRADE 40 FOR #3 AND 44, GRADE 60 FOR #5 AND LARGER, CONFORMING TO ASTM A615. LAP BARS 40 DIAM. MIN. WELDED WIRE FABRÏC SHALL CONFORM TO ASTM AI 85.

REINFORCING STEEL SHALL HAVE A MINIMUM CONCRETE PROTECTIVE COVERINGS AS FOLLOWS: POURED AGAINST EARTH

POURED AGAINST FORMS BUT EXPOSED TO EARTH OR WEATHER

WALLS AND SLABS NOT EXPOSED TO EARTH OR WEATHER

WELDED WIRE FABRIC SHALL BE LAPPED 1 $\frac{1}{2}$ " SPACES. (9" MIN). WELDED REBAR TO BE A706 GRADE 60 USE E90XX WELDING ROD. INTERIOR SLABS SHALL RECEIVE A STEEL TROWEL FINISH, THE EXTERIOR SLABS TO BE BROOM FINISHED. UNLESS NOTED OTHERWISE

BOLTS, ANCHORS, HOLD-DOWNS AND ALL INSERTS SHALL BE ACCURATELY LOCATED AND SECURELY HELD IN PLACE UNTIL CONCRETE IS HARDENED. ALL HOLD-DOWNS SHALL BE TIED IN PLACE PRIOR TO FOUNDATION INSPECTION.

CONCRETE MASONRY UNITS SHALL BE GRADE N LINITS CONFORMING TO THE ASTM DESIGNATION. C90 AND, IN ADDITION, THE REQUIREMENTS OF THE QUALITY CONTROL STANDARDS OF THE

PORTLAND CEMENT SHALL CONFORM TO ASTM DESIGNATION C150

MORTAR SHALL CONFORM TO ASTM C270.

GROUT SHALL BE FLUID CONSISTENCY, GROUT MIX SHALL BE TRANSIT MIX CONFORMING TO ASTM C-94 AND SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 2000 PSI. REINFORCING STEEL SHALL BE DEFORMED BARS CONFORMING TO ASTM DESIGNATION A 615 EXCEPT THAT X" TIES MAY BE PLAIN BARS. WIRE REINFORCEMENT SHALL CONFORM TO ASTM.

ALL GROUT SHALL BE CONSOLIDATED BY: VIBRATING USING A 3/4" HEAD VIBRATOR FOR ONE OR TWO SECONDS, WITH VIBRATION DONE AFTER THE INITIAL LOSS OF WATER AND BEFORE INITIAL SET, IN LIFTS, NOT EXCEEDING 4'-0".

TOOL ALL JOINTS TO A DENSE, SMOOTH CONCAVE SURFACE.

FURNISH AND INSTALL METAL FLASHING, GUTTERS, COPINGS, ETC.. WHERE REQUIRED.

INSTALL EXPANSION JOINTS WHERE APPLICABLE, TO ADEQUATELY PROVIDE FOR THERMAL MOVEMENT OF THE FINISHED WORK

OF WORK OUTLINED HEREIN

FRAMING LUMBER SHALL BE #2 SOUTHERN PINE OR AS NOTED ON THE DRAWINGS. FASCIAS, OUTLOOKERS, EXPOSED BEAMS, ETC. SHALL BE RESAWN UNLESS NOTED OTHERWISE,

PROVIDE 2 X BACKING FOR ALL WALL HUNG CABINETS, SHELVING, HANDRAILS, LIGHT FIXTURES, ACCESSORIES FTC. THE FRAMING HARDWARE NOTATIONS ARE BASED ON SIMPSON STRONG TIES, EQUAL PRODUCTS OF OTHER MANUFACTURES ARE ACCEPTABLE. APPLY A CONTINUOUS BEAD OF STRUCTURAL GLUE TO EACH JOIST WHEN THE SPAN OF THE HEADER EXCEEDS 4'-0". VERIFY ALL NOTES WITH STRUCTURAL PLANS

06200

ALL JOINTS SHALL BE TIGHT AND TRUE AND SECURELY FASTENED. CORNERS SHALL BE NEATLY MITERED BUTTED OR COPED WITH NAILS SET AND SURFACES FREE OF TOOL MARKS SHELVING SHALL HAVE SOLID EDGING AND WOOD SPECIES AS NOTED, GRADE AA-INT.

WOOD WORK SHALL BE ACCURATELY SCRIBED TO FIT ADJOINING SURFACES.

ALL WORK SHALL BE MACHINED OR HAND-SANDED, SHARP EDGES AND SPLINTERS REMOVED AND COMPLETELY PREPARED FOR FINISH.

FULL LENGTH CONTINUOUS BOARDS SHALL BE USED WHEREVER APPLICABLE OR SPECIFICALLY

EACH DOOR SHALL BE ACCURATELY CUT, TRIMMED, AND FITTED TO ITS RESPECTIVE FRAME AND HARDWARE WITH THE ALLOWANCE FOR PAINTER'S FINISHES.

FURNISH AND INSTALL UNFACED BLANKET INSULATION WITH R-VALUES AS REQUIRED. SUPPORT THE INSULATION WHERE REQUIRED TO PREVENT FALLING OUT, WITH WIRE, NETTING, ETC.

ALL OPENINGS IN THE BUILDING ENVELOPE SHALL BE CAULKED OR OTHERWISE SEALED.

INCLUDING BUT NOT LIMITED TO:

1. EXTERIOR JOINTS AROUND DOOR AND WINDOW FRAMES. BETWEEN WALL PLATES AND FLOOR OR CEILING, RIM JOISTS AND MASONRY FIREPLACES, ETC 2. OPENINGS FOR PLUMBING, ELECTRICAL, COMMUNICATION, AND MECHANICAL WORK IN WALLS,

3. OPENINGS IN THE ATTIC CEILING.

THOROUGHLY CLEAN ALL JOINTS TO BE SEALED AND APPLY PRIMER WHERE RECOMMENDED BY THE SEALANT MANUFACTURER. ALL WATERPROOFING SHALL BE INSTALLED PER MANUFACTURERS SPECIFICATIONS.

07100

ON THE EXTERIOR SURFACE OF WALLS BELOW GRADE, APPLY TEMPROOF 60, VULKAM 201 H OR SIMILAR MATERIAL MEETING ASTM C-836-78 FOLLOWING THE MANUFACTURERS INSTRUCTIONS. SURFACES TO RECEIVE DAMP PROOFING; SHALL BE SMOOTH AND FREE OF LOOSE DIRT, EXCESS MORTAR, ETC

INSTALL AMOCO6 POLYSTYRENE PROTECTION BOARD BEFORE BACK FILLING DAMP PROOFING WALLS

SOLID CORE DOORS TO BE PAINTED. SHALL BE PAINT GRADE WOOD VENEER FOR FLUSH DOORS

CLEARANCES AT THE LOCK AND HANGING STILES AT THE TOP SHALL NOT EXCEED 1/8". CLEARANCE AT THE BOTTOM SHALL BE ADJUSTED FOR FINISH FLOOR COVERING SCHEDULE, INCLUDING CARPETING

LOCK STILE EDGES SHALL BE BEVELED.

DOORS SHALL OPERATE FREELY, BUT NOT LOOSELY, WITHOUT STICKING OR BINDING AND WITHOUT HINGE BOUND CONDITIONS, AND WITH ALL HARDWARE PROPERLY ADJUSTED AND

USE 56" THICKNESS DRYWALL PANELS ON WALLS AND CEILINGS U.N.O. TAPE AND FLOAT ALL DRYWALL EDGES. SMOOTH FINISH ALL WALLS AND CEILINGS. NO TEXTURE IS TO BE APPLIED TO ANY SURFACE. PREPARE ALL SURFACES FOR PAINT FINISH.

15700

MECHANICAL SYSTEMS TO BE INSTALLED BY A LICENSED PROFESSIONAL INSTALLER IN COMPLIANCE WITH LOCAL CODES. SYSTEM MUST BE APPROVED BY DANIEL SCOTT TURNER DESIGN PRIOR TO INSTALLATION.

Daniel Scott Turner Design

2430 Albans Roac Houston, Texas USA 7700! p 1 512 801 338 turnerdanielscott@gmail.con

CONSULTANTS



PROJECT NAME

4214 Avenue G Residence

Austin, Texas 78751

Sebastien Weyland and Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL PERMIT, OR CONSTRUCTION. © Daniel Scott Turner, 2014

REVISION # DATE



09 March, 2015

SHEET TITLE(S)

PROJECT CONDITIONS DRAWING INDEX Subchapter F Compliance


REVISION DATE:

ISSUE DATE:

21 DEC, 201

PROJECT NUMBER:

FOR REGULATORY REVIEW



Daniel Scott Turner Design

2430 Albans Roac Houston, Texas USA 7700! p 1 512 801 338 turnerdanielscott@gmail.con

CONSULTANTS

CONSULTANTS

OF 19461

PROJECT NAME

4214 Avenue G Residence

Austin, Texas 78751

Sebastien Weyland and Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL, PERMIT, OR CONSTRUCTION. © Daniel Scott Turner, 2014

REVISION # DATE



09 March, 2015

SHEET TITLE(S)

SURVEY OF EXISTING CONDITIONS

REVISION DATE:


ISSUE DATE:

21 DEC, 201

1400

PROJECT NUMBER:

A0.02



Daniel Scott Turner Design

2430 Albans Roac Houston, Texas USA 7700! p 1 512 801 338 turnerdanielscott@gmail.con

CONSULTANTS



PROJECT NAME

4214 Avenue G Residence

Austin, Texas 78751

Sebastien Weyland and Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL PERMIT, OR CONSTRUCTION © Daniel Scott Turner, 2014

REVISION # DATE



09 March, 2015

SHEET TITLE(S)

NEW CONSTRUCTION SITE PLAN

Subchapter F Compliance

REVISION DATE:

ISSUE DATE:

21 DEC, 201

PROJECT NUMBER:


1400


A0.03


DEMOLITION WALL LEGEND

INDICATES WALLS TO REMAIN

INDICATES WALLS TO REMAIN







01 SECOND FLOOR DEMOLITION
SCALE 1/8" = 1'-0"

01 FIRST FLOOR DEMOLITION SCALE 1/8" = 1'-0"

Daniel Scott Turner Design

2430 Albans Roac Houston, Texas USA 7700! p 1 512 801 338 turnerdanielscott@gmail.con

CONSULTANTS



PROJECT NAME

4214 Avenue G Residence

Austin, Texas 78751

Sebastien Weyland and Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL, PERMIT, OR CONSTRUCTION. © Daniel Scott Turner, 2014

REVISION # DATE



SHEET TITLE(S)

EXISTING RESIDENCE DEMOLITION PLANS

Subchapter F Compliance

REVISION DATE:

ISSUE DATE:

ATE: 21 DEC, 201

PROJECT NUMBER:

 Λ

| 00 | SIZE '-0" X 7'-0"" 3'-0" X 7'-0" | TYPE EXT - SCWD EXT - GLASS | NOTE STOREFRONT | QUANTITY 1 |
|-------------|--|-----------------------------------|--------------------|---------------|
| <u>@</u> | 3'-0" X 7'-0" | | | 1 |
| ~~~ | | FXT - GLASS | | |
| 63 | | LIII OLNOO | STOREFRONT | 1 |
| (0) | S'-0" X 7'-0" | EXT - GLASS | PATIO SLIDER | 3 |
| ©4 2 | 2'-8" X 7'-0" | EXT - SCWD | FULL LITE GLASS | 3 |
| 05 5 | 5'-0" X 7'-0" | EXT - SCWD | PAIR | 1 |
| 06 2 | 2'-8" X 7'-0" | INT - SCWD | POCKET DOOR | 3 |
| (i) | 2'-8" X 7'-0" | INT - SCWD | PRIVACY HDWR | 1 |
| 08 : | 5'-0" X 7'-0" | INT - SCWD | PAIR - POCKET | 1 |
| <u></u> | 2'-8" X 7'-0" | INT - SCWD | PAIR | 1 |
| | | | | |
| | | | | |

GENERAL PLAN NOTES

- 1.) REFERENCE ELEVATION SHEETS A2.01 TO A2.04 FOR WINDOW SCHEDULE AND HEIGHT INFORMATION.
- 2.) ALL DIMENSIONS ARE ROUGH FRAMING DIMENSIONS
- TO THE FACE OF STUD UNLESS NOTED OTHERWISE.
- 3.) ALL WINDOW DIMENSIONS ARE TO THE CENTER OF THE FRAME. VERIFY ROUGH OPENING DIMENSIONS WITH WINDOW UNIT DIMENSIONS.

GENERAL PLAN LEGEND

BUILDING SECTION / ELEVATION

HOSE BIB

NATURAL GAS


NEW CONSTRUCTION EXTERIOR WALL

NEW CONSTRUCTION INTERIOR WALL

EXISTING WALL TO REMAIN

VISITABILITY COMPLIANCE NOTES

- 1.) VISITABILITY COMPLIANT ENTRANCE TO HAVE MAXIMUM 1/2" BEVELED THRESHOLD.
- 2.) ALL LIGHT SWITCHES AND ENVIRONMENTAL CONTROLS TO BE MOUNTED MAX. 48" A.F.F.
- 3.) WALL MOUNT ELECTRICAL RECEPTACLES TO BE MOUNTED AT 15" A.F.F.
- 4.) COMPLIANT BATHROOM, LIVING ROOM, DINING ROOM, AND KITCHEN ON VISITABILITY ROUTE.
- 5.) PROVIDE 2X6 BLOCKING IN WALLS AND AS REQUIRED IN ACCORDANCE WITH CITY OF AUSTIN ORDINANCE 20140130-021



Daniel Scott Turner Design

2430 Albans Roac Houston, Texas USA 7700! p 1 512 801 338 turnerdanielscott@gmail.con



PROJECT NAME

4214 Avenue G Residence Austin, Texas 78751

Sebastien Weyland and Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL, PERMIT, OR CONSTRUCTION.

REVISION # DATE

© Daniel Scott Turner, 2014



09 March, 2015

SHEET TITLE(S)

GROUND FLOOR
NEW CONSTRUCTION
PLAN

REVISION DATE:

ISSUE DATE:

GROUND FLOOR PLAN

SCALE 1/8" = 1'-0"

DATE: 21 DEC, 201

PROJECT NUMBER:

A1.01

| DOOF | RSCHEDULE | | | |
|------------|----------------|-------------|-----------------|----------|
| TAG | SIZE | TYPE | NOTE | QUANTITY |
| 01 | 3'-0" X 7'-0"" | EXT - SCWD | STOREFRONT | 1 |
| @ | 3'-0" X 7'-0" | EXT - GLASS | STOREFRONT | 1 |
| 03 | 6'-0" X 7'-0" | EXT - GLASS | PATIO SLIDER | 3 |
| @ 4 | 2'-8" X 7'-0" | EXT - SCWD | FULL LITE GLASS | 3 |
| © | 5'-0" X 7'-0" | EXT - SCWD | PAIR | 1 |
| <u>@</u> | 2'-8" X 7'-0" | INT - SCWD | POCKET DOOR | 3 |
| 07 | 2'-8" X 7'-0" | INT - SCWD | PRIVACY HDWR | 1 |
| 08 | 5'-0" X 7'-0" | INT - SCWD | PAIR - POCKET | 1 |
| 09 | 2'-8" X 7'-0" | INT - SCWD | PAIR | 1 |
| | | | | |
| | | | | |
| | | | | |

GENERAL PLAN NOTES

- 1.) REFERENCE ELEVATION SHEETS A2.01 TO A2.04 FOR WINDOW SCHEDULE AND HEIGHT INFORMATION.
- 2.) ALL DIMENSIONS ARE ROUGH FRAMING DIMENSIONS TO THE FACE OF STUD UNLESS NOTED OTHERWISE.
- 3.) ALL WINDOW DIMENSIONS ARE TO THE CENTER OF THE FRAME. VERIFY ROUGH OPENING DIMENSIONS WITH WINDOW UNIT DIMENSIONS.

GENERAL PLAN LEGEND


01/A3.02 BUILDING SECTION / ELEVATION

+ HOSE BIB
NATURAL GAS

NEW CONSTRUCTION EXTERIOR WALL

NEW CONSTRUCTION INTERIOR WALL

EXISTING WALL TO REMAIN





Daniel Scott Turner Design

2430 Albans Roac Houston, Texas USA 7700! p 1 512 801 338 turnerdanielscott@gmail.con



PROJECT NAME

4214 Avenue G Residence Austin, Texas 78751

Sebastien Weyland and Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL, PERMIT, OR CONSTRUCTION.

© Daniel Scott Turner, 2014

REVISION # DATE



09 March, 2015

SHEET TITLE(S)

SECOND FLOOR
NEW CONSTRUCTION
PLAN

REVISION DATE:


ISSUE DATE:

21 DEC, 201

PROJECT NUMBER:

A1.02





GENERAL PLAN NOTES

- 1.) REFERENCE ELEVATION SHEETS A2.01 TO A2.04 FOR WINDOW SCHEDULE AND HEIGHT INFORMATION.
- 2.) ALL DIMENSIONS ARE ROUGH FRAMING DIMENSIONS TO THE FACE OF STUD UNLESS NOTED OTHERWISE.
- 3.) ALL WINDOW DIMENSIONS ARE TO THE CENTER OF THE FRAME. VERIFY ROUGH OPENING DIMENSIONS WITH WINDOW UNIT DIMENSIONS.

GENERAL PLAN LEGEND


| 01/A3.02 | BUILDING SECTION / ELEVATION |
|--------------------|--------------------------------|
| D \$ | HOSE BIB NATURAL GAS |
| | NEW CONSTRUCTION EXTERIOR WAL |
| | NEW CONSTRUCTION INTERIOR WALI |


VISITABILITY COMPLIANCE NOTES

1.) VISITABILITY COMPLIANT ENTRANCE TO HAVE MAXIMUM 1/2" BEVELED THRESHOLD.

EXISTING WALL TO REMAIN

- 2.) ALL LIGHT SWITCHES AND ENVIRONMENTAL CONTROLS TO BE MOUNTED MAX. 48" A.F.F.
- 3.) WALL MOUNT ELECTRICAL RECEPTACLES TO BE MOUNTED AT 15" A.F.F.
- 4.) COMPLIANT BATHROOM, LIVING ROOM, DINING ROOM, AND KITCHEN ON VISITABILITY ROUTE.
- 5.) PROVIDE 2X6 BLOCKING IN WALLS AND AS REQUIRED IN ACCORDANCE WITH CITY OF AUSTIN ORDINANCE 20140130-021









2430 Albans Roac Houston, Texas USA 7700: p 1 512 801 338 turnerdanielscott@gmail.con

CONSULTANTS



PROJECT NAME

4214 Avenue G Residence

Austin, Texas 78751

Sebastien Weyland and Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL, PERMIT, OR CONSTRUCTION. © Daniel Scott Turner, 2014

REVISION # DATE



09 March, 2015

SHEET TITLE(S)

ROOF / CLERESTORY NEW CONSTRUCTION PLAN

REVISION DATE:

ISSUE DATE:

21 DEC, 201


PROJECT NUMBER:

41.03



01/A2.02

| WINDOW SCHEDULE | | | | | |
|-------------------------|---------------|-------------------------|-----------|----------|------------|
| TAG | SIZE | . <u>C</u> OPERATION | WALL TYPE | QUANTITY | SAFETY GL. |
| $\overline{\mathbb{A}}$ | 6'-0" X 3'-0" | DBL HUNG | 2X4 | 6 | T |
| $\overline{\mathbb{B}}$ | NOT USED | | | | |
| $\overline{\mathbb{C}}$ | 2'-8" X 7'-0" | PICTURE | 2X6 | 2 | T |
| | 3'-4" X 5'-0" | PICTURE | 2X6 | 1 | T |
| E | 4'-0" X 2'-0" | PICTURE | 2X4 | 1 | T |
| F | 3'-6" X 3'-6" | PICTURE | 2X6 | 1 | |
| G | 2'-0" X 4'-6" | CSMNT | 2X6 | 1 | Т |
| \bigcirc H \bigcirc | 2'-8" X 4'-6" | CSMNT | 2X6 | 1 | T |
| | 4'-6" X 2'-6" | PICTURE | 2X6 | 4 | |
| K | 3'-0" X 3'-0" | PICTURE | 2X4 | 5 | T |
| | 4'-0" X 2'-0" | PICTURE | 2X6 | 2 | |
| \overline{M} | 4'-0" X 2'-0" | CSMNT | 2X6 | 1 | T |
| $\overline{\mathbb{N}}$ | 1'-6" X 6'-0" | PICTURE | 2X6 | 1 | T |
| <u>P</u> | 2'-0" X 2'-0" | PICTURE | 2X6 | 1 | |
| Q | 2'-0" X 6'-0" | PICTURE | 2X6 | 1 | T |
| $\overline{\mathbb{R}}$ | 6'-0" X 1'-6" | PICTURE | 2X6 | 1 | |
| <u>(S)</u> | 1'-8" X 1'-8" | PICTURE | 2X6 | 1 | |
| | 1'-6" X 4'-6" | PICTURE | 2X4 | 1 | Т |
| | 3'-0" X 3'-6" | CSMNT | 2X4 | 1 | Т |
| $\overline{\mathbb{V}}$ | 1'-6" X 6'-0" | PICTURE | 2X4 | 1 | T |




SCALE 1/4" = 1'-0"

NORTH (STREET) ELEVATION

EAST (STREET) ELEVATION

SCALE 1/4" = 1'-0"



Daniel Scott Turner Design

2430 Albans Roac Houston, Texas USA 7700! p 1 512 801 338 turnerdanielscott@gmail.con

CONSULTANTS



PROJECT NAME

130.26 **4214 Avenue G** Residence

Austin, Texas 78751 Sebastien Weyland and

Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL, PERMIT, OR CONSTRUCTION. © Daniel Scott Turner, 2014

REVISION # DATE



09 March, 2015

SHEET TITLE(S)

EXTERIOR ELEVATIONS

REVISION DATE:

ISSUE DATE:

PROJECT NUMBER:

PROJECT NUMBER.


A2.01

21 DEC, 201

| WINDOW SCHEDULE | | | | | |
|--------------------------------|---------------|-----------|-----------|----------|------------|
| TAG | SIZE | OPERATION | WALL TYPE | QUANTITY | SAFETY GL. |
| $\overline{\langle A \rangle}$ | 6'-0" X 3'-0" | DBL HUNG | 2X4 | 6 | Ţ |
| $\overline{\mathbb{B}}$ | NOT USED | | | | |
| C | 2'-8" X 7'-0" | PICTURE | 2X6 | 2 | T |
| | 3'-4" X 5'-0" | PICTURE | 2X6 | 1 | T |
| E | 4'-0" X 2'-0" | PICTURE | 2X4 | 1 | T |
| E | 3'-6" X 3'-6" | PICTURE | 2X6 | 1 | |
| G | 2'-0" X 4'-6" | CSMNT | 2X6 | 1 | T |
| $\overline{\mathbb{H}}$ | 2'-8" X 4'-6" | CSMNT | 2X6 | 1 | T |
| | 4'-6" X 2'-6" | PICTURE | 2X6 | 4 | |
| K | 3'-0" X 3'-0" | PICTURE | 2X4 | 5 | T |
| | 4'-0" X 2'-0" | PICTURE | 2X6 | 2 | |
| \overline{M} | 4'-0" X 2'-0" | CSMNT | 2X6 | 1 | T |
| $\langle N \rangle$ | 1'-6" X 6'-0" | PICTURE | 2X6 | 1 | T |
| P | 2'-0" X 2'-0" | PICTURE | 2X6 | 1 | |
| Q | 2'-0" X 6'-0" | PICTURE | 2X6 | 1 | T |
| R | 6'-0" X 1'-6" | PICTURE | 2X6 | 1 | |
| S | 1'-8" X 1'-8" | PICTURE | 2X6 | 1 | |
| | 1'-6" X 4'-6" | PICTURE | 2X4 | 1 | T |
| U | 3'-0" X 3'-6" | CSMNT | 2X4 | 1 | T |
| $\overline{\mathbb{V}}$ | 1'-6" X 6'-0" | PICTURE | 2X4 | 1 | T |



SOUTH ELEVATION SCALE 1/4" = 1'-0"




WEST (REAR) ELEVATION SCALE 1/4" = 1'-0"

Daniel Scott Turner Design

2430 Albans Roac Houston, Texas USA 7700! p 1 512 801 338 turnerdanielscott@gmail.con

CONSULTANTS



PROJECT NAME

4214 Avenue G Residence

Austin, Texas 78751

Sebastien Weyland and Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL PERMIT, OR CONSTRUCTION. © Daniel Scott Turner, 2014

REVISION # DATE



09 March, 2015

SHEET TITLE(S)

EXTERIOR ELEVATIONS


REVISION DATE:

ISSUE DATE:

PROJECT NUMBER:

A2.02


21 DEC, 201




FOR REGULATORY REVIEW

A3.01

Daniel





01 FIRST FLOOR POWER AND LIGHTING
SCALE 1/4" = 1'-0"

Daniel Scott Turner Design

2430 Albans Roac Houston, Texas USA 7700! p 1 512 801 338 turnerdanielscott@gmail.con

CONSULTANTS

CONSULTANTS

PROJECT NAME

4214 Avenue G Residence Austin, Texas 78751

Sebastien Weyland and

Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL, PERMIT, OR CONSTRUCTION.

REVISION # DATE

© Daniel Scott Turner, 2014



09 March, 2015

SHEET TITLE(S)

FIRST FLOOR LIGHTING AND POWER PLAN


REVISION DATE:


ISSUE DATE:


21 DEC, 201

PROJECT NUMBER:

A4.01







Daniel Scott Turner Design

> 2430 Albans Roac Houston, Texas USA 7700! p 1 512 801 338 turnerdanielscott@gmail.con

CONSULTANTS



PROJECT NAME

4214 Avenue G Residence Austin, Texas 78751

Sebastien Weyland and

Dana Wassarman

IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR REGULATORY APPROVAL, PERMIT, OR CONSTRUCTION. © Daniel Scott Turner, 2014

REVISION # DATE



09 March, 2015

SHEET TITLE(S)

UPPER FLOOR LIGHTING AND POWER PLAN

REVISION DATE:

ISSUE DATE:

21 DEC, 201

PROJECT NUMBER:

A4.02

01 UPPER FLOOR POWER AND LIGHT PLAN

SCALE 1/4" = 1'-0"

GREENEARTH ENGINEERING, INC.
STRUCTURAL CONSULTING ENGINEERS
SEOW WEST WILLIAM CANNON BG. 1521 ASTIN, IN 78745
PRIONE (22. 288—2006 FAX (512) 422—0800
GE. JOB NOI: 14192

9 4214 AVE AUSTIN, TX

CHK. BY: TZ DRWN. BY: TZ DATE: 12/21/2014

SHEET NO.

S1

GREENEARTH ENGINEERING. INC.
STRUCTURAL CONSULTING ENGINEERS
SON STRIMM CANNON DR. \$201 MOTHL X 7814
PROOF \$273 288-9008
FOUR \$103 889-9008
E- JOB NO: 14192


 \mathcal{O} Z Z 4214 A1 AUSTIN,


CHK. BY: TZ DRWN. BY: TZ DATE: 12/21/2014


SHEET NO.

S2


OF








SECTION






NOTE: SEE 1/THIS SHEET FOR INFORMATION NOT SHOWN.

SECTION






NOTE: SEE 1/THIS SHEET FOR INFORMATION NOT SHOWN.




















SECTION

SECTION

NOTE: SEE 1/THIS SHEET FOR INFORMATION NOT SHOWN.



BUILDING PAD PREPARATION

1. Structural fill material shall consist of crushed limestone base material with the gradation as follows:

Retained on 2-1/2" screen Retained on 1-1/2" screen Retained on 3/4" screen Retained on 1/4" screen Retained on No. 40 mesh sieve

- Prior to placing fill material, remove all organic and other deleterious material from the existing subgrade for a distance of 2"-O" beyond building line. All exposed surfaces shall then be recompacted to a minimum of 95 percent of the maximum dry density as defined by 12001 test method 152 113-E or 114-E at a moisture content within 3 percent of the optimum maisture content. NOTE: THIS NOTE DOES NOT APPLY 10 THE 50% CRITICAL ROTO ZONE OF ANY PROTECTED TREE.
- Structural fill shall be placed in 8 inch loose lifts, watered as required and compacted to a minimum of 95 percent of the maximum dry density as defined in TADOT test method TEX 113-E at a moisture content within 3 percent of the optimum moisture content.
- Provide a 10 mil polyolefin Stego retarder. Place vapor barrier in accordance with manufacturer's recommendation on top of structural fill.

CAST IN PLACE CONCRETE

The use of fly ash is recommended, but shall not exceed 25% of the total of the cement plus fly ash by weight.


CONCRETE REINFORCING

- 1. Reinforcing steel shall be deformed new billet steel bars in accordance with ASTM A615 Grade 60.
- 2. Detailing of reinforcing steel shall conform to the American Concrete Institute Detailing Manual.
- Provide 2-#4 bent bar with 2'-0" legs top and bottom in interior and exterior face of grade beams at corners and top and bottom in exterior face of grade beam at intersections.
- 4. All hooks and bends in reinforcing bars shall conform to ACI detailing standards unless shown otherwise.
- 5. Welding of reinforcing steel will not be permitted.
- 6. Heat shall not be used in the fabrication or installation of reinforcement.
- 7. Reinforcing steel clear cover shall be as follows:
- a. Grade beams 1 1/2" top, 3" bottom, 2" side (formed), 3" side (placed against earth)



9 Z Z 4214 AV





2ND FLOOR/LOWER ROOF FRAMING PLAN

1/8" = 1'-0"

PLAN NOTES:

1. ALL WALLS ARE 2x4 @ 16" LOAD BEARING WALLS UNLESS NOTED OTHERWISE IN THIS PLAN. WALLS MARKED 2x6 ARE 2x6 @ 16" O.C.

2. BEAMS AND HEADERS SHALL BE SUPPORTED BY BUILT-UP COLUMNS & BLOCK SOLID TO FOUNDATION. SEE SCHEDULE IN THIS SHEET FOR BUILT-UP COLUMN SIZES.

- 3. LVL BEAMS AT THE BALCONY SHALL BE WRAPPED WITH WATERPROOF MATERIAL.
- 4. EXTERIOR WALLS AT THE STAIR SHALL BE CONTINUOUS FROM FOUNDATION TO RO
- 5. L4x4x1/4 x 12" LONG WITH 3-3/4"Ø THRU BOLTS INTO LVL BEAM AND WELD TO STEEL BEAM W/ 1/4" FILLET WELD

6. 4"Ø STANDARD STEEL PIPE COLUMN. SEE 3/S4 FOR STEEL BEAM OVER COLUMN CONNECTION.

| | BEAM SIZE | BUILT-UP STUD COLUMN |
|-------|------------------------|----------------------|
| L. | 2- 1 3/4"x14" LVL & UP | 4- STUD COLUMN |
| ROOF. | 2- 1 3/4"x12" LVL | 3- STUD COLUMN |
| | 3- 2 x | 3- STUD COLUMN |
| | 2- 2 x 12 | 3- STUD COLUMN |
| | 2- 2 x 10 OR SMALLER | 2- STUD COLUMN |


BUILT-UP COLUMN SCHEDULE

| _ | |
|------|------|
| _ | |
| REV. | DATE |
| | |
| | |
| | |
| | |
| | |
| | _ |

CHK. BY: TZ DRWN. BY: TZ DATE: 12/21/2014


SHEET NO.

S3.1



GREENEARTH ENGINEERING, INC.
STRUCTURAL CONSULTING ENGINEERS
PROOF ST MAN WORD IN. 18794
PROOF ST MAN ST 18794
GE JOB NO: 14192

9 4214 AVE AUSTIN, TX



ROOF FRAMING PLAN 1/8" = 1'-0"

PLAN NOTES:

2x8 RAFTERS @ 24"

HDR (E)

EXIST ROOF STRUCTL TO REMAIN

- 1. ALL WALLS ARE 2x4 @ 16" LOAD BEARING WALLS UNLESS NOTED OTHERWISE IN THIS PLAN. WALLS MARKED 2x6 ARE 2x6 @ 16" O.C.
- 2. BEAMS AND HEADERS SHALL BE SUPPORTED BY BUILT-UP COLUMNS & BLOCK SOLID TO FOUNDATION. SEE SCHEDULE IN THIS SHEET FOR BUILT-UP COLUMN SIZES.
- 3. 2x8 CEILING JOISTS @ 24" O.C. NOT SHOWN FOR CLARITY.

| BUILT-UP COLUMN SCHEDULE | | | |
|--------------------------|----------------------|--|--|
| BEAM SIZE | BUILT-UP STUD COLUMN | | |
| 2- 1 3/4"x14" LVL & UP | 4- STUD COLUMN | | |
| 2- 1 3/4"x12" LVL | 3- STUD COLUMN | | |
| 3- 2 x | 3- STUD COLUMN | | |
| 2- 2 x 12 | 3- STUD COLUMN | | |
| 2- 2 x 10 OR SMALLER | 2- STUD COLUMN | | |

| REV. | DATE |
|------|------|
| | |
| | |
| | |
| | |
| | |

CHK. BY: TZ DRWN. BY: TZ DATE: 12/21/2014

SHEET NO.

S3.2

OF



GREENEARTH ENGINEERING, INC.
STRUCTURAL CONSULTING ENGINEERS
SEOW WEST WILLIAM CANNON BG. 1521 ASTIN, IN 78745
PRIONE (22. 288—2006 FAX (512) 422—0800
GE. JOB NOI: 14192

9 Z Z 4214 AV

1 2 3 18'-11½" 27'-2" CS-WSP CS-WSP CS-WSP CS-WSP CS-WSP CS-WSP CS-WSP

1ST FLOOR WALL BRACING PLAN 1/8" = 1'-0"

| BRACE WALL LINE DATA | | | | |
|--|--------|-----------------------|-------------------------|-------------------------|
| BWL | STORY | BWL SPACING (FEET) | REQUIRED LENGTH (FT) | PROVIDED LENGTH (FT) |
| 1 | 1 OF 2 | 27 | 18 | 25 |
| 2 | 1 OF 2 | 27 | 9 | 12 |
| 3 | 1 OF 2 | 19 | 6.5 | 9+ |
| 4 | 1 OF 2 | 18 | 6.5 | 9+ |
| 5 | 1 OF 2 | 18 | 6.5 | 9+ |
| 9 | 1 OF 2 | 14 | 5 | 9+ |
| LECENDO, DIMI - DRACED WALL LINE, CO WCD - CONTINUOUS CHEATHED WOOD STOLICTURAL DANEL. | | | | |

ENDS: BWL = BRACED WALL LINE; CS-WSP = CONTINUOUS SHEATHED WOOD STRUCTURAL PANEL;
GB = GYPSUM BOARD; CS-PF = CONTINUOUS SHEATHED PORTAL FRAME.


- 1. BRACED WALL LINE DATA BASED ON SEISMIC DESIGN CATAGORY A AND A WIND SPEED OF 90 MPH OR LESS.
- 2. MAXIMUM BWL SPACING SHALL NOT EXCEED 60 FEET O.C.;
- 3. WOOD STRUCTURAL PANEL SHALL BE 1/2" OSB (OR PLYWOOD) SHEATHING AND SHALL BE FASTENED WITH 8d COMMON NAILS @ 6" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE FRAMING.
- 4. ALL HORIZONTAL PANEL SPLICES SHALL BE BLOCKED WITH BLOCKING EQUAL TO WALL STUD SIZE AND SHALL BE FASTENED WITH 8d COMMON NAILS @ 6" O.C.
- 5. THE FLOOR DECK SHALL BE 3/4" MIN OSB OR PLYWOOD DECK AND SHALL BE FASTENED WITH 8d COMMON NAILS. © 6" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE FRAMING.
- 6. THE ROOF DECK SHALL BE 5/8" MIN OSB OR PLYWOOD DECK AND SHALL BE FASTENED WITH 8d COMMON NAILS © 6" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE FRAMING.
- 7. GYBSUM BOARD SHALL BE 1/2" THICK AND SHALL BE FASTENED WITH 6d COMMON NAILS @ 6" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE FRAMING.

| REV. | DATE | |
|------|------|--|
| | | |
| | | |
| | | |
| _ | | |

| CHK. BY: TZ | |
|------------------|---|
| DRWN. BY: TZ | |
| DATE: 12/21/2014 | |
| | _ |

SHEET NO.

S3.3



GREENEARTH ENGINEERING INC.
STRUCTURAL CONSULTING ENGINEERS
STRUCTURAL CONSULTING ENGINEERS
STRUCTURAL CONSULTING ENGINEERS
FOOM (ST2) 462-4060
GE JOB NO: 14192

9 Z Z 4214 AV



| | 7 | | | 8 | |
|---------|-------------------|--------|---------|---------|---------------|
| | - | | 18'-4" | | |
| | | | | | |
| | | CS-WSP | | | |
| 9——— | | | CS-WS | | |
| | $\prod_{i=1}^{n}$ | | | | |
| | | | | | |
| | CS-WSP | | | SP SP | |
| | | | | CS-WSP | |
| | | | | 4 | |
| | | | | | |
| 5." | CS-WSP | | | | |
| 35'-2½" | Ś | | | | |
| | CS-WSP | | | | |
| | | | | | |
| | CS-WSP | | | CS-WSP | |
| | į) | _ | | | |
| | dS/+√S) | | | | |
| | | Н | | | |
| | SO | | | | |
| 10 | <u> </u> | CS-WSP | Tos-wsp | CS-W\$P | |
| | | C3-W3P | | | |
| | | | | | |
| | | | | I | <u> 2ND F</u> |

| BRACE WALL LINE DATA | | | | | | | |
|----------------------|--------|-----------------------|-------------------------|-------------------------|--|--|--|
| BWL | STORY | BWL SPACING (FEET) | REQUIRED LENGTH (FT) | PROVIDED LENGTH (FT) | | | |
| 7 | 2 OF 2 | 18 | 3.5 | 8+ | | | |
| 8 | 2 OF 2 | 18 | 3.5 | 8+ | | | |
| 9 | 2 OF 2 | 35 | 6 | 8+ | | | |
| 10 | 2 OF 2 | 35 | 6 | 6 | | | |
| | | | | | | | |
| | | | | | | | |

LEGENDS: BWL = BRACED WALL LINE; CS-WSP = CONTINUOUS SHEATHED WOOD STRUCTURAL PANEL;
GB = GYPSUM BOARD; CS-PF = CONTINUOUS SHEATHED PORTAL FRAME.

- 1. BRACED WALL LINE DATA BASED ON SEISMIC DESIGN CATAGORY A AND A WIND SPEED OF 90 MPH OR LESS.
- 2. MAXIMUM BWL SPACING SHALL NOT EXCEED 60 FEET O.C.;
- 3. WOOD STRUCTURAL PANEL SHALL BE 1/2" OSB (OR PLYWOOD) SHEATHING AND SHALL BE FASTENED WITH 8d COMMON NAILS @ 6" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE FRAMING.
- 4. ALL HORIZONTAL PANEL SPLICES SHALL BE BLOCKED WITH BLOCKING EQUAL TO WALL STUD SIZE AND SHALL BE FASTENED WITH 8d COMMON NAILS @ 6" O.C.
- 5. THE FLOOR DECK SHALL BE 3/4" MIN OSB OR PLYWOOD DECK AND SHALL BE FASTENED WITH 8d COMMON NAILS. @ 6" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE FRAMING.
- 6. THE ROOF DECK SHALL BE 5/8" MIN OSB OR PLYWOOD DECK AND SHALL BE FASTENED WITH 8d COMMON NAILS © 6" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE FRAMING.
- 7. GYBSUM BOARD SHALL BE 1/2" THICK AND SHALL BE FASTENED WITH 6d COMMON NAILS @ 6" O.C. AT PANEL EDGES AND 12" O.C. AT INTERMEDIATE FRAMING.

FLOOR WALL BRACING PLAN

CHK. BY: TZ DRWN. BY: TZ DATE: 12/21/2014

SHEET NO.

S3.4

OF

CHK. BY: TZ DRWN. BY: TZ DATE: 12/21/2014

SHEET NO

S4

STRUCTURAL GENERAL NOTES

CODES

- 1. Building Code: 2012 International Residential Code.
- Wood Framing: National Design Specifications For Wood Construction with Supplement, National Forest and Paper Products Association, Latest Edition.
- 3. Structural Plywood: Plywood Design Specification, American Plywood Association, Latest Edition.
- 4. Prefabricated Metal Plate Connected Wood Trusses: Design Standard for Metal Plate Connected Wood Truss Construction, ANSI/TPI Latest Edition.

DESIGN LOADS

- 1. Live Loads
- a. Roof b. Floor c. Stairs

TIMBER FRAMING


- Unless otherwise noted, all structural framing lumber shall be clearly marked no. 2 southern yellow pine or douglas fir, except that non-loadbearing interior walls may be stud grade southern yellow pine, douglas fir, or spruce-pine-fir.
- 2. All wood headers, beams, and top plates shall be no. 2 Southern Yellow Pine or Douglas Fir.
- All load bearing walls shall have solid 2x blocking at 4'-0" o.c. maximum vertically. End nail with 2-16d nails or side toe nail with 2-16d nails.
- 4. Provide double studs at all wall corners and on each side of all openings, unless noted or detailed otherwise.
- 5. The entire exterior wall framing shall be braced by a 4"-0" wide x 1/2" panel of APA rated sheathing with an exposure 1 rating extending from the top plate to the sill plate. Where wall is taller than 8"-0" provide multiple panels as required to extend from sill plate to top plate. Provide 2x blocking as required to support all panel edges. Nall with 8d common nails at 6" on center at supported edges and 12" on center at intermediate supports.
- Solid 2x blocking or bandboard shall be provided at supports and cantilever ends of all wood joists, and between supports in rows not exceeding 8'-0" apart.
- 7. All framing members framing into the side of a header, hip, valley, ridge, truss or any other beams shall be attached using metal joist hangers manufactured by the Simpson Company or equal. The hanger shall be sized and installed in accordance with the manufacturers recommendations for the size of joist supported.
- Nailing and attachment of all framing members and sheathing shall be as specified in the International Residential Code Nailing Schedule (Table 1862.3) unless noted otherwise in the drawings. Common wire noils or spikes, or galvanized box noils shall be used for all framing unless noted otherwise.
- 9. Place a single plate at the bottom and a double plate at the top of all stud walls. Exterior sill plates shall be baited to the foundation with 1/2" another bolts with a minimum embedment of 8" spaced at 4-0" on center. Provide a minimum of two bolts per plate segment. Sill plates in contact with concrete or masonry shall be pressure treated with a preservative.
- 10. Provide double joists under all interior partition walls oriented parallel to the joists.
- 11. Provide triple studs (or cripples) at each end of any header, beam, ridge, valley, or hip spanning over 10"-0" unless noted otherwise. Provide double studs (or cripples) at each end of any header, beam, ridge, valley, or hip spanning 5"-0" to 10"-0" unless noted otherwise.
- 12. The new generation of pressure treated lumber products are highly corrosive to metal connectors and fasteners. All fasteners and metal connectors used in conjunction with the new generation of pressure treated lumber shall be hot-dp galvanized or stainless steel. These locations include, but are not limited to the following:
- Anchor bolts at sole plate to foundation.
 Nails from sole plate to wall studs.
 Nails at exterior plywood sheathing to sole plate.
 Bolts at ledger to concrete.
 Joist to treated ledger connections.
 All hangers on treated joists.
 Wood posts to concrete.
 Deck board to treated joists.

PREFABRICATED METAL PLATE CONNECTED WOOD TRUSSES


- Trusses shall be designed by the Contractor in accordance with the Truss Plate Institute "Design Standard for Metal Plate Connected Wood Truss Construction" (ANSI/TPI 1-95).
- Truss members shall be clamped in a mechanical or hydraulic jig with sufficient pressure to bring members into reasonable contact at all joints during application of connector plates.
- 3. Provide adequate erection bracing in accordance with Truss Plate Institute publication HIB-91.
- Truss Manufacturer shall provide permanent bracing as required by the design of the trusses. Erection bracing may remain in place as permanent bracing where it does not interfere with the architectural finishes.
- All timber truss members shall be Southern Yellow Pine with a maximum moisture content of 19%. Chord members shall be no. 2 or better and web members shall be no. 3 or better.
- Connection plates shall be manufactured by a WTCA member plate manufacturer. Plates shall be 20 gauge minimum, ASTM A446 grade A steel, with a G60 galvanized coating.
- 7. Trusses shall be designed in accordance with the following requirements:
- a. Top chords shall be designed to resist the local bending induced by the floor or roof uniform load on the top chord.
- Limit live load deflection of floor trusses to L/480. Total load deflections shall be limited to L/360.

COMPOSITE WOOD MEMBERS


- Where noted on the drawings, joists shall be TJI "SP" series engineered wood joists, and beams shall be "Micro-Lam" or "Parallam" beams as manufactured by the Trus Joist Macmillan Corporation.
- Do not notch joists or beams. Drill holes through webs of engineered wood members for mechanical, electrical or plumbing services in accordance with the recommendations of the engineered wood product manufacturer.
- 3. Multiple wood beams up to three members thick shall be nailed together with three rows of 16d nails at 12" or who type wood became value of the three helicities and any multiple wood became sufficient by the first three helicities center. Four or more multiple wood became value of the three helicities of 44° shall be botted together with $1/2^{\circ}$ diameter botts four and bottom of a supports and ends of the beam, then at 24° on center, staggered top and bottom for the full leight of the beam.
- Where multiples of two 1 3/4" Micro-Lam beams are noted on the drawings, contractor may provide single 3 1/2" beams in lieu of double 1 3/4" beams.
- 5. Provide web stiffeners where required by the manufacturer for the specified support condition.












I-BEAM OVER HSS COL CONN TYPICAL DETAIL





4214 A1 AUSTIN,

OF