

ZONING CHANGE REVIEW SHEET

C3
/

CASE: C14-2015-0079 (The Bungalows)

Z.A.P. DATE: July 21, 2015

ADDRESS: 13311 Burnet Road

DISTRICT AREA: 7

OWNER/APPLICANT: Joe David Ross, Trustee

AGENT: Moncada Consulting (Phil Moncada)

ZONING FROM: GO

TO: GR

AREA: 1.22 acres

SUMMARY STAFF RECOMMENDATION:

The staff recommendation is to grant GR-CO, Community Commercial-Conditional Overlay District, zoning. The conditional overlay will limit the development intensity for the site to less than 2,000 vehicle trips per day.

ZONING AND PLATTING COMMISSION RECOMMENDATION:

DEPARTMENT COMMENTS:

The property in question is currently undeveloped. The applicant is requesting to rezone this site because they propose to develop a hotel on the property. The staff is recommending GR zoning for this site because the applicant's request meets the intent of the purpose statement for the GR, Community Commercial, zoning district. The property is adjacent to existing commercial (GR zoning to the south) and industrial (IP zoning to the east) zoning designations and will take access from a major arterial roadway, Burnet Road/FM 1325.

The applicant agrees with the staff recommendation.

EXISTING ZONING AND LAND USES:

| | ZONING | LAND USES |
|--------------|---------------------|------------------------------------------------------------|
| <i>Site</i> | GO | Undeveloped |
| <i>North</i> | MF-3-CO | Multifamily (Woods of Century Park) |
| <i>South</i> | GO, GR, LR, MF-3-CO | Undeveloped Tracts, Multifamily (Scofield Farm Apartments) |
| <i>East</i> | IP | Office (Grande Communications) |
| <i>West</i> | GR | Undeveloped |

AREA STUDY: North Lamar Area Study

TIA: Waived

WATERSHED: Walnut Creek

DESIRED DEVELOPMENT ZONE: Yes

CAPITOL VIEW CORRIDOR: N/A

HILL COUNTRY ROADWAY: N/A

C3/2

NEIGHBORHOOD ORGANIZATIONS:

Austin Heritage Tree Foundation
 Austin Independent School District
 Austin Northwest Association
 Bike Austin
 Friends of Austin Neighborhoods
 McNeil/Aston Woods Neighborhood Association
 North Growth Corridor Alliance
 SELTEXAS
 Sierra Club, Austin Regional Group
 The Real Estate Council of Austin, Inc.
 Wells Branch Neighborhood Association

CASE HISTORIES:

| NUMBER | REQUEST | COMMISSION | CITY COUNCIL |
|-------------------------------------------------------------------------------|------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------|
| C14-03-0188 (Cedar Elm-BWL: 13201-13205 Burnet Road) | GO to GR | 4/3/04: Approved staff's recommendation of GR zoning, by consent (9-0); J. Martinez-1 st , J. Gohil-2 nd . | 3/04/04: Granted GR zoning (6-0, McCracken-absent); all 3 readings |
| C14-00-2179 (Century Park: Century Park Boulevard) | IP to SF-2, SF-3, MF-1 | 10/17/00: Approved staff rec. of SF-2 (TR1), SF-3 (TR 2), and MF-1 (TR3) by consent (8-0) | 11/30/00: Approved SF-2-CO (TR1), SF-3-CO (TR2); MF-1-CO (TR3) w/condition of 2,000 vehicle trip per day limit (7-0); all 3 readings |
| C14-00-2112 (Century Park Apartments: 2700-2800 Century Park Boulevard) | IP to MF-3 | 9/19/00: Approved staff alternate rec. of MF-3-CO by consent (9-0); conditions as follows: 1) 2,000 vehicle trip per day limit 2) Maximum of 23 residential units per acre 3) A residential structure or portion of a residential structure may not be constructed within 100 ft of the north property line between Ida Ridge and Orchid Lane | 10/26/00: Approved MF-3-CO (7-0); 1 st reading 12/7/00: Approved MF-3-CO (7-0); 2 nd /3 rd readings |
| C14-95-0051 (Rainsoft: 13000 Ida Ridge) | GO to CS-CO | 5/23/95: Approved staff alternate rec. of CS-CO w/conditions (7-0) | 6/22/95: Approved CS-CO w/conditions (5-0); all 3 readings |
| C14-94-0056 (Scofield Farms: Scofield Lane) | LO, LR to MF-3 | 9/27/94: Approved MF-2-CO (TR1), MF-3-CO (TR2) w/ conditions (9-0) | 11/3/94: Approved MF-2-CO (TR1), MF-3-CO (TR2) w/conditions (5-0); all 3 readings |
| C14-92-0109 (Century | IP to MF-3 | 11/24/92: Approved MF-3 | 12/3/92: Approved MF-3-CO; with following conditions: |

3/3

| | | | |
|-------------------------------------------------------------------|------------|-------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Park Subdivision Block C: 3201 Century Park) | | | 1) Limit of 23 units per acre for multifamily development 2) Parkland dedication shall apply at site plan approval (6-0-1, RR-abstain); 1 st reading 4/7/94: Approved MF-3-CO (5-0-1, RR-abstain); 2 nd reading 4/21/94: Approved MF-3-CO (5-0-1, RR-abstain); 3 rd reading |
| C14-92-0108 (Century Park Subdivision Block B: 2701 Century Park) | IP to MF-3 | 11/24/92: Approved MF-3 | 12/3/92: Approved MF-3-CO; with following conditions: 1) Limit of 23 units per acre for multifamily development 2) Parkland dedication shall apply at site plan approval (6-0-1, RR-abstain); 1 st reading 4/7/94: Approved MF-3-CO (5-0-1, RR-abstain); 2 nd reading 4/21/94: Approved MF-3-CO (5-0-1, RR-abstain); 3 rd reading |

RELATED CASES: C14-85-149 (North Lamar Area Study Zonings)

ABUTTING STREETS:

| NAME | ROW | PAVEMENT | CLASSIFICATION | DAILY TRAFFIC |
|---------|--------|----------|----------------|---------------|
| FM 1325 | Varies | Varies | Major Arterial | N/A |

CITY COUNCIL DATE: August 13, 2015

ACTION:

ORDINANCE READINGS: 1st


2nd

3rd

ORDINANCE NUMBER:

CASE MANAGER: Sherri Sirwaitis




PHONE: 512-974-3057,
sherri.sirwaitis@austintexas.gov



ZONING

ZONING CASE#: C14-2015-0079





-  SUBJECT TRACT
-  PENDING CASE
-  ZONING BOUNDARY



This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries

This product has been produced by CTM for the sole purpose of geographic reference. No warranty is made by the City of Austin regarding specific accuracy or completeness

1" = 400'



3%

Map labels include street names: W HOWARD LN, ORCHID LN, DAISSY DR, GARDENIA DR, CENTURY PARK BLVD, ELM RIDGE LN, BURNET RD, MC NEIL DR, EL CAMINO RD, DEL ROBLES, SCOREFIELD RIDGE PKWY, ANACAPCO BLVD, LOU JOHN ST, ANACAPCO CV, WINWICK WAY, RODEO DR, SUMMIT DR, W HIGHLAND LN, IDA RIDGE DR, and CONCRETE PLANT. Lot numbers range from 48 to 90 along Daisy Dr and 11 to 43 along Lou John St. Zoning codes include MF-1-CO, MF-2-CO, MF-3-CO, SF-2-CO, SF-3-CO, SF-6-CO, IP, GR, LR, RR, PUD, UNDEV, OFFICE, GO, and CS-CO. A '3%' stamp is located on the right side of the map.



IDA RIDGE DR

CENTURY PARK BLVD

N MOPAC EXPY NB

N MOPAC EXPY SB

INGENIERO DR

EMERALD LN

WILLIAM KENNEDY DR

SF-2-CO

34-0184C

ANAKOS

3-3-CO

SCHEIDTDRIDGE PKWY

BURNET RD

BURNET RD

BURNET RD

C3
/7

STAFF RECOMMENDATION

The staff recommendation is to grant GR-CO, Community Commercial-Conditional Overlay District, zoning. The conditional overlay will limit the development intensity for the site to less than 2,000 vehicle trips per day.

BASIS FOR RECOMMENDATION

1. *The proposed zoning should be consistent with the purpose statement of the district sought.*

The Community Commercial (GR) district is the designation for an office or other commercial use that serves neighborhood and community needs and that generally is accessible from major traffic ways.

2. *The proposed zoning should promote consistency, and orderly planning.*

The site under consideration is adjacent to an existing GR (Community Commercial District) zoning to the south. There is IP (Industrial Park District) zoning located to the east of the subject tract.

3. *The proposed zoning should allow for a reasonable use of the property.*

The GR zoning district would allow for a fair and reasonable use of the site because it will permit this site to be developed with commercial uses along a major arterial roadway.

EXISTING CONDITIONS

Site Characteristics

The property in question is an undeveloped tract of land. The site is relatively flat and has a grassy terrain with clusters of trees. The property fronts onto Burnett Road/ FM 1325, a major arterial roadway. The tract of land to the north of this site is developed with a multifamily use (Woods of Century Park). There is an industrial use to the east (Grande Communications). The properties to the south of this site are zoned commercial (GR, LR) and are currently undeveloped.

Comprehensive Planning

GO to GR

This zoning case is located on the southeast corner of Burnet Road and Grand Boulevard, on an undeveloped parcel that is approximately 1.22 acres in size. This property not located within the boundaries of a planning area with an adopted neighborhood plan. Surrounding land uses includes a two story apartment complex to the north, a deteriorating barn to the south, the highly travelled Burnet Road and the Mopac frontage road, which run parallel to each other to the west, and a large office park to the east. The proposed use is a hotel.

Imagine Austin

The Imagine Austin Growth Concept Map, found in the Imagine Austin Comprehensive Plan (IACP) identifies this project as being located just outside the boundaries of a **Neighborhood Center**, which is located to the north. The IACP defines Neighborhood Centers as *“the smallest and least intense of the three types of activity centers outlined in the Growth Concept Map. Of the three, these will have a*

C3/4

more local focus. Businesses and services—doctors and dentists, shops, branch libraries, dry cleaners, hair salons, coffee shops, restaurants, and other small and local businesses—will generally serve the center and surrounding neighborhoods.” However, based on the comparative scale of this site when compared to surrounding commercial and office uses, this case falls below the scope of Imagine Austin, which is broad in scope, and consequently the plan is neutral on this proposed rezoning.

Environmental

The site is located over the Edwards Aquifer Recharge Zone. The site is in the Walnut Creek Watershed of the Colorado River Basin, which is classified as a Suburban Watershed by Chapter 25-8 of the City's Land Development Code. The site is in the Desired Development Zone.

According to floodplain maps there is a floodplain within or adjacent to the project location. Based upon the location of the floodplain, offsite drainage should be calculated to determine whether a Critical Water Quality Zone exists within the project location.

Standard landscaping and tree protection will be required in accordance with LDC 25-2 and 25-8 for all development and/or redevelopment.

Trees will likely be impacted with a proposed development associated with this rezoning case. Please be aware that an approved rezoning status does not eliminate a proposed development’s requirements to meet the intent of the tree ordinances. If further explanation or specificity is needed, please contact the City Arborist at 512-974-1876. At this time, site specific information is unavailable regarding other vegetation, areas of steep slope, or other environmental features such as bluffs, springs, canyon rimrock, caves, sinkholes, and wetlands.

Under current watershed regulations, development or redevelopment requires water quality control with increased capture volume and control of the 2 year storm on site.

At this time, no information has been provided as to whether this property has any preexisting approvals that preempt current water quality or Code requirements.

Impervious Cover

The maximum impervious cover allowed by the GR zoning district would be 90 %. However, because the Watershed impervious cover is more restrictive than the zoning district’s allowable impervious cover, the impervious cover on this site would be limited by the watershed ordinance.

Under current watershed regulations, development or redevelopment on this site will be subject to the following impervious cover limits:

| <i>Development Classification</i> | <i>% of Gross Site Area</i> | <i>% of Gross Site Area with Transfers</i> |
|--------------------------------------------------|-----------------------------|--------------------------------------------|
| Single-Family (minimum lot size 5750 sq. ft.) | 50% | 60% |
| Other Single-Family or Duplex | 55% | 60% |
| Multifamily | 60% | 70% |
| Commercial | 80% | 90% |

C3/a

Note: The most restrictive impervious cover limit applies.

Site Plan

Any new development is subject to Subchapter E. Design Standards and Mixed Use. Additional comments will be made when the site plan is submitted.

Stormwater Detention

At the time a final subdivision plat, subdivision construction plans, or site plan is submitted, the developer must demonstrate that the proposed development will not result in additional identifiable flooding of other property. Any increase in storm water runoff will be mitigated through on-site storm water detention ponds, or participation in the City of Austin Regional Stormwater Management Program, if available.

Transportation

A traffic impact analysis was waived for this case because the applicant agreed to limit the intensity and uses for this development. If the zoning is granted, development should be limited through a conditional overlay to less than 2,000 vehicle trips per day. [LDC, 25-6-117]

Nadia Barrera, Urban Trails, Public Works Department and Nathan Wilkes, Bicycle Program, Austin Transportation Department may provide additional comments regarding bicycle and pedestrian connectivity per the Council Resolution No. 20130620-056.

According to the Austin 2009 Bicycle Plan Update approved by Austin City Council in June, 2009, a wide curb is recommended along Burnet Road.

If the requested zoning is granted, it is recommended that joint use access be provided between the proposed lot and the lot to the north through the existing Driveway (Grand Boulevard) in accordance with our Complete Streets Policy Ordinance #20140612-119. The existing curb cut should be removed.

Existing Street Characteristics:

| Name | ROW | Pavement | Classification | Sidewalks | Bike Route | Capital Metro (within ¼ mile) |
|--------------------------|---------|----------|----------------|-----------|--------------------------------|-------------------------------|
| Loop 1 (Mopac Boulevard) | 470 ft. | <425 ft. | Arterial | Yes | Yes, Shared Lane, Route 434.01 | No |

Water and Wastewater

The landowner intends to serve the site with City of Austin water and wastewater utilities. The landowner, at own expense, will be responsible for providing any water and wastewater utility improvements, offsite main extensions, utility relocations and or abandonments required by the land use. The water and wastewater utility plan must be reviewed and approved by the Austin Water Utility for compliance with City criteria and suitability for operation and maintenance. Depending on the development plans submitted, water and or wastewater service extension requests may be

required. All water and wastewater construction must be inspected by the City of Austin. The landowner must pay the City inspection fee with the utility construction. The landowner must pay the tap and impact fee once the landowner makes an application for a City of Austin water and wastewater utility tap permit.

C3
/10