
A.R. Davis Treated Water Discharge and Power Distribution Upgrade

Water and Wastewater Commission September 9, 2015



Facility Engineering – Water Project Sponsor : Christopher Wolter




Presentation Topics


- Location Map
- Existing Layout and Process Flow
- Asset Management Methodology
- Proposed Improvements Layout & Overview
- Austin Energy Power Supply Project Overview
- Neighborhood Coordination
- Schedule & Cost
- Questions




Davis WTP Location Map







Austin Water Asset Management Methodology





Medium Service Pump Station

- Medium Service Pump Station (MSPS) original construction in 1953
- Equipment/piping more than 60 years old
- Motor controls and electrical equipment are obsolete
- Building is very confined and difficult or inaccessible to maintain







Medium Service Pump Station

- Pipe or valve failure could fail, resulting in the MSPS being out of service for an extended period of time
- Recent leak is evidence of potential for similar failure throughout the facility. This lead was very difficult to isolate and required a full shutdown of the MSPS to repair
- Valves and piping are inaccessible for replacement or maintenance







Power Distribution System

- Electrical substation constructed in 1965 (equipment 30 to 50 years old)
- The overhead bus system has failed and could fail again, shutting the entire plant down for an extended period of time
- Electrical equipment has safety concerns due to age and condition





Power Distribution System

- Cables are aging (many are original installation/60yrs old)
- Current power distribution system has single power feeds and transformers in critical areas of the plant. Failure in this non-redundant system would shutdown critical process areas









Criticality

MSPS & Power Distribution System

A. R. Davis WTP has provided continuous and reliable water treatment to the distribution for the past 60 years

- Retail and Wholesale customers = 977,491
- Service Area = 544 square miles
- Service Connections = 224,000
- Distribution = 3,801 Miles
- Fire Hydrants = 27,328
- Pump Stations/Local Boosters= 40
- Reservoirs = 40
- Major Water Treatment Plants = 3 (WTP4, Ullrich & Davis WTP)



Redundancy


MSPS & Power Distribution System

- The new MSPS will replace an existing, outdated pump station built in 1953, in order to continue to provide reliable, uninterrupted service to the residents of Austin
- The plant provides redundancy for maintenance issues and emergencies for the water system
- Difficult to maintain/most components are now obsolete and no longer manufactured. Repair parts have to be custom engineered/manufactured
- Not designed with isolation for maintenance. Austin Energy has to cut power to main circuits. Plant cannot internally re-route power during maintenance/emergencies



Business Needs


MSPS & Power Distribution System





Architectural Rendering

Proposed View From West 35th Street





Austin Energy's Power Supply

Existing Power Supply:

- AE Lakeshore feed power cables approx. 25 yrs. old. Originally 4 cables. One completely failed 10 years ago and three remain, but we experienced 2 cable failures last year
- Overhead neighborhood feed has more exposure than underground and is shared with neighbors/capacity not dedicated to plant

Proposed Power Supply:

- Install new transformer at Warren Substation.
- Install two underground cables from Warren Substation to Davis Water Treatment Plant



Neighborhood Coordination

March 2012 Design Meeting

May 2015 Austin Energy 35th Street & Davis WTP Projects

August 2015 Austin Energy 35th Street (2nd Meeting)

Sept 2015 Austin Energy 35th Street (Upcoming)



Project Schedule & Cost

Task Name ▼	Start Month 🔻	Finish Month 🔻	2015	2016	2017	2018	2019	2020
□ Combined Project Timeline	October 2015	June 2016						
■ MSPS Bid/Award/Execution Phase	October 2015	March 2016						
⊞ MSPS Construction Phase	March 2016	July 2019		-				
⊕ PDU Bid/Award/Execution Phase	January 2016	June 2016		——				
⊕ PDU Construction Phase	June 2016	June 2020		V				
			-			8 8 8 8 8		

PROJECT	ENGINEER ESTIMATE		
Davis Medium Service Pump Station	\$32 MM		
Davis Power Distribution Upgrade	\$22 MM		
TOTAL	\$56 MM		



Questions



