



**Recommendation for  
Water & Wastewater Commission**

<b>Commission Meeting Date:</b>	November 9, 2016
<b>Council Meeting Date:</b>	December 1, 2016
<b>Department:</b>	Public Works
<b>SUBJECT</b>	
Authorize execution of a construction contract with <b>INSITUFORM TECHNOLOGIES, LLC</b> , for Wastewater Collection System Rehabilitation of Lines – Group A in the amount of \$981,400 plus a \$98,140 contingency, for a total contract amount not to exceed \$1,079,540. (Districts 1, 3, 4, 8, 9, and 10)	
<b>AMOUNT AND SOURCE OF FUNDING</b>	
Funding is available in the Fiscal Year 2016-2017 Capital Budget of Austin Water.	
<b>Purchasing Language:</b>	Lowest responsive bid of two received through competitive Invitation for Bid solicitation.
<b>Prior Council Action:</b>	N/A
<b>For More Information:</b>	Darryl Haba, 512-974-7205; Michael Russ, 512-972-2054; Rolando Fernandez, 512-974-7749; Sarah Torchin, 512-974-7141; Denise Avery, 512-972-0104; Lucy Thompson, 512-974-7967
<b>Boards and Commission Action:</b>	November 9, 2016- To be reviewed by the Water and Wastewater Commission.
<b>MBE/WBE:</b>	This contract will be awarded in compliance with City Code Chapter 2-9A of the City Code (Minority Owned and Women Owned Business Enterprise Procurement Program) by meeting the goals or through the achievements of Good Faith Efforts with 5.20% MBE and 6.44% WBE subcontractor participation.

As part of the Wastewater Collection System, this project will rehabilitate approximately 15,000 linear feet of deteriorated wastewater pipe within several basins which include Upper Fort, Johnson, Lower Boggy, Town Lake, East Bouldin, Upper and Lower Shoal, and Lower Waller. The pipelines identified as part of this project were based on a ranking system of deteriorated pipes requiring action prior to failure.

Cured in Place Pipe (CIPP) method will be employed to rehabilitate the pipelines. This trenchless method will allow for the repair of the pipelines at roughly one third the cost of a traditional open cut methods and will also dramatically lessen the impact to the area residents, normal users of the impacted roadways, and Citizens of Austin.

The work within this project will be located at 61 sites throughout various parts of Austin.

This is a time sensitive project as these 61 locations were ranked as high in need of rehabilitation prior to failure. Delaying execution of the Contract could result in failure of these deteriorated wastewater collection system pipes.

Due to the potential for underground hidden conditions while inspecting the pipelines, a 10% contingency in funding has been included to allow for the expeditious processing of any change orders. A contingency is an additional amount of money added to the construction budget to cover any unforeseen construction costs associated with the project.

The contract allows 180 working days for completion of this project. This project is located throughout the City of Austin at sixty one locations within zip codes 78701, 78702, 78703, 78704, 78705, 78712, 78723, 78741, 78746, 78751, 78752, 78756, 78757, 78758, 78759 which span across Districts 1, 3, 4, 8, 9, and 10. The project will be managed by Public Works Project Management Division.

Insituform Technologies, LLC is located in San Marcos, Texas.

### **M/WBE Summary – Construction Contract w/contingency**

Public notice was given for this solicitation, CLMC617 Wastewater Collection System Rehabilitation of Lines – Group A, through the City's Vendor Connection web portal which resulted in 480 contractors receiving notification. Ten contractors obtained the bid documents and two bids were received and opened on September 8, 2016. One out of two bids received were certified MBE/WBE. Insituform Technologies, LLC submitted the lowest responsive bid of 2 bids received:

Insituform Technologies, LLC, San Marcos, Texas	\$981,400
Fuquay, Inc., (WBE/FW), New Braunfels, Texas	\$2,120,111

The contractor's choice of work methodology provides for 3 areas of subcontracting opportunities which are listed below. Participation goals stated in the solicitation were 5.19% MBE; 1.16% WBE. Total participation estimated on base bid amount of \$981,400:

<b>NON M/WBE – PRIME</b>	<b>\$867,150</b>	<b>88.36%</b>
Insituform Technologies, LLC, San Marcos, Texas	\$867,150	88.36%
<b>MBE TOTAL – SUBCONTRACTORS</b>	<b>\$51,000</b>	<b>5.20%</b>

<b>Hispanic Subtotal</b>	<b>\$51,000</b>	<b>5.20%</b>
(M/H) Briones Consulting and Engineering, LTD, San Antonio, Texas (Traffic controls)	\$51,000	5.20%

<b>WBE TOTAL – SUBCONTRACTORS</b>	<b>\$63,250</b>	<b>6.44%</b>
(F/W) Stephanie Braun Clayton, LLC, Austin, Texas, ST (Construction Photography)	\$11,250	1.14%
(F/W) DFW Infrastructure, Inc., Fort Worth, Texas (Pipe cleaning and inspection)	\$52,000	5.30%

The Contractor submitted a MBE/WBE Compliance Plan that met the goals of the solicitation and was approved by the Small & Minority Business Resources Department. Second and third low bidder information is provided.

SECOND BIDDER - Fuquay, Inc., (WBE/FW), New Braunfels, Texas      \$2,120,111  
93.45% WBE prime participation; 5.25% MBE; 1.30% WBE.

# CERTIFIED BID TAB

**CITY OF AUSTIN**      PROJECT SPONSOR: AUSTIN WATER      BID OPENING DATE: 9/8/2016  
 BID CERTIFICATION & CONTRACT REP: MONICA LOPEZ      TIME: 2:00 PM  
 PROJECT MANAGER: DARRYL HABA      LOCATION: 505 BARTON SPRINGS RD.  
 PROJECT CONSULTANTS: ENGINEERING SVCS      SUITE 1045C      PRICE EXPIRATION: 90 CAL. DAYS  
 DURATION: 180 WORKING DAYS      LIQUIDATED DAMAGES: \$1,740 P/WRK. DAY

**PROJECT:** WASTEWATER COLLECTION SYSTEM REHABILITATION OF LINES-GROUP A      SUB ID# 2231.264  
**BID INVITATION NO:** CLMC617      RESPONSES: 2  
**PROJECT NUMBER(S):** 4570 2307 4759      ESTIMATE: \$1,399,068.00

<b>BIDDER(S):</b>	INSITUFORM TECHNOLOGIES, LLC	FUQUAY, INC.
<b>LOCATION:</b>	CHESTERFIELD, MI	NEW BRAUNFELS, TX
<b>GUARANTEE:</b> BB-Bid Bond    CC-Cashiers Check    CTC-Cert. Chk.	BB	BB
<b>ADDENDA ACKNOWLEDGED</b>	1	1

BID ITEM	QTY	UNIT	ITEM DESCRIPTION	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SS5101-1	1	LS	LOCATION 1: CURED-IN-PLACE PIPE LINING, 175 LF OF 10-INCH DIA. MAIN FROM MH 27104 TO MH 230084, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9 AND ALLEY CLOSURE DETAIL, COMPLETE AND IN PLACE.	\$ 8,300.00	\$ 8,300.00	\$ 57,779.00	\$ 57,779.00	\$	\$
SS5101-2	1	LS	LOCATION 2: CURED-IN-PLACE PIPE LINING, 35 LF OF 8-INCH DIA. MAIN FROM MH 31447 TO MH 31445, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 4,700.00	\$ 4,700.00	\$ 17,046.00	\$ 17,046.00	\$	\$
SS5101-3	1	LS	LOCATION 3: CURED-IN-PLACE PIPE LINING, 491 LF OF 6 INCH DIA. MAIN FROM MH 31663 TO MH 31662, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 AND 6 OF 9; COMPLETE IN PLACE.	\$ 23,100.00	\$ 23,100.00	\$ 49,029.00	\$ 49,029.00	\$	\$

# CERTIFIED BID TAB

BIDDER(S):		INSITUFORM TECHNOLOGIES, LLC				FUQUAY, INC.	
SS5101-4	1	LS	LOCATION 4: CURED-IN-PLACE PIPE LINING, 376 LF OF 8-INCH DIA. MAIN FROM MH 31525 TO MH 31506, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 11,800.00	\$ 11,800.00	\$ 34,743.00	\$ 34,743.00
SS5101-8	1	LS	LOCATION 8: CURED-IN-PLACE PIPE LINING, 599 LF OF 8-INCH DIA. MAIN FROM MH 49667 TO MH 238114, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9 AND SPFT-E; COMPLETE AND IN PLACE.	\$ 25,100.00	\$ 25,100.00	\$ 54,083.00	\$ 54,083.00
SS5101-9	1	LS	LOCATION 9: CURED-IN-PLACE PIPE LINING, 390 LF OF 6-INCH DIA. MAIN FROM MH 32565 TO MH 32564, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS SPFT-E; COMPLETE AND IN PLACE.	\$ 19,500.00	\$ 19,500.00	\$ 56,244.00	\$ 56,244.00
SS5101-10	1	LS	LOCATION 10: CURED-IN-PLACE PIPE LINING, 190 LF OF 6-INCH DIA. MAIN FROM MH 50537 TO MH 49493, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 2 OF 9; COMPLETE AND IN PLACE.	\$ 13,700.00	\$ 13,700.00	\$ 28,509.00	\$ 28,509.00
SS5101-11	1	LS	LOCATION 11: CURED-IN-PLACE PIPE LINING, 259 LF OF 24-INCH DIA. MAIN FROM MH 255399 TO MH 50901, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 82,000.00	\$ 82,000.00	\$ 90,006.00	\$ 90,006.00
SS5101-12	1	LS	LOCATION 12: CURED-IN-PLACE PIPE LINING, 259 LF OF 8-INCH DIA. MAIN FROM THE MH 49363 TO MH 49338, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 10,000.00	\$ 10,000.00	\$ 36,403.00	\$ 36,403.00
SS5101-13	1	LS	LOCATION 13: CURED-IN-PLACE PIPE LINING, 526 LF OF 8-INCH DIA. MAIN FROM NH 46244 TO MH 214713, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 18,700.00	\$ 18,700.00	\$ 101,806.00	\$ 101,806.00
SS5101-14	1	LS	LOCATION 14: CURED-IN-PLACE PIPE LINING, 366 LF OF 8-INCH DIA. MAIN FROM MH 74251 TO MH 74250, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 11,500.00	\$ 11,500.00	\$ 53,700.00	\$ 53,700.00

# CERTIFIED BID TAB

BIDDER(S):		INSITUFORM TECHNOLOGIES, LLC		FUGUAY, INC.		
SS5101-15	1	LS	LOCATION 15: CURED-IN-PLACE PIPE LINING, 1671 LF OF 8-INCH DIA. MAIN FROM MH 75016 TO MH 75005. INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, COMPLETE AND IN PLACE.	\$ 58,400.00	\$ 126,821.00	\$ 126,821.00
SS5101-16	1	LS	LOCATION 16: CURED-IN-PLACE PIPE LINING, 551 LF OF 8-INCH DIA. MAIN FROM MH 74388 TO MH 74387, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, COMPLETE AND IN PLACE.	\$ 15,300.00	\$ 69,908.00	\$ 69,908.00
SS5101-17	1	LS	LOCATION 17: CURED-IN-PLACE PIPE LINING, 478 LF OF 8-INCH DIA. MAIN FROM MH 64472 TO MH 64267, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, COMPLETE AND IN PLACE.	\$ 13,800.00	\$ 46,372.00	\$ 46,372.00
SS5101-18	1	LS	LOCATION 18: CURED-IN-PLACE PIPE LINING, 308 LF OF 8-INCH DIA. MAIN FROM MH 64548 TO MH 64547, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, COMPLETE AND IN PLACE.	\$ 10,200.00	\$ 34,055.00	\$ 34,055.00
SS5101-19	1	LS	LOCATION 19: CURED-IN-PLACE PIPE LINING, 316 LF OF 8-INCH DIA. MAIN FROM MH 74068 TO MH 73579, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS SPTF-A, COMPLETE AND IN PLACE.	\$ 17,700.00	\$ 34,534.00	\$ 34,534.00
SS5101-20	1	LS	LOCATION 20: CURED-IN-PLACE PIPE LINING, 214 LF OF 8-INCH DIA. MAIN FROM MH 75640 TO MH 75639, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, COMPLETE AND IN PLACE.	\$ 8,300.00	\$ 40,794.00	\$ 40,794.00
SS5101-21	1	LS	LOCATION 21: CURED-IN-PLACE PIPE LINING, 771 LF OF 8-INCH DIA. MAIN FROM MH 75048 TO MH 75044, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, COMPLETE AND IN PLACE.	\$ 23,800.00	\$ 84,627.00	\$ 84,627.00
SS5101-23	1	LS	LOCATION 23: CURED-IN-PLACE PIPE LINING, 166 LF OF 8-INCH DIA. MAIN FROM MH 230646 TO MH 74260, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, COMPLETE AND IN PLACE.	\$ 7,700.00	\$ 23,448.00	\$ 23,448.00

# CERTIFIED BID TAB

BIDDER(S):		INSITUFORM TECHNOLOGIES, LLC		FUQUAY, INC.		
SS5101-24	1	LS	LOCATION 24: CURED-IN-PLACE PIPE LINING, 637 LF OF 8-INCH DIA. MAIN FROM MH 74352 TO MH 74351. INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, SPFT-E, COMPLETE AND IN PLACE.	\$ 39,600.00	\$ 54,364.00	\$ -
SS5101-25	1	LS	LOCATION 25: CURED-IN-PLACE PIPE LINING, 84 LF OF 8 INCH DIA. MAIN FROM MH 74395 TO MH 74394. INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, SPFT-F, COMPLETE AND IN PLACE.	\$ 14,800.00	\$ 18,895.00	\$ -
SS5101-26	1	LS	LOCATION 26: CURED-IN-PLACE PIPE LINING, 582 LF OF 8-INCH DIA. MAIN FROM MH 74401 TO MH 74403. INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, SPFT-F, COMPLETE AND IN PLACE.	\$ 38,400.00	\$ 50,405.00	\$ -
SS5101-27	1	LS	LOCATION 27: CURED-IN-PLACE PIPE LINING, 544 LF OF 8-INCH DIA. MAIN FROM MH 74416 TO MH 74415. INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, SPFT-E, COMPLETE AND IN PLACE.	\$ 24,800.00	\$ 57,135.00	\$ -
SS5101-28	1	LS	LOCATION 28: CURED-IN-PLACE PIPE LINING, 219 LF OF 8-INCH DIA. MAIN FROM MH 35967 TO MH 37305. INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, COMPLETE AND IN PLACE.	\$ 8,500.00	\$ 24,560.00	\$ -
SS5101-29	1	LS	LOCATION 29: CURED-IN-PLACE PIPE LINING, 905 LF OF 8-INCH DIA. MAIN FROM MH 55377 TO MH 55676. INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, COMPLETE AND IN PLACE.	\$ 34,000.00	\$ 71,092.00	\$ -
SS5101-30	1	LS	LOCATION 30: CURED-IN-PLACE PIPE LINING, 497 LF OF 8-INCH DIA. MAIN FROM MH 55293 TO MH 55670. INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, COMPLETE AND IN PLACE.	\$ 14,300.00	\$ 42,124.00	\$ -
SS5101-31	1	LS	LOCATION 31: CURED-IN-PLACE PIPE LINING, 178 LF OF 8-INCH DIA. MAIN FROM MH 56188 TO MH 56184. INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, SPFT-C, COMPLETE AND IN PLACE.	\$ 7,500.00	\$ 20,509.00	\$ -

# CERTIFIED BID TAB

BIDDER(S):				INSITUFORM TECHNOLOGIES, LLC		FUQUAY, INC.			
SS5101-32	1	LS	LOCATION 32: CURED-IN-PLACE PIPE LINING, 314 LF OF 8-INCH DIA. MAIN FROM MH 55699 TO MH 54611, INCLUDING BYPASS PUMPING, TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9, SPFT-A OR B; COMPLETE AND IN PLACE.	\$ 21,400.00	\$ 21,400.00	\$ 29,114.00	\$ 29,114.00	\$	\$
SS5101-33	1	LS	LOCATION 33: CURED-IN-PLACE PIPE LINING, 257 LF OF 8-INCH DIA. MAIN FROM MH 53634 TO MH 54465, INCLUDING TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 7 OF 9; COMPLETE AND IN PLACE.	\$ 34,400.00	\$ 34,400.00	\$ 34,336.00	\$ 34,336.00	\$	\$
SS5101-34	1	LS	LOCATION 34: CURED-IN-PLACE PIPE LINING, 570 LF OF 8-INCH DIA. MAIN FROM MH 39363 TO MH 40165, INCLUDING TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAILS 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 15,600.00	\$ 15,600.00	\$ 48,885.00	\$ 48,885.00	\$	\$
SS5101-38	1	LS	LOCATION 38: CURED-IN-PLACE PIPE LINING, 108 LF OF 8-INCH DIA. MAIN FROM MH 17327 TO JUNCTION BOX 209638; INCLUDING BYPASS PUMPING/HAULING PLAN, AND TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9; COMPLETE AND IN PLACE. BYPASS PUMPING THROUGH THE CREEK WILL NOT BE ALLOWED.	\$ 6,300.00	\$ 6,300.00	\$ 17,693.00	\$ 17,693.00	\$	\$
SS5101-40	1	LS	LOCATION 40: CURED-IN-PLACE PIPE LINING, 52 LF OF 8-INCH DIA. MAIN FROM MH 20090 TO MH 20091, INCLUDING BYPASS PUMPING, AND TEMPORARY TRAFFIC CONTROL FOR CUL-DE-SAC CLOSURE; COMPLETE AND IN PLACE.	\$ 5,200.00	\$ 5,200.00	\$ 18,116.00	\$ 18,116.00	\$	\$
SS5101-46	1	LS	LOCATION 46: CURED-IN-PLACE PIPE LINING, 814 LF OF 8-INCH DIA. MAIN FROM MH(CO 64500) TO MH 137159, INCLUDING TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 25,800.00	\$ 25,800.00	\$ 92,635.00	\$ 92,635.00	\$	\$
SS5101-47	1	LS	LOCATION 47: CURED-IN-PLACE PIPE LINING, 111 LF OF 8-INCH DIA. MAIN FROM MH(CO 64626) TO MH 64828, INCLUDING TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 6,200.00	\$ 6,200.00	\$ 19,136.00	\$ 19,136.00	\$	\$
SS5101-48	1	LS	LOCATION 48: CURED-IN-PLACE PIPE LINING, 417 LF OF 8-INCH DIA. MAIN FROM MH(CO64631) TO MH 64622, INCLUDING TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 12,600.00	\$ 12,600.00	\$ 39,736.00	\$ 39,736.00	\$	\$



# CERTIFIED BID TAB

BIDDER(S):		INSITUFORM TECHNOLOGIES, LLC		FUQUAY, INC.		
SS5101-49	1	LS	LOCATION 49: CURED-IN-PLACE PIPE LINING, 981 LF OF 8-INCH DIA. MAIN FROM MH 64338 TO MH 123987. INCLUDING TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 37,000.00	\$ 84,482.00	\$
SS5101-50	1	LS	LOCATION 50: CURED-IN-PLACE PIPE LINING, 313 LF OF 8-INCH DIA. MAIN FROM MH 54052 TO MH 54051. INCLUDING TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9, AND COA SPECIAL DETAIL SPFT-E; COMPLETE AND IN PLACE.	\$ 18,000.00	\$ 33,795.00	\$
SS5101-51	1	LS	LOCATION 51: CURED-IN-PLACE PIPE LINING, 160 LF OF 8-INCH DIA. MAIN FROM MH 54055 TO MH 54047. INCLUDING BYPASS PUMPING, AND TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9, AND COPA SPECIAL DETAIL SPFT-E; COMPLETE AND IN PLACE.	\$ 15,000.00	\$ 20,758.00	\$
SS5101-54	1	LS	LOCATION 54: CURED-IN-PLACE PIPE LINING, 330 LF OF 8-INCH DIA. MAIN FROM MH 91884 TO MH 65890. INCLUDING BYPASS PUMPING, AND TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9, AND COA SPECIAL DETAIL SPFT-A AND SPFT-B; COMPLETE AND IN PLACE.	\$ 18,100.00	\$ 31,343.00	\$
SS5101-55	1	LS	LOCATION 55: CURED-IN-PLACE PIPE LINING, 901 LF OF 8-INCH DIA. MAIN FROM MH 65835 TO MH245468. INCLUDING BYPASS PUMPING, AND TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9, AND 804S-1, 7 OF 9; COMPLETE AND IN PLACE.	\$ 63,700.00	\$ 88,546.00	\$
SS5101-56	1	LS	LOCATION 56: CURED-IN-PLACE PIPE LINING, 421 LF OF 8-INCH DIA. MAIN FROM MH 65861 TO MH 24574. AND 957 LF OF 8-INCH DIA. MAIN FROM MH 66727 TO MH 24571. INCLUDING BYPASS PUMPING, AND TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9 AND COA SPECIAL DETAIL SPFT-F; COMPLETE AND IN PLACE.	\$ 74,000.00	\$ 45,491.00	\$
SS5101-57	1	LS	LOCATION 57: CURED-IN-PLACE PIPE LINING, 513 LF OF 8-INCH DIA. MAIN FROM MH (CO 54935) TO MH 245497. INCLUDING BYPASS PUMPING AND TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 15,400.00	\$ 44,307.00	\$

# CERTIFIED BID TAB

BIDDER(S):		INSITUFORM TECHNOLOGIES, LLC		FUQUAY, INC.	
SS5101-58	1	LS	LOCATION 58: CURED-IN-PLACE PIPE LINING, 204 LF OF 8-INCH DIA. MAIN FROM MH (CO 51915) TO MH 251205, INCLUDING TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9 AND COA SPECIAL DETAIL SPFT-B; COMPLETE AND IN PLACE.	\$ 15,300.00	\$ 26,226.00
SS5101-60	1	LS	LOCATION 60: CURED-IN-PLACE PIPE LINING, 334 LF OF 6-INCH DIA. MAIN FROM MH 47688 TO MH 47687, INCLUDING BYPASS PUMPING AND TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9 AND COA SPECIAL DETAIL FOR ALLEY CLOSURE; COMPLETE AND IN PLACE.	\$ 22,900.00	\$ 41,008.00
SS5101-61	1	LS	LOCATION 61: CURED-IN-PLACE PIPE LINING, 221 LF OF 8-INCH DIA. MAIN FROM MH 89192 TO MH 89245, INCLUDING BYPASS PUMPING AND TEMPORARY TRAFFIC CONTROL PER COA STANDARD DETAIL 804S-1, 5 OF 9; COMPLETE AND IN PLACE.	\$ 9,000.00	\$ 25,513.00
<b>TOTAL BID:</b>				\$ 981,400.00	\$ 2,120,111.00

TRUE COPY OF BID TABULATION AS RECEIVED OR CORRECTED IN ACCORDANCE WITH CONDITIONS GOVERNING PROPOSALS.

 \_\_\_\_\_ 10/06/16

CAPITAL CONTRACTING OFFICE  
 CONTRACT PROCUREMENT DIVISION  
 CITY OF AUSTIN, TX