

## **ZONING CHANGE REVIEW SHEET**

**H.L.C. DATE:** February 26, 2018

**P.C. DATE:** February 27, 2018

**CASE:** C14-01-0046.02 (originally filed as C14-2017-0153) – The Baker School

**ADDRESS:** 3908 Avenue B, Austin, TX, 78751

**DISTRICT AREA:** 9

**OWNER/APPLICANT:** Austin Independent School District

**AGENT:** Weiss Architecture, Inc. (Richard Weiss)

**ZONING FROM:** UNZ (Unzoned) **TO:** CS-HD-NCCD-NP

**TOTAL AREA:** 4.361 acres

### **SUMMARY STAFF RECOMMENDATION:**

Staff recommends community commercial-historic district-neighborhood conservation combining district-neighborhood plan (GR-HD-NCCD-NP) combining district zoning.

### **HISTORIC LANDMARK COMMISSION RECOMMENDATION:**

February 26, 2018      *Scheduled for Historic Landmark Commission*

### **PLANNING COMMISSION RECOMMENDATION:**

February 27, 2018      *Scheduled for Planning Commission*

### **ISSUES:**

The Hyde Park Neighborhood Plan adopted by City Council in April, 2000 refers to the Baker School property and recommends that the historic school building be preserved, and that the property be returned to a community use that serves children (See Comprehensive Planning, below). The applicant's plans include preservation of the historic building, but not a return to a child-serving or civic use. The applicant has worked with the Hyde Park Neighborhood Association (HPNA), and has the support of the neighborhood association for this rezoning (See Exhibit F).

The Traffic Impact Analysis (TIA) is waived for this project until the time of site plan. A provision will be placed in a Public Restrictive Covenant to require a TIA if the proposed development on the property, considered cumulatively with all existing or previously authorized development and uses, generates traffic that exceeds 2,000 trips per day.

## **DEPARTMENT COMMENTS:**

The subject property is the location of the historic Baker Elementary School building, which has been used for many years as an administration building for AISD. Like many historic school sites, the property has never been zoned. It is located in the western part of the Hyde Park neighborhood, a block from Guadalupe Street to the west. Vehicular access is currently available to West 39<sup>th</sup> and West 40<sup>th</sup> Streets, and Avenue B. There is also an alley to the west of the site that extends the length of the block.

The applicant proposes to zone the property and has requested a base zoning of general commercial services (CS). Because of the location of the property within existing Hyde Park overlays, the request includes Neighborhood Conservation Combining District (-NCCD), Historic District (-HD), and Neighborhood Plan (-NP). The applicant proposes to amend the NCCD to add the subject property and to change some of the development standards, and add allowed uses, specifically for the property. Therefore the case number is an extension of the original NCCD case number. Ultimately, the applicant is interested in a Historic Landmark (-H) designation, but is not making that request at this time.

The Hyde Park Historic District was approved by Council in December, 2010, and contains a preservation plan, and design standards. The subject site is within the bounds of the historic district, and in the approved ordinance for the district, 3908 Avenue B is listed as a Contributing property (See Exhibit J).

The Hyde Park NCCD ordinance created a handful of special subdistricts; all parcels not in a special subdistrict, are classed in the Residential subdistrict. The subject property does not fall into a special subdistrict, and would therefore be classed as Residential subdistrict. (See Exhibit H & Amendment to the NCCD, Exhibit I).

The applicant's conceptual plan shows no changes to current vehicular access (See Exhibit G). The applicant is proposing changes to the NCCD, which would apply only to this property. Starting from a baseline of requirements in the Residential subdistrict, the following changes are proposed: increasing the allowable height from 30 feet to 50 feet, increasing the allowable FAR from 0.5:1 to 1.5:1, and allowing a set of uses. For the full list, see the letter from the applicant, Exhibit E. Proposed Uses that would not otherwise be permitted – in a commercial base zone in the Residential subdistrict – are as follows:

- Condominium Residential
- Financial Services
- Food Sales (5000 s.f. limit)
- General retail sales
- Indoor entertainment
- Multifamily Residential
- Restaurant (limited) (5000 s.f. limit)
- Restaurant (general) (5000 s.f. limit)
- Software Development
- Theater (5000 s.f. limit)

Staff recommends the base zoning of community commercial (GR), which is defined as “office or other commercial use that serves neighborhood and community needs.” GR is preferred over general commercial services (CS) as a zoning category that typically permits a wide range of commercial and light industrial uses, and would not be appropriate in this predominantly residential area.

Further, staff recommends granting the applicant’s request to change the development standards - increasing the allowable height from 30 feet to 50 feet, and increasing the allowable FAR from 0.5:1 to 1.5:1 - which will accommodate the applicant’s preliminary plan. This plan includes a residential structure in the undeveloped western portion of the site, to the rear of the historic structure.

Finally, staff recommends adding allowed uses, recognizing that these uses have been agreed upon with the neighborhood, and finding these uses to be compatible with the surrounding neighborhood. Some small changes to the original request are recommended: General retail sales should be clarified to “General Retail Sales (Convenience)” and limited to 5,000 square feet. Indoor Entertainment should be limited to 5,000 square feet.

The applicant has worked extensively with the Hyde Park Neighborhood Association, and gained their support for the rezoning (See Exhibits E & F). The applicant has made agreements with the neighborhood association that include the provision of affordable housing units at such a time that a multifamily building would be constructed on the site.

#### **EXISTING ZONING AND LAND USES:**

|              | <b>ZONING</b>  | <b>LAND USES</b>   |
|--------------|--|--|
| <i>Site</i>  | UNZ (Unzoned)  | AISD Administration (Office)                                       |
| <i>North</i> | W 40 <sup>th</sup> Street, then LR-MU-V-HD-NCCD-NP; LR-MU-HD-NCCD-NP; CS-HD-NCCD-NP; SF-3-HD-NCCD-NP | W 40 <sup>th</sup> Street, then Single Family, Duplex, Multifamily |
| <i>South</i> | W 39 <sup>th</sup> Street, then MF-4-NCCD-NP   | W 39 <sup>th</sup> Street, then Single Family, Duplex, Multifamily |
| <i>East</i>  | Avenue B, then SF-3-HD-NCCD-NP   | Avenue B, then Church, Single Family                               |
| <i>West</i>  | CS-V-NCCD-NP, then Guadalupe Street  | Commercial, then Guadalupe Street                                  |

#### **NEIGHBORHOOD PLANNING AREA:** Hyde Park

**TIA:** No, however a TIA may be required at the time of site plan.

**WATERSHED:** Waller Creek

**DESIRED DEVELOPMENT ZONE:** Yes

**CAPITOL VIEW CORRIDOR:** No

**HILL COUNTRY ROADWAY:** No

**NEIGHBORHOOD ORGANIZATIONS:**

| <i>Community Registry Name</i>                   | <i>ID</i> |
|--|-----------|
| 45th St Concerned Citizens                       | 1194      |
| Austin Independent School District               | 742       |
| Austin Neighborhoods Council                     | 511       |
| Bike Austin                                      | 1528      |
| Central Austin Community Development Corporation | 1391      |
| Friends Of Austin Neighborhoods                  | 1530      |
| Friends Of Hyde Park                             | 1503      |
| Homeless Neighborhood Association                | 1550      |
| Hyde Park Neighborhood Assn                      | 34        |
| Hyde Park Neighborhood Plan Contact Team         | 1254      |
| North Austin Neighborhood Alliance               | 283       |
| Preservation Austin                              | 1424      |
| Seltexas   | 1363      |
| Shoal Creek Conservancy                          | 1497      |
| Sierra Club Austin Regional Group                | 1228      |

**SCHOOLS:** Lee Elementary School, Kealing Middle School, McCallum High School

**CASE HISTORIES:**

| NUMBER  | REQUEST  | PLANNING COMMISSION                              | CITY COUNCIL   |
|---|--|--|--|
| C14-2016-0072<br>39 <sup>th</sup> Street<br>Apartments<br>405 W 39 <sup>th</sup> Street | SF-3 to MF-4   | 10-11-16- Apvd MF-4-NCCD-NP as Staff recommended | 11-10-16- Apvd MF-4-NCCD-NP as PC rec, on all 3 Rdgs   |
| C14-2016-0065<br>Pioneer Bank on W. 38 <sup>th</sup><br>623 W. 38 <sup>th</sup> Street  | GR-CO-NP, Remove CO to remove prohibition of drive-in services | 01-24-17- Denied GR-CO-NP                        | 03-02-17- Case withdrawn by Applicant; no action taken |

| <b>NUMBER</b>  | <b>REQUEST</b>               | <b>PLANNING COMMISSION</b>  | <b>CITY COUNCIL</b>  |
|--|------------------------------|---|--|
| C14-2007-0263<br>Hyde Park<br>Neighborhood<br>Planning Area<br>Vertical Mixed Use<br>Building Rezoning                                 | Vertical Mixed Use<br>(VMU)  | 01-15-08 - Apvd<br>staff rec by consent   | 05-22-08- Apvd Ord.<br>20080522-044 for V<br>(Tracts 1-12) |
| C14-2007-0263.001<br>Hyde Park<br>Neighborhood<br>Planning Area<br>Vertical Mixed Use<br>Building (V) Opt-<br>In/Opt-<br>4000 Avenue B | LR-MU-V-NCCD                 | 04-22-08 - Apvd LR-<br>MU-V-NCCD for Tr<br>100 (4000 Avenue<br>B) w/ conditions | 05-22-08 - Apvd<br>Ord. 20080522-061<br>for VMU for Tr 100 |
| C14-2007-0210<br>The Kocurek<br>Building<br>511 W 41 <sup>st</sup> Street  | SF-3 to NO-H-<br>NCCD        | 02-12-08- Apvd staff<br>rec of NO-H-NCCD  | 06-05-08- Apvd Ord.<br>20080605-062 for<br>NO-H-NCCD       |
| C14H-2007-0018<br>Plumb House<br>4100 Avenue D   | SF-3 to SF-3H                | Never heard by<br>Commission -<br>Postponed<br>indefinitely                     | N/A  |
| C14H-2007-0019<br>John & Lela Gay<br>House<br>4108 Avenue D  | SF-3-NCCD to SF-3-<br>H-NCCD | 10-23-07- Apvd staff<br>rec of SF-3-H-NCCD                                      | 11-29-07- Apvd Ord.<br>20071129-075 for<br>SF-3-H-NCCD     |
| C14H-2007-0024<br>Hume-Rowe House<br>4002 Avenue C   | SF-3-NCCD to SF-3-<br>H-NCCD | 11-13-07- Apvd staff<br>rec of SF-3-H-NCCD                                      | 12-06-07- Apvd Ord.<br>20071206-081 for<br>SF-3-H-NCCD     |

**RELATED CASES:**

| <b>NUMBER</b>                                    | <b>REQUEST</b>                                     | <b>PLANNING<br/>COMMISSION</b>  | <b>CITY COUNCIL</b>   |
|--|--|---|---|
| C14H-2010-0019<br>Hyde Park Historic<br>District | Historic District<br>(HD)                          | 10-12-10- Apvd<br>staff's rec for HD  | 12-16-10- Ordinance<br>No. 20101216-093<br>for historic area<br>combining district<br>zoning approved<br>with the Hyde Park<br>Preservation Plan<br>and Design<br>Standards |
| C14-01-0046<br>Hyde Park NCCD                    | Neighborhood<br>Conservation<br>Combining District | 05-22-01- Apvd staff<br>rec with conditions   | 01-31-02- Apvd<br>ordinance 020131-20   |
| C14-01-0046.01<br>Hyde Park NCCD<br>Amendment #1 | Modify the NCCD                                    | 12-13-11- Apvd<br>amendment to the<br>Hyde Park NCCD<br>with a maximum of<br>.4 FAR | 01-12-12- Apvd ord<br># 20120112-086  |

**SUBDIVISION:**

4.361 acres of land designated as a portion of Austin Rapid Transit Co. Park by Hyde Park Addition No. 2, a subdivision of record in Volume 1, Page 75, of the Plat Records of Travis County Texas.

**ABUTTING STREETS:**

| <b>Name</b>         | <b>ROW</b> | <b>Pavement</b> | <b>Classification</b> | <b>Sidewalks</b> | <b>Bike Route</b> | <b>Capital Metro<br/>(within ¼ mile)</b> |
|---------------------|------------|-----------------|-----------------------|------------------|-------------------|--|
| Avenue B            | 80'        | 49'             | Collector             | Y                | Y                 | Route 50, 990, 801, 1                    |
| 40 <sup>th</sup> St | 80'        | 43'             | Collector             | Y                | Y                 | Route 50, 990, 801, 1                    |
| 39 <sup>th</sup> St | 60         | 37              | Local                 | Y                | Y                 | Route 50, 990, 801, 1                    |

***Transportation – Mark Kere – 512-974-2964***

TR1. Additional right-of-way may be required at the time of subdivision and/or site plan.

**CITY COUNCIL DATE:**

March 22, 2018

**ACTION:**

**ORDINANCE READINGS:**

**1st**

**2<sup>nd</sup>**

**3<sup>rd</sup>**

**ORDINANCE NUMBER:**

**CASE MANAGER:** Scott Grantham

**PHONE:** 512-974-3574

**EMAIL:** [scott.grantham@austintexas.gov](mailto:scott.grantham@austintexas.gov)

## **BASIS FOR RECOMMENDATION**

1. *Zoning should promote a transition between adjacent and nearby zoning districts, land uses, and development intensities.*

From Guadalupe Street to the west, the height entitlement would step down to the rest of the Hyde Park neighborhood to the east. 60 feet of height is allowed on Guadalupe, the request is for an entitlement of 50 feet, which would apply to the western portion of the site. The historic school building furthest west will be maintained at 40 feet in height.

2. *Zoning should promote clearly-identified community goals, such as creating employment opportunities or providing for affordable housing.*

Affordable housing is a provision of the agreement between the applicant and the Hyde Park Neighborhood Association.

3. *Zoning should allow for reasonable use of the property.*

The property is currently unzoned, and zoning should allow for uses beyond the existing administrative and business use of the property, expanding entitlements to allow for residential uses.

## **EXISTING CONDITIONS**

### ***Site Characteristics***

The historic Baker School building is located on the site, and is currently occupied by an office use. There are parking lots to the north and south of the building, with driveway access from W. 40<sup>th</sup> Street and W. 39<sup>th</sup> Street. There is also vehicular access from Avenue B, and an alleyway to the west of the site that runs the length of the block. There are several heritage trees to the north, south, and east of the building. There is a large open field to the west of the building. The site is relatively flat, and is not located within a flood plain.

### ***Impervious Cover***

The site is located in an Urban Watershed and therefore the zoning district will determine the impervious cover limits. The Residential District within the Hyde Park NCCD allows up to 70% impervious cover.



## ***Comprehensive Planning – Kathleen Fox – 512-974-7877***

The subject property is located within the boundaries of the Hyde Park Neighborhood Planning Area. The proposed use is mixed use for a new corporate headquarters. There is a possibility of affordable housing units and space for creative industry non-profits to be located on the property in the future.

### **Connectivity**

Public sidewalks are available on the eastern and southern borders of the property, but not to the north. A Capital Metro transit stop is located within walking distance to this site. The Walkscore for this site is 83/100, Very Walkable, meaning most errands can be accomplished on foot.

### **Hyde Park Neighborhood Plan**

The HPNP *does not* have a Future Land Use Map. The following goals, objectives and text are relevant to this case:

*Residential District:* Purpose: To maintain Hyde Park's traditional single family character and encourage compatible redevelopment of apartment uses. To maintain civic uses in scale and use to be compatible with the predominant single family character. (p. 11)

5. Consider for Historic Landmark status buildings and structures that are eligible, (including): p. 17
  - **Baker School**

### **Goal 6: Foster a genuine community of neighbors of every age and background. (p. 45)**

59. Preserve Baker School and encourage its return to use for public academic purposes and community uses. Neighborhood Action Item: NPT, AISD (p. 47)
61. The Yarbrough Library serves the Hyde Park area. Future joint reuse of Baker School or other civic buildings should be investigated for a public reading room and/or library book drop-off bin. Neighborhood Action Item: NPT, Library Dept., AISD
63. Additional park facilities should be provided as following: C) Austin Independent School District (AISD) should improve and maintain the facilities at Baker School, including the Baker School fields. (p. 48)

Beyond day care, there is an intense interest among residents for community-based education. Baker School was Hyde Park's original 1st through 8th grade school. It was converted from Community College use to office facilities for AISD in 1998. HPNA opposed this change and requested that the school be returned to service as a school. During the recent past, while the school has served needs other than those of neighborhood school, the facility has not provided for community use beyond as a voting location. (p. 48)

Return Baker School to uses for children. It is the wish of the neighborhood that the school return to use as both a school for area children and as a focus of community

activity including after school care and other child care and community activities such as Parks & Recreation's summer teen program (in the summer of 1997 and 1998 this programs utilized the gym and grounds), community meetings, and access to the gym for recreation. Planning Principle: NPT

The HPNP appears to support uses which are compatible and in scale with the predominant single family character in the Residential District. In addition, the Neighborhood Plan supports the preservation and historic designation of the Baker School, but desires the school to be converted back to a community use.

### **Imagine Austin**

The property is located less than 100 ft. away from a designated Activity Corridor on Guadalupe Street. Activity Corridors are intended to allow people to reside, work, shop, access services, people watch, recreate, and hang out without traveling far distances. The following Imagine Austin policies are taken from Chapter 4 of the IACP, which specifically discusses the promotion of different types of housing throughout Austin:

- **LUT P7.** Encourage infill and redevelopment opportunities that place residential, work, and retail land uses in proximity to each other to maximize walking, bicycling, and transit opportunities.
- **HN P10.** Create complete neighborhoods across Austin that have a mix of housing types and land uses, affordable housing and transportation options, and access to schools, retail, employment, community services, and parks and recreation options.

Based upon this project being adjacent to an Activity Corridor, and the Imagine Austin policies referenced above that supports mixed use and a variety of housing types, this project appears to be supported by the Imagine Austin Comprehensive Plan, and partially supported by the HPNP.

### ***Site Plan – Amelia Watts – 512-974-3103***

- SP 1. Site plans will be required for any new development other than single-family or duplex residential.
- SP 2. Any development which occurs in an SF-6 or less restrictive zoning district which is located 540 feet or less from property in an SF-5 or more restrictive zoning district will be subject to compatibility development regulations.
- SP 3. Any new development is subject to Subchapter E. Design Standards and Mixed Use. Additional comments will be made when the site plan is submitted.

### **Compatibility Standards**

- SP 4. The site is subject to compatibility standards. Along the North, East, and South property lines, the following standards apply:
- No structure may be built within 25 feet of the property line.

- No structure in excess of two stories or 30 feet in height may be constructed within 50 feet of the property line.
- No structure in excess of three stories or 40 feet in height may be constructed within 100 feet of the property line.
- No parking or driveways are allowed within 25 feet of the property line.
- A landscape area at least 25 feet wide is required along the property line. In addition, a fence, berm, or dense vegetation must be provided to screen adjoining properties from views of parking, mechanical equipment, storage, and refuse collection.
- For a structure more than 100 feet but not more than 300 feet from property zoned SF-5 or more restrictive, height limitation is 40 feet plus one foot for each 10 feet of distance in excess of 100 feet from the property line.
- An intensive recreational use, including a swimming pool, tennis court, ball court, or playground, may not be constructed 50 feet or less from adjoining SF-3 property.
- A landscape area at least 25 feet in width is required along the property line if the tract is zoned LR, GO, GR, L, CS, CS-1, or CH.

Additional design regulations will be enforced at the time a site plan is submitted.

FYI. Additional comments may occur in the Site Plan review stages, as this falls near a “National Register of Historic Districts.


***Environmental - Mike Mcdougal - 512-974-6380***

1. The site is not located over the Edwards Aquifer Recharge Zone. The site is located in the Waller Creek Watershed of the Colorado River Basin, which is classified as an Urban Watershed by Chapter 25-8 of the City's Land Development Code. It is in the Desired Development Zone.
2. Zoning district impervious cover limits apply in the Urban Watershed classification.
3. According to floodplain maps there is no floodplain within or adjacent to the project location.
4. Standard landscaping and tree protection will be required in accordance with LDC 25-2 and 25-8 for all development and/or redevelopment.
5. Trees will likely be impacted with a proposed development associated with this rezoning case. Please be aware that an approved rezoning status does not eliminate a proposed development's requirements to meet the intent of the tree ordinances. If further explanation or specificity is needed, please contact the City Arborist at 974-1876. At this time, site specific information is unavailable regarding other vegetation, areas of steep slope, or other environmental features such as bluffs, springs, canyon rimrock, caves, sinkholes, and wetlands.

6. This site is required to provide on-site water quality controls (or payment in lieu of) for all development and/or redevelopment when 8,000 s.f. cumulative is exceeded, and on site control for the two-year storm.
7. At this time, no information has been provided as to whether this property has any preexisting approvals that preempt current water quality or Code requirements.

***Austin Water Utility – 512-972-0000***


The landowner intends to serve the site with City of Austin water and wastewater utilities. The landowner, at own expense, will be responsible for providing any water and wastewater utility improvements, offsite main extensions, water or wastewater easements, utility relocations and or abandonments required by the proposed land use. Depending on the development plans submitted, water and or wastewater service extension requests may be required. Water and wastewater utility plans must be reviewed and approved by Austin Water for compliance with City criteria and suitability for operation and maintenance. All water and wastewater construction must be inspected by the City of Austin. The landowner must pay the City inspection fee with the utility construction. The landowner must pay the tap and impact fees once the landowner makes an application for Austin Water utility tap permits.



# ZONING

CASE#: C14-2017-0153

## EXHIBIT A





This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries.

This product has been produced by the Planning and Zoning Department for the sole purpose of geographic reference. No warranty is made by the City of Austin regarding specific accuracy or completeness.



Created: 12/22/2017





## ZONING & VICINITY

Zoning Case: C14-01-0046.02  
 Address: 3908 Avenue B  
 Subject Area: 4.361 Acres  
 Case Manager: Scott Grantham


This map has been produced for the Planning and Zoning Department for the sole purpose of geographic reference. No warranty is made by the City of Austin regarding specific accuracy or completeness.



**EXHIBIT B**



BASELINE LAND SURVEYORS, INC.  
PROFESSIONAL LAND SURVEYING SERVICES  
8333 CROSS PARK DRIVE  
AUSTIN, TEXAS 78754  
TELE: 512.374.9722 FAX: 512.873.9743  
FIRM REGISTRATION CERTIFICATE #10015100  
scott-baseline@austlnr.com



| TABLE OF PARKING SPACES |    |
|-------------------------|----|
| ONSITE STANDARD         | 90 |
| ONSITE HANDICAP         | 3  |
| ANGLED STREET PARKING   | 50 |

[illegible][illegible]

0: (1) AUSTIN INDEPENDENT SCHOOL DISTRICT, (II)

(iii) FIRST AMERICAN TITLE INSURANCE COMPANY, AND (iv) HERITAGE TITLE COMPANY OF AUSTIN, INC.;

[illegible]

PREPARED BY THE TEXAS SOCIETY OF PROFESSIONAL SURVEYORS.



SCOTT LASWELL  
STATE OF TEXAS REGISTRATION NUMBER 5583



**EXHIBIT D**  
*Land Surveyors, Inc.*  
8333 Cross Park Drive  
Austin, Texas 78754  
Office: 512.374.9722  
Fax: 512.873-9743

### METES AND BOUNDS DESCRIPTION

BEING 4.361 ACRES OF LAND DESIGNATED AS A PORTION OF AUSTIN RAPID TRANSIT CO. PARK BY HYDE PARK ADDITION NO. 2, A SUBDIVISION OF RECORD IN VOLUME 1, PAGE 75, OF THE PLAT RECORDS OF TRAVIS COUNTY TEXAS, AND BEING COMPRISED OF TWO TRACTS: TRACT 1 BEING A PARCEL OF LAND 262 FEET BY 425 FEET CONVEYED TO THE BOARD OF TRUSTEES OF THE PUBLIC FREE SCHOOLS OF THE CITY OF AUSTIN BY INSTRUMENT OF RECORD IN VOLUME 246, PAGE 154, OF THE DEED RECORDS OF TRAVIS COUNTY TEXAS; AND TRACT TWO BEING A PARCEL OF LAND 185 FEET BY 425 FEET CONVEYED TO THE BOARD OF TRUSTEES OF THE PUBLIC FREE SCHOOLS OF THE CITY OF AUSTIN BY INSTRUMENT OF RECORD IN VOLUME 586, PAGE 96, OF THE DEED RECORDS OF TRAVIS COUNTY TEXAS; AND BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING at a calculated point in a concrete sidewalk for the southeast corner of said "Tract 1" and being the point of intersection of the north right-of-way line of West 39<sup>th</sup> Street (60' R.O.W.) and the west right-of-way line of Avenue B (80' R.O.W.), from which an iron pipe found in asphalt for the northwest corner of a tract of land conveyed to Artesia 305 W. 39<sup>th</sup>, LLC by instrument of record in Doc. No. 2014112130 of the Official Public Records of Travis County, Texas, and being the point of intersection of the south right-of-way line of said West 39<sup>th</sup> Street and the east right-of-way line of said Avenue B bears South 19°44'29" East a distance of 88.79 feet;

THENCE North 62°21'59" West (record – "Westerly"), along the south line of "Tract1" and said "Tract 2", and the north right-of-way line of West 39<sup>th</sup> Street, a distance of 447.00 feet (record – 447 feet) to a calculated point for the southwest corner of "Tract 2" and the southeast corner of a 12 foot wide alley dedicated by instrument of record in Volume 242, Page 116 of the Deed Records of Travis County, Texas, from which an "X" cut in concrete for the southwest corner of said 12 foot wide alley, the southeast corner of a 125 foot by 212.50 foot parcel of land out of said Austin Rapid Transit Co. Park dedicated by said Hyde Park Addition No. 2, conveyed to Chalet Properties Austin, LLC by instrument of record in Doc. No. 2008166351 of the Official Public Records of Travis County, Texas, and being in the north right-of-way line of West 39<sup>th</sup> Street, bears North 62°17'22" West (record – "Westerly") a distance of 11.97 feet (record – 12 feet), and from said "X" cut in concrete a 1/2" rebar found for the northeast corner of said 125 foot by 212.50 foot parcel conveyed to Chalet Properties Austin, LLC, the southeast corner of a 125 foot by 212.50 foot parcel of land out of Austin Rapid Transit Co. Park dedicated by Hyde Park Addition No. 2, conveyed to Sigmor Number 80, Inc. by instrument of record in Doc. No. 2010020896 of the Official Public Records of Travis County, Texas, and being in the west line of the 12 foot wide alley, bears North 27°38'01" East a distance of 212.55 feet (record - North 28°32'54" East a distance of 212.50 feet);

THENCE North 27°38'01" East (record – "Northerly"), along the west line "Tract 2" and the east line of the 12 foot wide alley, a distance of 425.00' (record – 425 feet) to a 1/2" rebar



found for the northwest corner of "Tract 2", the northeast corner of the 12 foot wide alley, and being in the south right-of-way line of West 40<sup>th</sup> Street (80' R.O.W.), from which a 1/2" iron pipe found for the northwest corner of the 12 foot wide alley, the northeast corner of said 125 foot by 212.50 foot parcel conveyed to Sigmor Number 80, Inc., and being in the south right-of-way line of said West 40<sup>th</sup> Street, bears North 61°31'09" West (record – "Westerly") a distance of 11.97 feet (record – 12 feet), and from said 1/2" iron pipe found said 1/2" rebar found for the southeast corner of the 125 foot by 212.50 foot parcel conveyed to Sigmor Number 80, Inc., the northeast corner of the 125 foot by 212.50 foot parcel conveyed to Chalet Properties Austin, LLC, and being in the west line of the 12 foot wide alley, bears South 27°38'01" West a distance of 212.61 feet (record – South 28°32'54" West a distance of 212.50 feet);


THENCE South 62°21'59" East (record – "Easterly"), along the north line of "Tract 2" and "Tract 1", and the south right-of-way line of West 40<sup>th</sup> Street, a distance of 447.00 feet (record – 447 feet) to a 1/2" rebar set with plastic cap which reads "Baseline Inc" for the northeast corner of "Tract 1" and being the point of intersection of the south right-of-way line of West 40<sup>th</sup> Street and the west right-of-way line of Avenue B, from which a 1/2" rebar found for the southeast corner of a tract of land conveyed to Hong Tao Lee and Jenny C, Lee by instrument of record in Volume 10796, Page 334 of the Real Property Records of Travis County, Texas, and being the point of intersection of the north right-of-way line of West 40<sup>th</sup> Street and the west right-of-way line of Avenue B, bears North 27°30'13" East a distance of 80.27 feet (record – 80 feet), and also from which a 1/2" rebar found for the southwest corner of a tract of land conveyed to Leopold P. Wolf by an unrecorded will, and being the point of intersection of the north right-of-way line of West 40<sup>th</sup> Street and the east right-of-way line of Avenue B, bears North 72°31'58" East a distance of 112.60 feet;

THENCE South 27°38'01" West (record – "Southerly"), along the east line "Tract 1" and the west right-of-way line of Avenue B, a distance of 425.00 feet (record - 425 feet) to the POINT OF BEGINNING.

This parcel contains 4.361 acres of land, more or less, designated as a portion of Austin Rapid Transit Co. Park by Hyde Park Addition No. 2, a subdivision of record in Volume 1, Page 75, of the Plat Records of Travis County, Texas.

Bearing Basis: Texas State Plane Coordinates, Central Zone, NAD 83\96CORS.

  
 J. Scott Laswell                      Date  
 Registered Professional Land Surveyor  
 State of Texas No. 5583



File: S:\Projects\AISD Baker Center\Docs\Field Notes\Title Survey M&B.doc  
 Drawing: S:\Projects\AISD Baker Center\Dwg\Title Survey.dwg

Dear Planning Department,

## EXHIBIT E

Please see below the term sheet agreed upon by AISD and HPNA for rezoning the Baker School Property located at 3900 (3908) Avenue B, Austin Texas

**The Baker Center proposal accepted by the full HPNA (26-0) at the December 04 2017 Meeting-**

The items in highlighted in bold require a change to the Hyde Park NCCD that would run in parallel with the Zoning request. The neighborhood (subcommittee) has also agreed to ask the neighborhood to write a letter of support for a variance to count the parking adjacent to the site on W.39<sup>th</sup> and W.40<sup>th</sup> St toward the on-site parking requirements for the project (to be filed after zoning complete)

**Zoning request: CS-HD-NCCD (need to verify with the city that the NCCD allowing residential use on the site does not also require the MU designation)- also need to verify if H is required in order to be designated a Historic Landmark**

**Maximum FAR: 1.5 to 1 (requires a change to the NCCD)**

**Maximum Height allowed: 50' (height above what is currently allowed in the NCCD only allowed on the west portion of the site behind the original Baker School Building- the rest of the site will be restricted to the height specified in the NCCD)- (requires a change to the NCCD)**

### ***Allowable uses on the Site***

Admin and Business office

Art and Craft Studio (limited and general)

Cultural Services

**Condominium Residential (requires a change to the NCCD)**

Day Care Services (limited and General)

Financial Services

Food Sales (5000 s.f. limit)

**Art Gallery (not listed in NCCD uses)**

General retail sales

Indoor entertainment

**Multifamily Residential (requires a change to the NCCD)**

Personal Improvement Services

Personal Services

Private Primary Educational Facilities

Private Secondary Educational Facilities

Professional Office

Public Primary Educational Facilities

Public Secondary Educational Facilities

Professional Office

Restaurant (limited and general- 5000 s.f. limit)

Software Development

Theater (5,000)

### **Affordable Housing Terms-**

Dear Planning Department,

Please see below the term sheet agreed upon by AISD and HPNA for rezoning the Baker School Property located at 3900 (3908) Avenue B, Austin Texas

The Baker Center proposal accepted by the full HPNA (26-0) at the December 04 2017 Meeting-

|                |   |
|----------------|---|
| Homeownership- | 25% of the total units affordable to 120% MFI |
| Rental-        | 10% Affordable to 80% MFI                     |
|                | 15% Affordable to 100% MFI                    |
| Term-          | 30 years (per the AISD RFP)                   |

In addition, Alamo Drafthouse agrees to the following:

1. Alamo Drafthouse ("Alamo") will support the neighbors along Ave B in applying for the Residential Parking Permit (RPP) program at the city of Austin
2. Alamo agrees to seek historic designation for Baker building
3. Alamo agrees to maintain and care for trees on site
4. Alamo agrees to place dumpsters in alley to west of new building or in alleyway between Baker and new building. Dumpsters will be screened

Thank You

Richard Weiss AIA

Weiss Architecture Inc.

3355 Bee Cave Road #303

Austin TX 78746

(512) 447-6806 ph

(512) 851-2005 fx

[richard@weissarc.com](mailto:richard@weissarc.com)

[www.weissarc.com](http://www.weissarc.com)

## EXHIBIT F

### Hyde Park Neighborhood Association

P.O. Box 49427 • Austin, TX 78765 • [www.austinhdepark.org](http://www.austinhdepark.org)

December 18, 2017

Jerry Rusthoven  
Acting Assistant Director  
Planning and Zoning Department  
City of Austin  
505 Barton Springs Road  
Austin, Texas 78704


Dear Jerry:

At its December 4th general meeting, the Hyde Park Neighborhood Association voted to approve an agreement on zoning for the Baker Center property that is under an option to Alamo Drafthouse (Hereafter Alamo). The agreement was approved without opposition to support a zoning of the Baker Center to CS-NCCD-HD-H. This zoning category will be followed with an amendment from the neighborhood to change the allowable uses on this site as well as to modify the FAR to 1.5:1 and a maximum height on the field behind the building of 50'.


Additionally, the neighborhood also agreed to support a variance for the inclusion of the parking spaces along both 39<sup>th</sup> and 40<sup>th</sup> Streets towards the parking count for the Baker Center site.

Finally, please do not hesitate to contact me regarding this zoning matter. We look forward to working with you and Alamo Drafthouse on this particular project.

Sincerely,



Reid Long  
President








THE BAKER CENTER  
MASSING MODEL

EXHIBIT G

SITE PLAN



THE BAKER CENTER  
MASSING MODEL

SITE PLAN  
ENLARGED





THE BAKER CENTER  
MASSING MODEL

50' BUILDING  
PERSPECTIVE 1



THE BAKER CENTER  
MASSING MODEL

50' BUILDING  
PERSPECTIVE 2



## **EXHIBIT H**

### **ORDINANCE NO. 020131-20**

**AN ORDINANCE REZONING AND CHANGING THE ZONING MAP ACCOMPANYING CHAPTER 25-2 OF THE CITY CODE TO ESTABLISH THE HYDE PARK NEIGHBORHOOD CONSERVATION COMBINING DISTRICT (NCCD) FOR THE PROPERTY WHOSE BOUNDARIES ARE 45<sup>TH</sup> STREET TO THE NORTH, 38<sup>TH</sup> STREET TO THE SOUTH, GUADALUPE STREET TO THE WEST AND DUVAL STREET TO THE EAST, IN THE CITY OF AUSTIN, TRAVIS COUNTY, TEXAS; AND TO MODIFY CERTAIN BASE DISTRICTS IN THE NCCD; AND DECLARING AN EMERGENCY.**

#### **BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF AUSTIN:**

**PART 1.** The zoning map established by Section 25-2-191 of the City Code is amended to establish the Hyde Park neighborhood conservation combining district (NCCD) and to add a NCCD to each base zoning district within the property bounded by 45<sup>th</sup> Street to the north, 38<sup>th</sup> Street to the south, Guadalupe Street to the west, and Duval Street to the east, described in File C14-01-0046 and as more particularly identified in the map attached as Exhibit "A," SAVE AND EXCEPT Lots 5 through 16 of Block 12 of the Hyde Park Addition No. 1, and to change the base zoning districts on 13 tracts of land within the NCCD.

**PART 2.** The base zoning of the 13 tracts shown in the chart below are changed from family residence (SF-3) district, multifamily residence medium density (MF-3) district, multifamily residence moderate- high density (MF-4) district, multifamily residence moderate-high density-historic (MF-4-H) combining district, limited office-historic (LO-H) combining district, and general commercial services (CS) district, to multifamily residence limited density neighborhood conservation (MF-1-NCCD) combining district, multifamily residence low density neighborhood conservation (MF-2-NCCD) combining district, family residence neighborhood conservation (SF-3-NCCD) combining district, family residence-historic-neighborhood conservation (SF-3-H-NCCD) combining district, limited office-historic-neighborhood conservation (LO-H-NCCD) combining district, neighborhood commercial neighborhood conservation (LR-NCCD) combining district, and multifamily residence medium density neighborhood conservation (MF-3-NCCD) combining district.

| MAP<br>TRACT # | PROPERTY ADDRESS  | FROM | TO        |
|----------------|-------------------|------|-----------|
| 2              | 4309 Avenue D     | MF-4 | SF-3-NCCD |
| 2              | 4307 Avenue D     | MF-4 | SF-3-NCCD |
| 2              | 4311 Avenue D     | MF-4 | SF-3-NCCD |
| 3              | 4416 Speedway     | MF-3 | SF-3-NCCD |
| 3              | 4414 Speedway     | MF-3 | SF-3-NCCD |
| 3              | 4412 Speedway     | MF-3 | SF-3-NCCD |
| 3              | 4410 Speedway     | MF-3 | SF-3-NCCD |
| 3              | 4408 Speedway     | MF-3 | SF-3-NCCD |
| 3              | 4406 Speedway     | MF-3 | SF-3-NCCD |
| 3              | 4404 Speedway     | MF-3 | SF-3-NCCD |
| 3              | 4402 Speedway     | MF-3 | SF-3-NCCD |
| 3              | 4400 Speedway     | MF-3 | SF-3-NCCD |
| 4              | 4313 Speedway     | MF-3 | SF-3-NCCD |
| 4              | 4311 Speedway     | MF-3 | SF-3-NCCD |
| 4              | 4309 Speedway     | MF-3 | SF-3-NCCD |
| 6              | 4408 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4406 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4404 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4402 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4400 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4316 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4314 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4308 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4306 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4302 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4204 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4202 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4106 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4104 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4100 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4016 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4012 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4014 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4008 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4006 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4004 Duval Street | MF-4 | SF-3-NCCD |
| 6              | 4200 Duval Street | MF-4 | SF-3-NCCD |

| MAP TRACT # | PROPERTY ADDRESS              | FROM   | TO  |
|-------------|-------------------------------|--------|---|
| 7           | 4112 Duval Street             | MF-4   | MF-2-NCCD   |
| 8           | 4214 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4210 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4213 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4203 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4112 Speedway                 | MF-4-H | SF-3-H-NCCD   |
| 8           | 4201 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4110 Speedway                 | MF-4-H | SF-3-H-NCCD   |
| 8           | 4115 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4113 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4108 Speedway                 | MF-4-H | SF-3-H-NCCD   |
| 8           | 4104 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4109 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4107 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4100 Speedway                 | MF-4   | SF-3-NCCD   |
| 8           | 4101 Speedway                 | MF-4   | SF-3-NCCD   |
| 9           | 4006 Speedway                 | LO-H   | LO-H-NCCD   |
| 10          | 4007 Speedway                 | MF-4   | SF-3-NCCD   |
| 10          | 4009 Speedway                 | MF-4   | SF-3-NCCD   |
| 11          | 3913 Avenue C (2 parcels)     | MF-4-H | SF-3-H-NCCD   |
| 12          | 3900 Avenue C (2 parcels)     | MF-4-H | SF-3-H-NCCD   |
| 13          | 4002 Avenue B                 | CS     | SF-3-NCCD   |
| 14          | 408 W 40th Street             | CS     | LR-MU-NCCD  |
| 14          | 406 W 40 <sup>th</sup> Street | CS     | LR-MU-NCCD  |
| 14          | 4000 Avenue B                 | CS     | LR-MU-NCCD  |
| 15          | 3815 Guadalupe Street         | CS     | CS-NCCD for first 120' from the r.o.w.; MF-3-NCCD for remainder |

**PART 3. DEFINITIONS.** In this ordinance:

**ACCESSORY BUILDING** means a building in which an accessory use is located that is detached from and located on the same site as a building in which a principal use is located.

**AVENUE** means a street running in a north-south direction and designated as an avenue.

**CIRCULAR DRIVEWAYS** means a cul-de-sac type driveway with one access point or a half-circular driveway with two access points.

**COMMERCIAL DISTRICT** means the districts within the hierarchy of zoning districts from neighborhood office (NO) district through commercial-liquor sales (CS-1) district.

**DISTRICT** means the Residential District, Speedway District, West 38<sup>th</sup> District, Guadalupe District, Duval District, or the Hyde Park Civic District.

**DRIVEWAY RUNNERS** means a pair of pavement strips acting as a driveway.

**FULL BATHROOM** means a bathroom with a toilet, sink, and a bathtub or shower or shower/bathtub combination.

**REDEVELOPMENT** means development in which the value of the improvements is 50 percent of the value of all existing improvements on the site or development that requires a site plan.

**TANDEM PARKING** means one car behind another so that one car must be moved before the other can be accessed.

**PART 4.** The Hyde Park NCCD is divided into the following districts which are more particularly identified on the map attached as Exhibit B.

1. The Residential District - includes all property not included in another district.
2. The Speedway District - generally located one-half block on each side of Speedway Street from 38<sup>th</sup> Street to 45<sup>th</sup> Street.
3. The Duval District – generally located one-half block west of Duval Street from 40<sup>th</sup> Street to 45<sup>th</sup> Street.
4. The West 38<sup>th</sup> Street District - generally located one block between West 38<sup>th</sup> Street and West 38<sup>th</sup> ½ Street from one lot back from Speedway to one lot back from Guadalupe Street.

5. The Guadalupe District – generally located from Guadalupe Street to one-half block east of Guadalupe Street from 38<sup>th</sup> Street to 45<sup>th</sup> Street.
6. The Hyde Park Civic District - generally located in the area of Speedway and 40<sup>th</sup> Street.

**PART 5.** Development in the Hyde Park Civic District is subject to Ordinance No. 900830-Q. The regulations in Part 6 (Permitted and Conditional Uses), Part 7 (General Provisions), Part 8 (Residential District) and Part 9 (Speedway District) of this ordinance apply to development in the Hyde Park Civic District if they do not conflict with Ordinance No. 900830-Q, as amended. If a use regulation or site development standard is not addressed by Ordinance No. 900830-Q or this ordinance, then the base zoning district regulations as they existed on August 30, 1990 apply.

**PART 6. Permitted and Conditional Uses.**

1. The following table establishes the permitted and conditional uses for property in commercial zoning districts in the Hyde Park NCCD. Use regulations in this section may be modified in Section 2 of this part.

Column (A) applies to property with commercial zoning in the Residential, Speedway, Duval, West 38<sup>th</sup>, and Hyde Park Civic Districts that are not included in Column (B) or Column (C).

Column (B) applies to property at the following locations: 408 E. 43<sup>rd</sup> Street; the Duval Shopping Center which includes 411, 413, 417, and 419 E.43<sup>rd</sup> Street and 4220, 4222, 4224 and 4230 Duval Street; and 4206 Duval Street.

Column (C) applies to property located at 4300 Speedway.

| USES:                               | Column A |    |    |    |    | Column B |    |    | Column C |
|-------------------------------------|----------|----|----|----|----|----------|----|----|----------|
|                                     | A        |    |    |    |    | B        |    |    | C        |
|                                     | CS       | GR | GO | LO | NO | CS       | GR | LR | CS       |
| Administrative and business offices | P        | P  | P  | P  | P  | P        | P  | P  | P        |
| Art and craft studio (limited)      | P        | P  | P  | P  | -- | P        | P  | P  | P        |

| USES:                                      | Column |    |    |    |    | Column |    |    | Column |
|--|--------|----|----|----|----|--------|----|----|--------|
|  | A      |    |    |    |    | B      |    |    | C      |
|  | CS     | GR | GO | LO | NO | CS     | GR | LR | CS     |
| Art and craft studio (general)             | P      | -- | -- | -- | -- | P      | -- | -- | P      |
| Commercial off-street parking              | C      | C  | -- | -- | -- | C      | C  | -- | C      |
| Condominium Residential                    | --     | -- | -- | -- | -- | --     | -- | -- | P      |
| Congregate living                          | C      | C  | C  | C  | C  | C      | C  | C  | C      |
| Consumer convenience services              | C      | C  | -- | -- | -- | P      | P  | P  | P      |
| Consumer repair services                   | C      | C  | -- | -- | -- | P      | P  | P  | P      |
| Cultural services                          | P      | P  | P  | P  | -- | P      | P  | P  | P      |
| Custom manufacturing                       | --     | -- | -- | -- | -- | C      | -- | -- | --     |
| Club or lodge                              | C      | C  | C  | C  | -- | C      | C  | C  | C      |
| Day care services (limited)                | P      | P  | P  | P  | P  | P      | P  | P  | P      |
| Day care services (general)                | P      | P  | P  | P  | P  | P      | P  | P  | P      |
| Day care services (commercial)             | P      | P  | P  | P  | P  | P      | P  | P  | P      |
| Duplex residential                         | P      | P  | P  | P  | P  | P      | P  | P  | P      |
| Family home                                | P      | P  | P  | P  | P  | P      | P  | P  | P      |
| Financial services                         | C      | C  | -- | -- | -- | P      | P  | P  | P      |
| Food sales                                 | C      | C  | -- | -- | -- | P      | P  | P  | P      |
| General retail sales (convenience)         | C      | C  | -- | -- | -- | P      | P  | P  | P      |
| General retail sales (general)             | C      | C  | -- | -- | -- | P      | P  | -- | --     |
| Group home class I (limited)               | P      | P  | P  | P  | P  | P      | P  | P  | P      |
| Group home class I (general)               | P      | P  | P  | P  | P  | P      | P  | P  | P      |
| Group home class II                        | P      | P  | P  | C  | C  | P      | P  | P  | P      |
| Guidance services                          | P      | P  | P  | -- | -- | P      | P  | P  | P      |
| Hospital (limited) not to exceed 2500 s.f. | P      | P  | P  | C  | -- | P      | P  | C  | P      |
| Indoor entertainment                       | C      | C  | -- | -- | -- | C      | C  | -- | --     |
| Laundry services                           | --     | -- | -- | -- | -- | C      | -- | -- | --     |
| Local utility services                     | --     | -- | -- | -- | -- | C      | C  | C  | --     |
| Medical offices (not over 5000 s.f.)       | P      | P  | P  | P  | -- | P      | P  | P  | P      |

| USES:   | Column A |    |    |    |    | Column B |    |    | Column C |
|---|----------|----|----|----|----|----------|----|----|----------|
|   | CS       | GR | GO | LO | NO | CS       | GR | LR | CS       |
| Medical offices (over 5000 s.f.)              | --       | -- | -- | -- | -- | --       | -- | -- | P        |
| Multifamily residential                       | --       | -- | -- | -- | -- | --       | -- | -- | P        |
| Off-site accessory parking                    | C        | C  | C  | -- | -- | C        | C  | C  | C        |
| Personal improvement services                 | P        | P  | -- | -- | -- | P        | P  | -- | P        |
| Personal services                             | P        | P  | P  | -- | -- | P        | P  | P  | P        |
| Private primary educational facilities        | P        | P  | P  | P  | P  | P        | P  | P  | P        |
| Private secondary educational facilities      | P        | P  | P  | P  | P  | P        | P  | P  | P        |
| Public primary educational facilities         | P        | P  | P  | P  | P  | P        | P  | P  | P        |
| Public secondary educational facilities       | P        | P  | P  | P  | P  | P        | P  | P  | P        |
| Professional office                           | P        | P  | P  | P  | P  | P        | P  | P  | P        |
| Religious assembly                            | P        | P  | P  | P  | P  | P        | P  | P  | P        |
| Restaurant (drive-in, fast food)              | --       | -- | -- | -- | -- | C        | C  | C  | --       |
| Restaurant (limited)                          | --       | -- | -- | -- | -- | P        | P  | P  | P        |
| Restaurant (general)                          | --       | -- | -- | -- | -- | P        | P  | P  | P        |
| Service Station                               | --       | -- | -- | -- | -- | C        | C  | C  | --       |
| Single-family residential                     | P        | P  | P  | P  | P  | P        | P  | P  | P        |
| Software development                          | C        | C  | C  | C  | C  | P        | P  | P  | P        |
| Theater                                       | C        | C  | -- | -- | -- | P        | P  | -- | C        |
| Two-family residential                        | P        | P  | P  | P  | P  | P        | P  | P  | P        |
| Veterinary services (not to exceed 2500 s.f.) | P        | -- | -- | -- | -- | P        | -- | -- | P        |
|   |          |    |    |    |    |          |    |    |          |
|   |          |    |    |    |    |          |    |    |          |

2. The section applies to the uses established in Section 1 of this part.

- a. The maximum size of a day care services (commercial) use permitted under Column A is 5000 square feet, under Column B is 2500 square feet, and under Column C is 5000 square feet.

- b. A financial service use or food sales use permitted under Column B and Column C may not include a drive-in service.
  - c. A medical office (over 5000 square feet) permitted under Column C may not exceed 8000 square feet plus 50 percent of the gross floor area of a building over 8000 square feet.
  - d. A multifamily residential use, condominium residential use, or any combination of multifamily and condominium residential uses permitted under Column C may not exceed 75 percent of the gross floor area of all buildings constructed on a site.
  - e. The maximum size of a private primary educational facilities use permitted under Column A is 5000 square feet, under Column B is 2500, and under Column C is 2500 square feet.
  - f. The maximum size of a private secondary educational facilities use permitted under Column A is 5000 square feet, under Column B is 2500 square feet, and under Column C is 5000 square feet.
  - g. The maximum size of a restaurant (limited) and restaurant (general) use permitted under Column C is 3500 square feet.
  - h. The maximum size of a theater use established under Column A and Column B is 5000 square feet.
- 3. On property located at 4307 Speedway, the permitted uses are those permitted in a multifamily residence medium density (MF-3) district and off-site accessory parking.
  - 4. The following uses are permitted on property located in the Guadalupe District.
    - a. Permitted uses.

Administrative and business offices  
 Art and craft studio (general)  
 Automotive rentals  
 Business or trade school  
 Business support services  
 Communication service facilities

Agricultural sales and services  
 Art and craft studio (limited)  
 Automotive washing (of any type)  
 Veterinary services  
 College and university facilities  
 Communications services



Community recreation (public)  
 Congregate living  
 Consumer repair services  
 Cultural services  
 Day care services (commercial)  
 Day care services (limited)  
 Exterminating services  
 Family home  
 Food sales  
 General retail sales (convenience)  
 Group home class I (general)  
 Group home class II  
 Hospital services (limited)  
 Indoor entertainment  
 Local utility services  
 Monument retail sales  
 Outdoor sports and recreation  
 Personal improvement services  
 Pet services  
 Private secondary educational facilities  
 Public secondary educational facilities  
 Religious assembly  
 Residential treatment  
 Restaurant (general)  
 Plant nursery  
 Theater (not to exceed 5000 s.f. )  
 Duplex residential

Community recreation (private)  
 Consumer convenience services  
 Counseling services  
 Custom manufacturing  
 Day care services (general)  
 Electronic prototype assembly  
 (not to exceed 7500 s.f.)  
 Financial services  
 Funeral services  
 General retail sales (general)  
 Group home class I (limited)  
 Guidance services  
 Hotel-motel  
 Indoor sports and recreation  
 Medical offices  
 Multifamily residential  
 Pawn shop services  
 Personal services  
 Private primary educational facilities  
 Public primary educational facilities  
 Professional office  
 Research services  
 Restaurant (limited)  
 Safety services  
 Software development  
 Single-family residential  
 Two-family residential

- b. An automotive repair services use is a permitted use on property north of 4001 Guadalupe Street. The maximum lot size for the use is 9500 square feet.
- c. A limited warehousing and distribution use is a permitted use on property south of 40<sup>th</sup> Street. The use may not exceed 7500 square feet.
- d. A telecommunications tower use is a permitted or conditional use as determined by Section 25-2-839 of the City Code.
- e. A residential use may not be located in the front 70 percent of the ground floor of a building.

5. The following uses are conditional uses on property in the Guadalupe District.

a. Conditional uses.

Building maintenance services  
Commercial off-street parking  
Convenience storage  
Equipment repair services  
Laundry services  
Hospital services (general)  
Off-site accessory parking

Commercial blood plasma center  
Construction sales and services  
Drop-off recycling collection facility  
Equipment sales  
Service station  
Club or lodge

b. Except as otherwise provided in this subsection, a restaurant (drive-in, fast food) use is a conditional use. A drive-in service is prohibited on property located between 40<sup>th</sup> and 43<sup>rd</sup> Streets.

**PART 7. GENERAL PROVISIONS.** Except as otherwise provided in Part 5 of this ordinance or in this part, the following provisions apply to all property within the NCCD.

1. Except as otherwise provided, a building shall front on a north-south street. A building located on a lot that only has frontage on a numbered street may front on the numbered street. A building on a through lot located west of Speedway on West 38<sup>th</sup> Street or West 39<sup>th</sup> Street shall front on West 38<sup>th</sup> Street or West 39<sup>th</sup> Street. The street on which a building fronts under this section is the front of the property on which the building is located for purposes of this ordinance.
2. This section applies to a property that is redeveloped for multifamily, commercial or civic use.
  - a. A site for a dumpster shall be provided on the property. The dumpster shall be screened from the view of adjacent property.
  - b. Except as otherwise provided in this subsection, each parking space shall be independently accessible. For a multifamily use, tandem parking is permitted if the spaces are assigned to one dwelling unit.
3. Except as otherwise provided in this section, the maximum gross floor area of the rear dwelling unit of a two-family residential use is 850 square feet. On a corner lot, the

rear dwelling unit may exceed 850 square feet if the following conditions and other applicable site development regulations are satisfied:

- a. living space is provided on the ground floor;
  - b. one unit has frontage on an north-south street; and
  - c. one unit has frontage on a numbered street.
4. Accessory buildings may not exceed 10 percent of the site area.
  5. A fence located in a front yard may not exceed a height of four feet and shall have a ratio of open space to solid material of not less than 1 to 1.5.
  6. This section applies to a fence located in a street side yard that faces an avenue and is greater than four feet in height. The portion of a fence that is greater than four feet shall have a ratio of open space to solid material of not less than 1 to 1.5.
  7. A fence located along an alley shall have an inset to accommodate a trash receptacle. The inset shall be a minimum 18 square feet.
  8. A driveway that provides four or fewer required parking spaces may be designed with gravel surfacing or using driveway runners. Design and construction must be approved by the Director of the Watershed Protection and Development Review Department. A driveway apron shall comply with City of Austin specifications.
  9. A required or excess parking space may not be located in a street yard. This provision does not apply to property in the West 38<sup>th</sup> Street District or to property located at 4300 or 4307 Speedway if provisions for those areas permit parking in the street yard.
  10. Except as otherwise provided in this section, the entrance of a building in which a principal use is located shall be located on the front of a building.
  11. If a parking facility is located on the ground floor of a building, pedestrian-oriented uses must be located at the front of the building.
  12. Except for a single-family, duplex, or two-family residential use, excess parking is prohibited. This section does not apply to property located at 4300 or 4307 Speedway if excess parking is permitted by the provisions applicable to the property.

13. This section applies to a multifamily use.
  - a. A maximum of one sign is permitted on a building.
  - b. The size of a sign may not exceed one foot in height and eight feet in length.
  - c. Internal lighting of a sign is prohibited except for the internal lighting of individual letters.
  - d. Free-standing signs are prohibited.
14. Alley access is permitted if the access complies with applicable City regulations.
15. Except in the Guadalupe District, this section applies to construction of a single-family, duplex or two-family residential use on property that is located in a townhouse and condominium residence (SF-6) district or less restrictive zoning district. Except as otherwise provided in this section, construction must comply with the regulations for the family residence (SF-3) district. Construction may comply with the regulations of the district in which the use is located if construction complies with the compatibility standards of the City Code.
16. Except as otherwise provided in this section, parking is permitted in a street yard on West 38<sup>th</sup> ½ Street. Parking may not be closer than ten feet to a property line.
17. Except as otherwise provided in this section, the following provisions apply in all Districts except the Guadalupe District.
  - a. A circular driveway is not permitted.
  - b. Except as otherwise provided in the section, access to a site is limited to one curb cut. Except in the Residential District, a site that has 100 feet of frontage or more may have two curb cuts. In the Residential District, a site may have two curb cuts if the site has 100 feet of frontage or more and has two dwelling units. Property located at 4300 Speedway may have 3 curb cuts.
  - c. The width of a driveway:

1. for a residential use, may not exceed 12 feet from the driveway apron to the building setback line and 24 feet from the building setback line to a parking area;
  2. for a commercial, civic, multifamily residential, or condominium residential use, may not exceed 25 feet.
- d. For an existing single-family, duplex, or two-family residential use:
1. compliance with current City parking regulations is required if:
    - a. 200 square feet or more are added to a building floor area;
    - b. the principal use changes; or
    - c. a full bathroom is added to a dwelling unit that has three or more bathrooms; and
  2. a person may not reduce the parking spaces to a number less than the number of spaces prescribed in the City Code.
- e. For property located at 4300 Speedway:
1. the minimum parking requirement is 70 percent of the minimum requirement established by the City Code;
  2. the maximum parking allowed is 100 percent of the minimum requirement established by the City Code;
  3. parking in excess of the maximum allowed is not permitted, provided that excess parking that exists on the effective date of this ordinance may continue as long as not more than 5000 square feet of gross floor area is added to the property; and
  4. off-site parking at 4307 Speedway does not count against the maximum parking allowed at 4300 Speedway.
- f. The design and location of parking facilities located at 4300 and 4307 Speedway is permitted as shown on the survey of the property conducted by Roy D. Smith

Surveyors and dated August 26, 1993, attached to this ordinance as Exhibit "C" and on file with the Director of Neighborhood Planning and Zoning Department in File C14-01-0046.

g. The following provision applies to parking required under Subsection d.

1. Tandem parking:

- a. for a single-family or duplex residential use, is permitted; and
- b. for a multi-family use, is permitted if both spaces are assigned to the same unit.

2. Two parking spaces per dwelling unit are required in the Residential District and the West 38<sup>th</sup> Street District.

h. This subsection applies to property located at 4307 Speedway. Parking is permitted in a street yard for any use if an off-site accessory parking use exists on any part of the property.

**PART 8. RESIDENTIAL DISTRICT.** The following site development regulations apply in the Residential District.

1. Site Development Standards Table. Except as otherwise modified in this part, the following site development regulations apply in the Residential District.

| RESIDENTIAL DISTRICT |                                   |                                 |                                |
|----------------------|-----------------------------------|---------------------------------|--------------------------------|
|                      | Site Development Standards        |                                 |                                |
|                      | Single-family<br>Zoning Districts | Multifamily<br>Zoning Districts | Commercial<br>Zoning Districts |
| Minimum lot<br>size  | 5750                              | 8000                            | 5750                           |
| Minimum lot<br>width | 50                                | 50                              | 50                             |
| Maximum FAR          |                                   | 0.5 to 1                        | 0.5 to 1                       |

|                                    |     |     |     |
|------------------------------------|-----|-----|-----|
| Maximum building coverage          | 40% | 50% | 50% |
| Maximum impervious cover           | 45% | 60% | 70% |
| Maximum height                     | 30  | 30  | 30  |
| Minimum interior side yard setback | 5   | 5   | 5   |
| Minimum rear setback               | 10  | 10  | 10  |

2. Except as otherwise provided in this part, on an avenue, Duval Street, and the south side of West 39<sup>th</sup> Street:
  - a. the minimum street yard setback is 25 feet; and
  - b. the maximum street yard setback is 30 feet.
3. This section applies to a street other than a street identified in Section 2 of this part. Except as otherwise provided in this part, the minimum street yard setback is 15 feet.
4. This section applies to the minimum street yard setback established in Subsection 2.a. of this part.
  - a. The minimum street yard setback may equal the average of the street yard setbacks of the principal buildings on the same side of the block that are 25 feet or less from the street property line. If more than one principal building is located on a property, then the setback of the building closest to the street property line is used in the calculation.
  - b. Notwithstanding any provision in this section, a setback may not be less than five feet.
5. This subsection applies to the street yard setback established in Section 3 of this part.

- a. The street yard setback of the subject property may equal the average of the street yard setbacks of the buildings on adjoining lots if the setbacks are 15 feet or less. In this section, a building across an alley is a building on an adjoining lot. The street yard setback may be established by a principal building or an accessory building that contains a living unit on the ground floor that fronts on the street.
  - b. Notwithstanding any provision in this section, a setback may not be less than five feet.
6. For a building façade that is longer than 50 feet, the façade may not extend horizontally in an unbroken line for more than 30 feet.
7. A two-family residential use is permitted in the Residential District on a lot that is 7000 square feet or larger.
8. Except as provided in Section 9 of this part, a porch may extend:
  - a. on an avenue, a maximum of eight feet in front of the street yard setback; and
  - b. on a street other than an avenue, a maximum of five feet in front of a street yard setback.
9. A porch must be at least five feet from a property line that faces a street.
10. Except as otherwise provided in Sections 13 and 14 in this part, for an accessory building the minimum setback from:
  - a. a property line facing an avenue, Duval Street, or the south side of West 39<sup>th</sup> Street is 60 feet;
  - b. a property line facing a street other than a street identified in Subsection a. of this section is 15 feet; and
  - c. an interior side property line is five feet.
11. Except as otherwise provided in Section 12, 13, and 14 of this part, the minimum setback from a rear property line for an accessory building that is not more than 30 feet in height, is five feet.



12. Section 11 of this part does not apply to a through lot.
13. An attached or detached garage that has vehicular access on an alley or street shall be set back at least 20 feet from the alley or street.
14. A non-complying accessory building may be reconstructed at its existing location, but may not be less than three feet from the rear and interior and street side property lines.
15. An attached garage shall be a minimum of 60 feet from the property line facing an avenue, Duval Street, or the south side of West 39<sup>th</sup> Street.
16. This section applies to a duplex or two-family residential use if there are at least five bathrooms in all buildings in which the use is located. An additional parking space is required for each new full bathroom constructed on the property.
17. Driveway runners or gravel driveways are permitted. The design and construction must be approved by the Director of the Watershed Protection and Development Review Department.

**PART 9. SPEEDWAY DISTRICT.** The following provisions apply in the Speedway District.

1. Site Development Standards Table. Except as otherwise modified in this part, the following site development regulations apply in the Speedway District.

| SPEEDWAY DISTRICT         |                            |   |
|---------------------------|----------------------------|---|
|                           | SITE DEVELOPMENT STANDARDS |   |
|                           | SF-3 Zoning District       | Multifamily & Commercial Zoning Districts |
| Minimum lot size          | 5750                       | 8000                                      |
| Minimum lot width         | 50                         | 50  |
| Maximum FAR               | --                         | 0.5 to 1                                  |
| Maximum building coverage | 40%                        | 50%                                       |

|                                       |     |                          |
|---------------------------------------|-----|--------------------------|
| Maximum impervious cover              | 50% | 70% MF<br>80% commercial |
| Maximum height                        | 30  | 30                       |
| Minimum interior side yard<br>Setback | 5   | 5                        |
| Minimum rear setback                  | 10  | 10                       |

2. Except as otherwise provided in this part, on Speedway:
  - a. the minimum street yard setback is 25 feet; and
  - b. the maximum street yard setback is 30 feet.
3. This section applies to a street other than Speedway. Except as otherwise provided in this part, the minimum street yard setback is 15 feet.
4. This section applies to the minimum street yard setback established in Subsection 2.a. of this part.
  - a. The minimum street yard setback may equal the average of the street yard setbacks of the principal buildings on the same side of the block that are 25 feet or less from the street property line. If more than one principal building is located on a property, then the setback of the building closest to the street property line is used in the calculation.
  - b. Notwithstanding any provision in this section, a setback may not be less than five feet.
5. This subsection applies to the street yard setback established in Section 3 of this part.
  - a. The street yard setback of the subject property may equal the average of the street yard setbacks of the buildings on adjoining lots if the setbacks are 15 feet or less. In this section, a building across an alley is a building on an adjoining lot. The street yard setback may be established by a principal building or an accessory building that contains a living unit on the ground floor that fronts on the street.

- b. Notwithstanding any provision in this section, a setback may not be less than five feet.
6. The following site development regulations apply to property located at 4300 Speedway.
- a. The maximum floor-to-area ratio is 0.75 to 1.
  - b. Except as otherwise provided in this subsection, the maximum height is 30 feet. A building may have a height of 36 feet if the building has a pitched roof, measured to the average height of the highest gable.
  - c. There is not a maximum street yard setback on Speedway. There is not a street yard setback on West 43<sup>rd</sup> Street. There is not an interior side yard or rear yard setback.
  - d. The maximum impervious cover is 80 percent.
  - e. The maximum building coverage is 55 percent.
  - f. Chapter 25-2, Subchapter C, Article 10 (*Compatibility Standards*) of the City Code does not apply to the modification of the structure that exists at 4300 Speedway on the effective date of this ordinance if:
    - 1. 5000 square feet of gross floor area or less is added to the structure; and
    - 2. the modifications are permitted for noncomplying structures under Section 25-2-963 (*Modifications and Maintenance of Noncomplying Structures*) of the City Code.
7. There is not a minimum or maximum street yard setback on Speedway for an off-site accessory parking use on property located at 4307 Speedway.
8. A duplex or two-family residential use is permitted on a lot that is 6000 square feet or larger.
9. Except as provided in Section 10 of this part, a porch may extend:
- a. on Speedway, a maximum of ten feet in front of the street [~~front~~] yard setback; and

- b. on a street other than Speedway, a maximum of five feet in front of the street yard setback.
- 10. A porch must be at least five feet from a property line that faces a street.
- 11. Except as otherwise provided in Sections 14 and 15 in this part, for an accessory building, the minimum setback from:
  - a. a property line facing Speedway is 60 feet;
  - b. a property line facing a street other than Speedway is 15 feet; and
  - c. an interior side property line is five feet.
- 12. Except as otherwise provided in Section 13, 14, and 15 of this part, the minimum setback from a rear property line for an accessory building that is not more than 30 feet in height is five feet.
- 13. Section 12 of this part does not apply to a through lot.
- 14. An attached or detached garage that has vehicular access on an alley or street must be set back at least 20 feet from the alley or street.
- 15. A non-complying accessory building may be reconstructed at its existing location, but may not be less than three feet from the rear and interior and street side property lines.
- 16. An attached garage shall be a minimum of 60 feet from a property line facing Speedway.
- 17. This section applies to a duplex or two-family residential use if there are at least five bathrooms in all buildings in which the use is located. An additional parking space is required for each new full bathroom constructed on the property.
- 18. Driveway runners and gravel surfacing driveways are permitted. Design and construction must be approved by the Director of the Watershed Protection and Development Review Department.

19. This section applies to a restaurant use at 4300 Speedway that provides outdoor seating.
- a. The outdoor seating area does not count against the allowable square footage for a restaurant (limited) and restaurant (general) use established in Part 6, Subsection 2.g. of this ordinance and is not used to determine the parking requirement if:
    1. the outdoor seating does not exceed 40 percent of the total seating; and
    2. not more than 10 tables are located outside.
  - b. The outdoor seating area that exceeds 40 percent of the total seating area is counted as part of the allowable square footage for a restaurant (limited) and restaurant (general) use and shall be used to determine the parking requirement.

**PART 10. DUVAL DISTRICT.** The following provisions apply in the Duval District.

1. Site Development Standards Table. Except as otherwise modified in this part, the following site development regulations apply in the Duval District.

| DUVAL DISTRICT            |                            |   |
|---------------------------|----------------------------|---|
|                           | SITE DEVELOPMENT STANDARDS |   |
|                           | SF-3 Zoning District       | Multifamily & Commercial Zoning Districts |
| Minimum lot size          | 5750                       | 8000                                      |
| Minimum lot width         | 50                         | 50  |
| Maximum FAR               |                            | 0.5 to 1                                  |
| Maximum building coverage | 40%                        | 50%                                       |
| Maximum impervious cover  | 50%                        | 60% MF<br>80% commercial                  |
| Maximum height            | 30                         | 30  |

|                                       |    |    |
|---------------------------------------|----|----|
| Minimum interior side yard<br>Setback | 5  | 5  |
| Minimum rear setback                  | 10 | 10 |

2. Except as otherwise provided in this part, on Duval Street and Avenue H:
  - a. the minimum street yard setback is 25 feet; and
  - b. the maximum street yard setback is 30 feet.
3. This section applies to a street other than a street identified in Section 2 of this part. Except as otherwise provided in this part, the minimum street yard setback is 15 feet.
4. This section applies to the minimum street yard setback established in Subsection 2.a. of this part.
  - a. The minimum street yard setback may equal the average of the street yard setbacks of the principal buildings on the same side of the block that are 25 feet or less from the street property line. If more than one principal building is located on a property, then the setback of the building closest to the street property line is used in the calculation.
  - b. Notwithstanding any provision in this section, a setback may not be less than five feet.
5. This subsection applies to the street yard setback established in Section 3 of this part.
  - a. The street yard setback of the subject property may equal the average of the street yard setbacks of the buildings on adjoining lots if the setbacks are 15 feet or less. In this section, a building across an alley is a building on an adjoining lot. The street yard setback may be established by a principal building or an accessory building that contains a living unit on the ground floor that fronts on the street.
  - b. Notwithstanding any provision in this section, a setback may not be less than five feet.



6. A duplex or two-family use is permitted on a lot that is 5900 square feet or larger.
7. Except as provided in Section 8 of this part, a porch may extend:
  - a. on an avenue, a maximum of eight feet in front of the street yard setback; and
  - b. on a street other than an avenue, a maximum of five feet in front of a street yard setback.
8. A porch must be at least five feet from a property line that faces a street.
9. Except as otherwise provided in Sections 12 and 13 in this part, for an accessory building the minimum setback from:
  - a. a property line facing Duval Street or Avenue H is 60 feet;
  - b. a property line facing a street other than Duval Street and Avenue H is 15 feet; and
  - c. an interior side property line is five feet.
10. Except as otherwise provided in Section 11, 12, and 13 of this part, the minimum setback from a rear property line for an accessory building that is not more than 30 feet in height is five feet.
11. Section 10 of this part does not apply to a through lot.
12. An attached or detached garage that opens on an alley or street must be set back at least 20 feet from the alley or street.
13. A non-complying accessory building may be reconstructed at its existing location but may not be less than three feet from the rear and interior and street side property lines.
14. An attached garage:
  - a. shall be a minimum of 60 feet from a property line facing Duval Street or Avenue H; and
  - b. may not face Duval Street or Avenue H.

15. This section applies to a restaurant use that provides outdoor seating.
  - a. The outdoor seating area is not used to determine the parking requirement if:
    1. the outdoor seating does not exceed 40 percent of the total seating; and
    2. not more than 10 tables are located outside.
  - b. The outdoor seating area that exceeds 40 percent of the total seating area shall be used to determine the parking requirement.

**PART 11. WEST 38<sup>TH</sup> STREET DISTRICT.** The following provisions apply in the West 38<sup>th</sup> Street District.

1. Site Development Standards Table. Except as otherwise modified in this part, the following site development regulations apply in the West 38<sup>th</sup> Street District.

| WEST 38 <sup>TH</sup> STREET DISTRICT |   |                                |
|---------------------------------------|---|--------------------------------|
|                                       | SITE DEVELOPMENT STANDARDS                                |                                |
|                                       | All Residential<br>Zoning Districts                       | Commercial<br>Zoning Districts |
| Minimum lot size                      | 5750 SF residential<br>6000 two-family, duplex<br>8000 MF | 5750                           |
| Minimum lot width                     | 50  | 50                             |
| Maximum FAR                           | 0.6 to 1 MF   | 0.6 to 1                       |
| Maximum building coverage             | 45% SF<br>55% MF  | 55%                            |
| Maximum impervious cover              | 50% SF<br>70% MF  | 70%                            |
| Maximum height                        | 30  | 30                             |

|                                    |    |    |
|------------------------------------|----|----|
| Minimum interior side yard Setback | 5  | 5  |
| Minimum rear setback               | 10 | 10 |

2. On 38<sup>th</sup> Street, 38<sup>th</sup> ½ Street, and Avenue B, the minimum street yard setback is 25 feet.
3. On 38<sup>th</sup> Street and 38<sup>th</sup> ½ Street, the maximum street yard setback is 50 feet.
4. On Avenue B, the maximum street yard setback is 30 feet.
5. In a neighborhood office (NO) district:
  - a. floor-to-area ratio is 0.35 to 1;
  - b. maximum impervious cover is 60%; and
  - c. maximum building coverage is 45%.
6. In a general office (GO) district:
  - a. maximum impervious coverage is 80%; and
  - b. maximum building coverage is 60%.
7. A parking area may be located at ground level under a building if the parking area is screened from the street.
8. A building may be 40 feet in height if the following is provided:
  - a. a screened ground level parking area below the building, and
  - b. a minimum of one tree at least every 12 feet the width of the landscape yard.
9. An attached or detached garage that has vehicular access on an alley shall be set back at least 20 feet from the alley.

**PART 12. GUADALUPE DISTRICT.** The following provisions apply in the Guadalupe District.

1. Site Development Standards Table. Except as otherwise modified in this part, the following site development regulations apply in the Guadalupe District.

| GUADALUPE DISTRICT                 |  |
|------------------------------------|--|
|                                    | SITE DEVELOPMENT STANDARDS<br>ALL USES |
| Minimum lot size                   | 4000                                   |
| Minimum lot width                  | 25                                     |
| Maximum FAR                        | 2 to 1                                 |
| Maximum building coverage          | 95%                                    |
| Maximum impervious cover           | 95%                                    |
| Minimum interior side yard setback | 0                                      |
| Minimum rear setback               | 10                                     |

2. On Guadalupe Street:
  - a. the minimum street yard setback is 0 feet; and
  - b. the maximum street yard setback is 10 feet.
3. On a street other than Guadalupe Street, the minimum street yard setback is ten feet.

4. The maximum height:
  - a. on property north of 40<sup>th</sup> Street is 40 feet; and
  - b. on property south of 40<sup>th</sup> Street is 60 feet.
5. This section applies to property north of 40<sup>th</sup> Street. A building that is 30 feet or less from the rear property line may not exceed 30 feet in height. A parapet wall may exceed the height established in this part by 10 percent.
6. A sidewalk sign is permitted. Section 25-10-153 (*Sidewalk Sign in Downtown Sign District*) applies to a sidewalk sign. A projecting sign is permitted. Section 25-10-129 (*Downtown Sign District Regulations*) applies to a projecting sign.
7. This section applies to a restaurant use that provides outdoor seating.
  - a. The outdoor seating area is not used to determine the parking requirement if:
    1. the outdoor seating does not exceed 40 percent of the total seating; and
    2. not more than 10 tables are located outside.
  - b. The outdoor seating area that exceeds 40 percent of the total seating area shall be used to determine the parking requirement.
8. Chapter 25-2, Subchapter C, Article 10 (*Compatibility Standards*) of the City Code does not apply to the rear yard setback established in Section 1 of this part. Parking is permitted in the rear setback.


**PART 13.** The Council waives the requirements of Section 2-2-3, 2-2-5, and 2-2-7 of the City Code for this ordinance.

**PART 14.** The Council finds that the ambiguity concerning the appropriate development regulations to be applied to the Hyde Park neighborhood combining district should finally be resolved in an expeditious manner because the issue has been debated too long, which constitutes an emergency. Because of this emergency, this ordinance takes effect immediately on the passage for the immediate preservation of the public peace, health and safety.

**PASSED AND APPROVED**


\_\_\_\_\_, January 31, 2002

§  
§  
§




Gustavo L. Garcia  
Mayor

APPROVED:

  
Sedora Jefferson  
City Attorney

ATTEST:

  
Shirley A. Brown  
City Clerk





SUBJECT TRACT  
PENDING CASE  
ZONING BOUNDARY  
CASE MGR: C.WILLIAMS

CASE #: C14-01-0046  
ADDRESS: HYDE PARK NCCD  
SUBJECT AREA (acres): N/A

ZONING EXHIBIT A  
pg 1 of 2  
DATE: 02-02  
INTLS: TRC

CITY GRID  
REFERENCE  
NUMBER  
J25,26 K25,2  
6



EXHIBIT A - pg. 2 of 2




Proposed Hyde Park Neighborhood Conservation Combining District  
Proposed Base District Zoning Changes

REC 50  
Passed April 2001

See attached chart for zoning recommendations.


This map is intended to provide a visual representation of the proposed zoning changes. It is not a legal document and should not be used for legal purposes. For more information, please contact the City of Chicago Planning Department.





Hyde Park Neighborhood Plan  
 Proposed Hyde Park Neighborhood Conservation Combining District  
 Proposed Subdistricts of the Hyde Park NCCD

EXHIBIT B



PEC30  
 Printed: April 2001

Proposed Hyde Park NCCD

Residential District

Speedway District

W. 38th District

Guadalupe District

Duval District

Hyde Park Civic NCCD  
 (Hyde Park Baptist Church  
 - Civic District)

This map has been produced by the City of Austin as a working map and is not intended for any other use. No warranty is made by the City of Austin regarding the accuracy or completeness. Reproductions are not permitted without prior written permission from Planning, Environmental & Conservation Services Dept., City of Austin.

SURVEY PLAT OF LOTS 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, BLOCK 14  
AND LOTS 7, 8, 9, 10, 11, BLOCK 15, HYDE PARK ADDITION, A SUBDIVISION  
IN THE CITY OF AUSTIN, TRAVIS COUNTY, TEXAS AS RECORDED IN PLAT  
BOOK 1, PAGE 67 OF THE PLAT RECORDS OF TRAVIS COUNTY, TEXAS.

SCALE 1" = 20'

# LEGEND

- Station Markers
- Iron Bolt Marker
- Utility Pole
- Overhead Power Line
- Lighted Light Pole
- Wood Guard Fence
- Chain Link Fence
- Iron Bolt
- Overhead Telephone Line
- Record Plat Data

## RESTRICTIONS NOTES:

The subject properties shown herein are subject to the restrictive covenants recorded in the following instruments: Volume 117, Page 210; Volume 118, Page 255; Volume 119, Page 252 and Volume 120, Page 255. All of the above mentioned instruments recorded in Volume 117, Page 210; Volume 118, Page 255 and Volume 119, Page 252 and those recorded in Volume 120, Page 255, all of the said records of Travis County, Texas.

To: Correction Interest, Inc.,  
Clary J. Brown, President  
Title Agency of Austin, Tex.  
Placing Stationing and Surveying Company

The undersigned do hereby certify that this survey was this day made on the ground of the property legally described herein and is correct and that there are no visible discrepancies, dead line encroachments, overlapping of improvements, visible utility easements or encroachments, except as shown herein and that said property has frontage on a public roadway, except as shown herein.

To the line holders and/or the owners of the premises surveyed.

The property described herein is not within the boundaries of the 100 Year Flood Plain as identified by the National Flood Insurance Program Flood Insurance Rate Map for the City of Austin, Travis County, Texas dated September 2, 1981, Panel No. 0015-0.

SURVEYED BY  
ROY D. SMITH SURVEYORS  
Copyright 1982




*Roy D. Smith*  
ROY D. SMITH  
Registered Professional Surveyor  
1214 West 4th Street  
Austin, Texas 78701  
PH. (512) 262-3000

*Not properly shown  
the above line  
to the north of  
the lot 17/18*

*Section  
marked  
from 17/18 to  
19/20  
from 20/21 to  
22/23*

EXHIBIT C



WEST 43RD STREET (W. Side) Asphalt Road

## EXHIBIT I

### ORDINANCE NO. 20120112-086

**AN ORDINANCE AMENDING ORDINANCE NO. 20020131-20, REZONING AND CHANGING THE ZONING MAP FOR THE PROPERTY WHOSE BOUNDARIES ARE EAST 45<sup>TH</sup> STREET TO THE NORTH, 38<sup>TH</sup> STREET TO THE SOUTH, GUADALUPE STREET TO THE WEST AND DUVAL STREET TO THE EAST, IN THE HYDE PARK NCCD-NP AREA FROM NEIGHBORHOOD CONSERVATION-NEIGHBORHOOD PLAN (NCCD-NP) COMBINING DISTRICT TO NEIGHBORHOOD CONSERVATION-NEIGHBORHOOD PLAN (NCCD-NP) COMBINING DISTRICT, TO CHANGE A CONDITION OF ZONING.**

#### **BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF AUSTIN:**

**PART 1.** The zoning map established by Section 25-2-191 of the City Code is amended to change the base district from neighborhood conservation-neighborhood plan (NCCD-NP) combining district to neighborhood conservation-neighborhood plan (NCCD-NP) combining district on the property (the "Property") whose boundaries are East 45<sup>th</sup> Street to the north, 38<sup>th</sup> Street to the south, Guadalupe Street to the west, and Duval Street to the east, as described in Zoning Case No. C14-01-0046.01 and as more particularly identified in the map attached as Exhibit "A," SAVE AND EXCEPT Lots 5 through 16 of Block 12 of the Hyde Park Addition No. 1.

**PART 2.** The Hyde Park NCCD-NP was approved January 31, 2002 under Ordinance No. 020131-20 (the "Original Ordinance") and amended under Ordinance No. 20080605-062. The Hyde Park Local Historic district was established for a portion of the NCCD under Zoning Case C14H-2010-0019 and those properties must comply with the Preservation Plan and Design Standards set forth in Ordinance No. 20101216-93 as well as the Original Ordinance, as amended.

**PART 3.** Except as otherwise provided in this ordinance the Property is subject to the Original Ordinance, as amended, and in all other respects, the terms and conditions of the Original Ordinance, as amended, remain in full force and effect.

**PART 4.** Part 7 (*General Provisions*) of The Ordinance is amended to change a condition of zoning for certain property in the Hyde Park NCCD-NP area as shown in this ordinance.

Part 7. (*General Provisions*) Except as otherwise provided in Part 5 and Part 8 of this ordinance, or in this part, the following provisions apply to all property within the NCCD-NP.

1. Except as otherwise provided, a building shall front on a north-south street. A building located on a lot that only has frontage on a numbered street may front on the numbered street. A building on a through lot located west of Speedway on West 38<sup>th</sup> Street or West 39<sup>th</sup> Street shall front on West 38<sup>th</sup> Street or West 39<sup>th</sup> Street. The street on which a building fronts under this section is the front of the property on which the building is located for purposes of this ordinance.
2. This section applies to a property that is redeveloped for multifamily, commercial or civic use.
  - a. A site for a dumpster shall be provided on the property. The dumpster shall be screened from the view of adjacent property.
  - b. Except as otherwise provided in this subsection, each parking space shall be independently accessible. For a multifamily use, tandem parking is permitted if the spaces are assigned to one dwelling unit.
3. Except as otherwise provided in this section, the maximum gross floor area of the rear dwelling unit of a two-family residential use is 850 square feet. On a corner lot, the rear dwelling unit may exceed 850 square feet if the following conditions and other applicable site development regulations are satisfied:
  - a. living space is provided on the ground floor;
  - b. one unit has frontage on an north-south street; and
  - c. one unit has frontage on a numbered street.
4. Accessory buildings may not exceed 10 percent of the site area.
5. A fence located in a front yard may not exceed a height of four feet and shall have a ratio of open space to solid material of not less than 1 to 1.5.
6. This section applies to a fence located in a street side yard that faces an avenue and is greater than four feet in height. The portion of a fence that is greater than four feet shall have a ratio of open space to solid material of not less than 1 to 1.5.



7. A fence located along an alley shall have an inset to accommodate a trash receptacle. The inset shall be a minimum 18 square feet.
8. A driveway that provides four or fewer required parking spaces may be designed with gravel surfacing or using driveway runners. Design and construction must be approved by the Director of the Watershed Protection and Development Review Department. A driveway apron shall comply with City of Austin specifications.
9. A required or excess parking space may not be located in a street yard. This provision does not apply to property in the West 38<sup>th</sup> Street District or to property located at 4300 or 4307 Speedway if provisions for those areas permit parking in the street yard.
10. Except as otherwise provided in this section, the entrance of a building in which a principal use is located shall be located on the front of a building.
11. If a parking facility is located on the ground floor of a building, pedestrian-oriented uses must be located at the front of the building.
12. Except for a single-family, duplex, or two-family residential use, excess parking is prohibited. This section does not apply to property located at 4300 or 4307 Speedway if excess parking is permitted by the provisions applicable to the property.
13. This section applies to a multifamily use.
  - a. A maximum of one sign is permitted on a building.
  - b. The size of a sign may not exceed one foot in height and eight feet in length.
  - c. Internal lighting of a sign is prohibited except for the internal lighting of individual letters.
  - d. Free-standing signs are prohibited.
14. Alley access is permitted if the access complies with applicable City regulations.

15. Except in the Guadalupe District, this section applies to construction of a single-family, duplex or two-family residential use on property that is located in a townhouse and condominium residence (SF-6) district or less restrictive zoning district. Except as otherwise provided in this section, construction must comply with the regulations for the family residence (SF-3) district. Construction may comply with the regulations of the district in which the use is located if construction complies with the compatibility standards of the City Code.
16. Except as otherwise provided in this section, parking is permitted in a street yard on West 38<sup>th</sup> ½ Street. Parking may not be closer than ten feet to a property line.
17. Except as otherwise provided in this section, the following provisions apply in all Districts except the Guadalupe District.
  - a. A circular driveway is not permitted.
  - b. Except as otherwise provided in the section, access to a site is limited to one curb cut. Except in the Residential District, a site that has 100 feet of frontage or more may have two curb cuts. In the Residential District, a site may have two curb cuts if the site has 100 feet of frontage or more and has two dwelling units. Property located at 4300 Speedway may have 3 curb cuts.
  - c. The width of a driveway:
    1. for a residential use, may not exceed 12 feet from the driveway apron to the building setback line and 24 feet from the building setback line to a parking area;
    2. for a commercial, civic, multifamily residential, or condominium residential use, may not exceed 25 feet.
  - d. For an existing single-family, duplex, or two-family residential use:
    1. compliance with current City parking regulations is required if:

- a. 200 square feet or more are added to a building floor area;
  - b. the principal use changes; or
  - c. a full bathroom is added to a dwelling unit that has three or more bathrooms; and
- 2. a person may not reduce the parking spaces to a number less than the number of spaces prescribed in the City Code.
- e. For property located at 4300 Speedway:
  - 1. the minimum parking requirement is 70 percent of the minimum requirement established by the City Code;
  - 2. the maximum parking allowed is 100 percent of the minimum requirement established by the City Code;
  - 3. parking in excess of the maximum allowed is not permitted, provided that excess parking that exists on the effective date of this ordinance may continue as long as not more than 5000 square feet of gross floor area is added to the property; and
  - 4. off-site parking at 4307 Speedway does not count against the maximum parking allowed at 4300 Speedway.
- f. The design and location of parking facilities located at 4300 and 4307 Speedway is permitted as shown on the survey of the property conducted by Roy D. Smith Surveyors and dated August 26, 1993, attached to this ordinance as Exhibit "C" and on file with the Director of Neighborhood Planning and Zoning Department in File C14-01-0046.
- g. The following provision applies to parking required under Subsection d.
  - 1. Tandem parking:
    - a. for a single-family or duplex residential use, is permitted; and

- b. for a multi-family use, is permitted if both spaces are assigned to the same unit.
- 2. Two parking spaces per dwelling unit are required in the Residential District and the West 38<sup>th</sup> Street District.
- h. This subsection applies to property located at 4307 Speedway. Parking is permitted in a street yard for any use if an off-site accessory parking use exists on any part of the property.

18. The maximum floor to-area-ratio (FAR) for property subject to the City of Austin Land Development Code, Subchapter F, Article 2, (Development Standards) Section 2.1 (Maximum Development Permitted), is 0.4 to 1.0, except for 511 West 41<sup>st</sup> Street, and specifically applies to single family zoning district properties in the Residential District and is reflected in the Site Development Table in Part 8 of this ordinance.

**PART 8. RESIDENTIAL DISTRICT.** The following site development regulations apply in the Residential District.

- 1. Site Development Standards Table. Except as otherwise modified in this part, the following site development regulations apply in the Residential District.

| RESIDENTIAL DISTRICT      |                                   |                                 |                                |
|---------------------------|-----------------------------------|---------------------------------|--------------------------------|
|                           | Site Development Standards        |                                 |                                |
|                           | Single-family<br>Zoning Districts | Multifamily<br>Zoning Districts | Commercial<br>Zoning Districts |
| Minimum lot size          | 5750                              | 8000                            | 5750                           |
| Minimum lot width         | 50                                | 50                              | 50                             |
| Maximum FAR               | <u>0.4 to 1 *</u>                 | 0.5 to 1                        | 0.5 to 1                       |
| Maximum building coverage | 40%                               | 50%                             | 50%                            |
| Maximum impervious cover  | 45%                               | 60%                             | 70%                            |

|  |    |    |    |
|--|----|----|----|
| Maximum height                                     | 30 | 30 | 30 |
| Minimum interior side yard setback                 | 5  | 5  | 5  |
| Minimum rear setback                               | 10 | 10 | 10 |
| <u>*does not apply to 511 W 41<sup>st</sup> St</u> |    |    |    |

2. Except as otherwise provided in this part, on an avenue, Duval Street, and the south side of West 39<sup>th</sup> Street:
  - a. the minimum street yard setback is 25 feet; and
  - b. the maximum street yard setback is 30 feet.
3. This section applies to a street other than a street identified in Section 2 of this part. Except as otherwise provided in this part, the minimum street yard setback is 15 feet.
4. This section applies to the minimum street yard setback established in Subsection 2.a. of this part.
  - a. The minimum street yard setback may equal the average of the street yard setbacks of the principal buildings on the same side of the block that are 25 feet or less from the street property line. If more than one principal building is located on a property, then the setback of the building closest to the street property line is used in the calculation.
  - b. Notwithstanding any provision in this section, a setback may not be less than five feet.
5. This subsection applies to the street yard setback established in Section 3 of this part.
  - a. The street yard setback of the subject property may equal the average of the street yard setbacks of the buildings on adjoining lots if the setbacks

are 15 feet or less. In this section, a building across an alley is a building on an adjoining lot. The street yard setback may be established by a principal building or an accessory building that contains a living unit on the ground floor that fronts on the street.

- b. Notwithstanding any provision in this section, a setback may not be less than five feet.
6. For a building façade that is longer than 50 feet, the façade may not extend horizontally in an unbroken line for more than 30 feet.
  7. A two-family residential use is permitted in the Residential District on a lot that is 7000 square feet or larger.
  8. Except as provided in Section 9 of this part, a porch may extend:
    - a. on an avenue, a maximum of eight feet in front of the street yard setback; and
    - b. on a street other than an avenue, a maximum of five feet in front of a street yard setback.
  9. A porch must be at least five feet from a property line that faces a street.
  10. Except as otherwise provided in Sections 13 and 14 in this part, for an accessory building the minimum setback from:
    - a. a property line facing an avenue, Duval Street, or the south side of West 39<sup>th</sup> Street is 60 feet;
    - b. a property line facing a street other than a street identified in Subsection a. of this section is 15 feet; and
    - c. an interior side property line is five feet.
  11. Except as otherwise provided in Section 12, 13, and 14 of this part, the minimum setback from a rear property line for an accessory building that is not more than 30 feet in height, is five feet.



12. Section 11 of this part does not apply to a through lot.
13. An attached or detached garage that has vehicular access on an alley or street shall be set back at least 20 feet from the alley or street.
14. A non-complying accessory building may be reconstructed at its existing location, but may not be less than three feet from the rear and interior and street side property lines.
15. An attached garage shall be a minimum of 60 feet from the property line facing an avenue, Duval Street, or the south side of West 39<sup>th</sup> Street.
16. This section applies to a duplex or two-family residential use if there are at least five bathrooms in all buildings in which the use is located. An additional parking space is required for each new full bathroom constructed on the property.
17. Driveway runners or gravel driveways are permitted. The design and construction must be approved by the Director of the Watershed Protection and Development Review Department.
18. The following applies to a two-family use located at 511 West 41<sup>st</sup> Street:
  - a. The minimum lot area is 5,900 square feet.
  - b. A two-family residential use is permitted on a lot that is 5,900 square feet or larger.
  - c. The maximum building coverage is 55 percent.
  - d. For a two-family residential use, the maximum floor-to-area ratio (FAR) is 0.5 to 1.0.
  - e. The maximum impervious cover is 91 percent.
  - f. The minimum setbacks are as follows:
    - i. the front setback is 0 feet;
    - ii. the rear setback is five feet;

- iii. the east interior side yard setback is 10 feet; and
  - iv. the west alley setback is 0 feet.
- 
- g. The second dwelling unit on the eastern portion of the property is limited to a maximum of 750 square feet and two bedrooms.
  - h. Part 8 10(b) does not apply to the second dwelling unit. Its front setback from 41<sup>st</sup> Street may equal that of the principal building.
  - i. The maximum number of parking spaces is five. For a residential use, two parking spaces per dwelling unit are allowed; for a commercial use, one space per 1200 sq. ft. is allowed.
  - j. The width of a driveway must be greater than 10 feet in width but less than 15 feet.
  - k. The provisions under Subchapter F, Section 2.7 (*Sidewall Articulation*) and Section 3.1 (*Buildable Area*) do not apply along the west property line abutting the existing alley.
  - l. Part 7.2.a and Part 7.17.b do not apply to the property at 511 West 41st Street.
  - m. Par 7.4 is modified to allow an accessory building a maximum of 15 percent of site area.

**PART 5.** This ordinance takes effect on January 23, 2012.

**PASSED AND APPROVED**

January 12, 2012 §  
Lee Leffingwell  
Mayor

**APPROVED:** Karen M. Kennard  
City Attorney

**ATTEST:** Shirley A. Gentry  
City Clerk



## **EXHIBIT J**

### **ORDINANCE NO. 20101216-093**

**AN ORDINANCE REZONING AND CHANGING THE ZONING MAP TO ESTABLISH THE HYDE PARK LOCAL HISTORIC DISTRICT FOR THE PROPERTY LOCALLY KNOWN AS THE PROPERTIES GENERALLY BOUNDED BY WEST 45<sup>TH</sup> ON THE NORTH, WEST 38<sup>TH</sup> STREET ON THE SOUTH, AVENUE A ON THE WEST AND DUVAL STREET ON THE EAST IN THE HYDE PARK NEIGHBORHOOD CONSERVATION AREA.**

#### **BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF AUSTIN:**

**PART 1.** The zoning map established by Section 25-2-191 of the City Code is amended to add a historic area (HD) combining district to each base zoning district within the property (the "Property") described in Zoning Case No. C14H-2010-0019, on file at the Planning and Development Review Department, as follows:

All lots fronting on Avenue A from 40<sup>th</sup> Street to 43<sup>rd</sup> Street;

All lots fronting on Avenue B from 39<sup>th</sup> Street to 45<sup>th</sup> Street;

All lots fronting on Avenue C from 39<sup>th</sup> Street to 45<sup>th</sup> Street;

All lots fronting on Avenue D from 39<sup>th</sup> Street to 45<sup>th</sup> Street;

All lots fronting on Speedway from 38<sup>th</sup> Street to 45<sup>th</sup> Street with the exception of those lots on the west side of Speedway from 38 ½ Street to 40<sup>th</sup> Street and those lots on the east side of Speedway from 39<sup>th</sup> Street to 40<sup>th</sup> Street;

All lots fronting on Avenue F from 38<sup>th</sup> Street to 45<sup>th</sup> Street with the exception of those lots on the west side of Avenue F from 39<sup>th</sup> Street to 40<sup>th</sup> Street;

All lots fronting on Avenue G from 38<sup>th</sup> Street to 45<sup>th</sup> Street;

All lots fronting on Avenue H from 38<sup>th</sup> Street to 45<sup>th</sup> Street with the exception of those lots on the east side of Avenue H from 39<sup>th</sup> Street to 40<sup>th</sup> Street;

All lots fronting on the west side of Duval Street from 38<sup>th</sup> Street to 45<sup>th</sup> Street with the exception of those lots on the west side of Duval Street from 39<sup>th</sup> Street to 40<sup>th</sup> Street;



All lots fronting the north side of 38<sup>th</sup> Street from Speedway to Duval Street;

All lots fronting the south side of 39<sup>th</sup> Street from the intersection of Avenue C to the north-south alley between Avenue C and Avenue D;

All lots fronting on the south side of 39<sup>th</sup> Street between Speedway and Avenue F;

All lots fronting on 39<sup>th</sup> Street from Avenue F to Avenue H;

All lots fronting on the south side of 39<sup>th</sup> Street between Avenue H and Duval Street;

All lots fronting on 40<sup>th</sup> Street from the north-south alley between Guadalupe Street and Avenue A to the north-south alley running between Avenue D and Speedway;

All lots fronting on the north side of 40<sup>th</sup> Street from the north-south alley between Avenue D and Avenue F;

All lots fronting on 40<sup>th</sup> Street from Avenue F to Duval Street, with the exception of the lots on the south side of 40<sup>th</sup> Street between Avenue H and Duval Street;

All lots fronting on 41<sup>st</sup> Street between the north-south alley between Guadalupe Street and Avenue A and the west side of Duval Street;

All lots fronting on 42<sup>nd</sup> Street between the north-south alley between Guadalupe Street and Avenue A and the west side of Duval Street;

All lots fronting on 43<sup>rd</sup> Street between the north-south alley between Guadalupe Street and Avenue A and the west side of Duval Street with the exception of the lots fronting on the north side of 43<sup>rd</sup> Street between the north-south alley between Guadalupe Street and Avenue A and the north-south alley between Avenue A and Avenue B;

All lots fronting on 44<sup>th</sup> Street between the north-south alley between Avenue A and Avenue B and the west side of Duval Street; and,

All lots fronting the south side of 45<sup>th</sup> Street between the north-south alley between Avenue A and Avenue B and the west side of Duval Street.

generally known as the Hyde Park Local Historic District, in the City of Austin, Travis County, Texas, and identified in the map attached as Exhibit "A".

**PART 2.** The properties within Hyde Park Local Historic District are more particularly described and identified as to their contributing (C) and noncontributing (NC) status in the chart attached as Exhibit "B".

**PART 3.** Except as specifically provided in Part 4 and Part 5 of this ordinance, the Property may be developed and used in accordance with the regulations established for the respective base districts, and other applicable requirements of the City Code.

**PART 4.** The Property identified as the Hyde Park Local Historic District must comply with the Preservation Plan and Design Standards as set forth in Exhibit "C" attached and incorporated to this ordinance.

**PART 5.** The Property is subject to Ordinance No. 020131-20 that established the Hyde Park neighborhood conservation combining district.

**PART 6.** This ordinance takes effect on December 27, 2010.

**PASSED AND APPROVED**


December 16, 2010

§  
§  
§




Lee Leffingwell  
Mayor

APPROVED:




Karen M. Kennard  
Acting City Attorney

ATTEST:




Shirley A. Gentry  
City Clerk





# HISTORIC ZONING EXHIBIT A

ZONING CASE#: C14H-2010-0019  
 ADDRESS: GENERALLY 38TH ST TO 45TH ST &  
 AVENUE A TO DUVAL ST  
 GRID: J25  
 MANAGER: STEVE SADOWSKY



This map has been produced by the Communications Technology Management Dept. on behalf of the Planning Development Review Dept. for the sole purpose of geographic reference. No warranty is made by the City of Austin regarding specific accuracy or completeness.



| Address               |      | Legal Description   | Contributing |
|-----------------------|------|---|--------------|
| 104 E.                | 38th | S 61.92 FT OF LOT 5 SHADOW LAWN                                       | Yes          |
| 106 E.                | 38th | LOT 8 * & W 8FT OF LOT 7 * LESS S 15FT OLT 78 DIV D OAKLAND SQUARE    | Yes          |
| 204 E.                | 38th | S 65FT LOT 19 SHADOW LAWN   | Yes          |
| 207 E.                | 39th | LOT 24A * RESUB LOT 24 SHADOW LAWN                                    | No           |
| 200 W.                | 39th | E 70.62FT OF LOT 18-21 BLK 10 HYDE PARK ADDN NO 2                     | Yes          |
| 202 W.                | 39th | W54.38FT LOT 18-21 BLK 10 HYDE PARK ADDN NO 2                         | Yes          |
| 207 W.                | 39th | LOT 15-17 BLK 13 HYDE PARK ADDN NO 2                                  | Yes          |
| 209 W.                | 39th | LOT 11-14 BLK 13 HYDE PARK ADDN NO 2                                  | Yes          |
| 308 W.                | 39th | LOT 16A HYDE PARK ADDN NO 2 AMENDED PLAT OF LOTS 15,16 & 17 BLK 9     | No           |
| 312 W.                | 39th | LOT 15A HYDE PARK ADDN NO 2 AMENDED PLAT OF LOTS 15,16 & 17 BLK 9     | No           |
| 200 E.                | 40th | LOT 13-16 BLK 31 HYDE PARK ADDN NO 1                                  | No           |
| 205 E.                | 40th | E 29.5X66FT LOT 11 * & S 8.5X66FT & 10X38 LOT 27 SHADOW LAWN          | No           |
| 306 E.                | 40th | LOT 14-16 BLK 30 HYDE PARK ADDN                                       | No           |
| 404 E.                | 40th | LOT 14-16 BLK 29 HYDE PARK ADDN                                       | Yes          |
| 200 W.                | 40th | LOT 13-16 BLK 31 HYDE PARK ADDN NO 1                                  | Yes          |
| 406 W.                | 40th | W50.5FT OF LOT 17-21 * & CEN 12.46FT OF LOT 17-18 HYDE PARK ADDN NO 2 | Yes          |
| 408 and<br>408 1/2 W. | 40th | LOT 13-16 BLK 7 HYDE PARK ADDN NO 2                                   | Yes          |
| 203 E.                | 41st | LOT 1-2 * & N 16FT LOT 3 BLK 31 HYDE PARK ADDN NO 1                   | Yes          |
| 302 E.                | 41st | LOT 14-16 BLK 27 HYDE PARK ADDN NO 1                                  | No           |
| 108 W.                | 41st | E 50FT OF LOT 13-16 BLK 24 HYDE PARK ADDN NO 1                        | No           |
| 112 W.                | 41st | W 70FT LOT 13-16 BLK 24 HYDE PARK ADDN NO 1                           | Yes          |
| 213 W.                | 41st | LOT 1-5 BLK 5 HYDE PARK ADDN NO 2                                     | Yes          |
| 304 W.                | 41st | E 40FT OF LOT 13-16 BLK 17 HYDE                                       | Yes          |
| 306 W.                | 41st | CEN 50FT OF LOT 13-16 BLK 17 HYDE PARK ADDN NO 2                      | Yes          |
| 308 W.                | 41st | W 40FT OF LOT 13-16 BLK 17 HYDE PARK ADDN NO 2                        | Yes          |
| 311 W.                | 41st | E65FT LOT 1-4 BLK 6 HYDE PARK ADDN NO 2                               | Yes          |
| 313 W.                | 41st | W 65FT LOT 1-4 BLK 6 HYDE PARK ADDN NO 2                              | No           |
| 404 W.                | 41st | LOT 17-18 BLK 4 HYDE PARK ADDN NO 2                                   | Yes          |
| 405 W.                | 41st | E50FT LOT 1-2 BLK 7 HYDE PARK ADDN NO 2                               | Yes          |
| 501 W.                | 41st | E44.33FT LOT 30-32 BLK 8 HYDE PARK ADDN NO 2                          | Yes          |
| 503 W.                | 41st | W 80.27 FT OF LOT 30-32 BLK 8 HYDE PARK ADDN NO 2                     | Yes          |
| 511 W.                | 41st | W 80.27 FT OF LOT 30-32 BLK 8 HYDE PARK ADDN NO 2                     | Yes          |
| 105 E.                | 42nd | LOT 1&2 BLK 25 HYDE PARK ADDN NO 1                                    | Yes          |
| 303 E.                | 42nd | LOT 1-4 BLK 27 HYDE PARK ADDN NO 1                                    | No           |
| 304 E.                | 42nd | LOT 15 & 16 BLK 20 HYDE PARK ADDN NO 1                                | Yes          |

|                       |   |   |     |
|-----------------------|---|---|-----|
| 4112 Avenue           | A | LOT 29-30 BLK 3 HYDE PARK ADDN NO 2                                     | Yes |
| 4114 Avenue           | A | LOT 31-32 BLK 3 HYDE PARK ADDN NO 2                                     | Yes |
| 4115 Avenue           | A | LOT 3-4 BLK 4 HYDE PARK ADDN NO 2                                       | Yes |
| 4117 Avenue           | A | LOT 1-2 BLK 4 HYDE PARK ADDN NO 2                                       | Yes |
| 4200 Avenue           | A | LOT 17-22 BLK 2 HYDE PARK ADDN NO 2                                     | No  |
| 4201 Avenue           | A | LOT 14-16 BLK 1 HYDE PARK ADDN NO 2                                     | No  |
| 4203 Avenue           | A | LOT 13 * & S 10FT OF LOT 12 BLK 1 HYDE PARK ADDN NO 2                   | No  |
| 4205 Avenue           | A | LOT 11 * & N 15 FT OF LOT 12 BLK 1 HYDE PARK ADDN NO 2                  | No  |
| 4207 Avenue           | A | LOT 9-10 BLK 1 HYDE PARK ADDN NO 2                                      | Yes |
| 4209 Avenue           | A | LOT 7-8 BLK 1 HYDE PARK ADDN NO 2                                       | Yes |
| 4210 Avenue           | A | LOT 27-28 BLK 2 HYDE PARK ADDN NO 2                                     | Yes |
| 4211 Avenue           | A | LOT 5-6 BLK 1 HYDE PARK ADDN NO 2                                       | No  |
| 4212 Avenue           | A | LOT 29-30 BLK 2 HYDE PARK ADDN NO 2                                     | No  |
| 4213 Avenue           | A | LOT 3-4 BLK 1 HYDE PARK ADDN NO 2                                       | Yes |
| 4214 Avenue           | A | E 7.5FT OF LOT 31-32 BLK 2 HYDE PARK ADDN NO 2                          | Yes |
| 4215 Avenue           | A | LOT 1-2 BLK 1 HYDE PARK ADDN NO 2                                       | Yes |
| 4108 A&B Avenue       | A | LOT 25-26 BLK 3 HYDE PARK ADDN NO 2                                     | Yes |
| 4206 -<br>4208 Avenue | A | LOT A FIESTA APTS NO 2  | No  |
| 3903 Avenue           | B | LOT 13-14 BLK 9 HYDE PARK ADDN NO 2                                     | Yes |
| 3905 Avenue           | B | LOT 11-12 BLK 9 HYDE PARK ADDN NO 2                                     | Yes |
| 3907 Avenue           | B | LOT 9-10 BLK 9 HYDE PARK ADDN NO 2                                      | Yes |
| 3908 Avenue           | B | 447X425FT OLT 78 HYDE PARK ADDN PEVILION TRACT                          | Yes |
| 3909 Avenue           | B | LOT 7-8 BLK 9 HYDE PARK ADDN NO 2                                       | Yes |
| 3911 Avenue           | B | LOT 1-6 BLK 9 HYDE PARK ADDN NO 2                                       | Yes |
| 3913 Avenue           | B | LOT 1-6 BLK 9 HYDE PARK ADDN NO 2                                       | Yes |
| 4000 Avenue           | B | E67.5FT LOT 17 * & E 67.5FT OF S21FT LOT 18 BLK 7 HYDE PARK ADDN NO 2   | No  |
| 4001 Avenue           | B | LOT 15-16 BLK 6 HYDE PARK ADDN NO 2                                     | Yes |
| 4002 Avenue           | B | E79.5FT LOT 19-21 * & N 4FT OF E79.5 LOT 18 BLK 7 HYDE PARK ADDN NO 2   | No  |
| 4002 1/2 Avenue       | B | E79.5 FT LOT 19-21 * & N4 FT OF E79.5' LOT 18 BLK 7 HYDE PARK ADDN NO 2 | Yes |
| 4003 Avenue           | B | S12.5FT LOT 12,13-14 BLK 6 HYDE PARK ADDN NO 2                          | No  |
| 4004 Avenue           | B | LOT 22-23 BLK 7 HYDE PARK ADDN NO 2                                     | Yes |
| 4005 Avenue           | B | LOT 10-11 * & N 12.5FT OF LOT 12 BLK 6 HYDE PARK ADDN NO 2              | Yes |
| 4006 Avenue           | B | LOT 26 * & S12.5FT LOT 27 BLK 7 HYDE PARK ADDN NO 2                     | Yes |
| 4006 Avenue           | B | LOT 24-25 BLK 7 HYDE PARK ADDN NO 2                                     | Yes |
| 4007 Avenue           | B | LOT 7-9 BLK 6 HYDE PARK ADDN NO 2                                       | Yes |
| 4009 Avenue           | B | LOT 5-6 BLK 6 HYDE PARK ADDN NO 2                                       | Yes |