## HISTORIC LANDMARK COMMISSION

## APRIL 27, 2020

## APPLICATION FOR A CERTIFICATE OF APPROPRIATENESS LHD-2020-0010

# 1105 CASTLE COURT (1105 W. 12<sup>TH</sup> STREET) CASTLE HILL HISTORIC DISTRICT

## **PROPOSAL**

Construct an accessible ramp and deck to the main (south) entrance, replace non-historic infill at the north entrance, and replace and reconfigure windows on non-historic addition.

#### ARCHITECTURE

Reportedly the former mess hall of the Texas Military Institute, the building has been used at various times as a residence and office. It is a one-story, rectangular building with load-bearing limestone walls, a steeply pitched hipped roof, a shed-roofed frame addition on the east, and 2:2 and 6:6 light double-hung wood windows.

### PROJECT SPECIFICATIONS

The proposed project includes:

- 1) On the south elevation at the main entrance and entrance to the addition, demolition of the existing stairs and deck; construction of a new concrete ramp, connecting wood deck on brick piers, and limestone stairs with bronze handrails; and installation of shed-roofed awnings;
- 2) Replacement of the non-historic six-panel main entrance door (south elevation) with a wood door with two lights over a single panel, and reconstruction of the missing transom;
- 3) Replacement of non-historic infill at the north entrance with inoperable door(s):
  - a. Option 1. Wood door with transom and sidelights based on the south entrance, or
  - b. Option 2. Paired wood doors with six lights matching the proportions of the north elevation windows;
- 4) On the non-historic addition, replacement of 1:1 windows and French doors with 4:4 windows and a single multi-light door, and replacement of wood siding with fiber-cement siding;
- 5) Replacement of existing R-panel metal roof with composition shingle roofing and installation of copper half-round gutters; and
- 6) Selective masonry cleaning and repointing.

### STANDARDS FOR REVIEW

The property is contributing to the Castle Hill Historic District. The following requirements from the historic district design standards apply to the proposed project:

#### General District Standards

A.1.b. Do not make changes to the public view of an existing contributing or noncontributing building that have no historic basis and/or that seek to create the appearance of an architectural style that is not original to the existing building.

There is no documentary or physical evidence for the historic appearance of the north entrance; the current infill is believed to be from a 1971 remodel. Paint analysis revealed that the transom and sidelights at the south entrance do not

match the frame but are a historic-period alteration. Option 1 is based on this historic precedent, while Option 2 is differentiated yet compatible.

- C.1.e.2. Unacceptable roof materials are those that are not used elsewhere in the district, are not appropriate for the subject property, or have otherwise been determined incompatible with the district or the subject property.
- C.2.d.1. Acceptable roof materials include but may not be limited to composition shingle, metal roofs of all types except corrugated metal, fiberglass shingles, metal shingles, as determined appropriate.

The building historically had wood shingles, as indicated in 1921 Sanborn fire insurance maps. Composition shingles are an appropriate replacement material.

C.1.f. When repointing existing masonry, new mortar shall match the original mortar in color, composition, texture, and tooling.

Masonry will be repointed to match.

The proposed project meets the applicable standards.


#### COMMITTEE RECOMMENDATIONS

Not reviewed.

#### STAFF RECOMMENDATION


Approve the plans with either Option 1 or Option 2 for the north infill, as selected by the applicant.





## **NOTIFICATIONS**

CASE#: LHD-2020-0010 LOCATION: 1105 CASTLE COURT



1 " = 333 '

This product has been produced by CTM for the sole purpose of geographic reference. No warranty is made by the City of Austin regarding specific accuracy or completeness.



Photos



North elevation, view from West 12th Street. Photo by O'Connell Architecture, 2019.



South elevation and main entrance, view from parking lot. Photo by O'Connell Architecture, 2019.

