

ORDINANCE NO. 20201210-078

AN ORDINANCE REZONING AND CHANGING THE ZONING MAP FOR THE PROPERTY LOCATED AT 14231 NORTH U.S. HIGHWAY 183A SERVICE ROAD NORTHBOUND FROM GENERAL COMMERCIAL SERVICES-MIXED USE (CS-MU) COMBINING DISTRICT TO COMMERCIAL HIGHWAY SERVICES (CH) DISTRICT.

BE IT ORDAINED BY THE CITY COUNCIL OF THE CITY OF AUSTIN:

PART 1. The zoning map established by Section 25-2-191 of the City Code is amended to change the base district from general commercial services-mixed use (CS-MU) combining district to commercial highway services (CH) district on the property described in Zoning Case No. C14-2020-0127, on file at the Housing and Planning Department, as follows:

A 0.0726 acre of land (230,773 square feet), being a portion of Lot 2, Block C, AVERY LAKELINE, a subdivision in Williamson County, Texas, recorded in Document No. 2020023739, of the Official Public Records of Williamson County, Texas, said 0.0726 acre of land being more particularly described by metes and bounds in **Exhibit "A"** incorporated into this ordinance (the "Property"),

locally known as 14231 North U.S. Highway 183A Service Road Northbound in the City of Austin, Williamson County, Texas, generally identified in the map attached as **Exhibit "B"**.

PART 2. This ordinance takes effect on December 21, 2020.

PASSED AND APPROVED

_____, December 10, 2020

§
§
§




Steve Adler
Mayor

APPROVED:



Anne L. Morgan
City Attorney

ATTEST:



Jannette S. Goodall
City Clerk

(Zoning Exhibit)
Lot 2, Block C, Avery Lakeline

Legal Description

BEING A DESCRIPTION OF A TRACT OF LAND CONTAINING 0.0726 ACRE (3,165 SQUARE FEET), BEING A PORTION OF LOT 2, BLOCK C, AVERY LAKELINE, A SUBDIVISION IN WILLIAMSON COUNTY, TEXAS, RECORDED IN DOCUMENT NO. 20200232739 OF THE OFFICIAL PUBLIC RECORDS OF WILLIAMSON COUNTY, TEXAS (O.P.R.W.C.T.), SAID LOT 2 CONVEYED TO ASCENSION SETON IN DOCUMENT NO. 2020029508 (O.P.R.W.C.T.), SAID 0.0726 ACRE BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:



PO Box 90876
Austin, TX 78709
512.554.3371
jward@4wardls.com
www.4wardls.com

COMMENCING, at a 1/2-inch iron rod with "LSI" cap found in the west right-of-way line of North Lake Creek Parkway (64' Right-of-way), and being in the east line of Lot 1, Block A of said Avery Lakeline, from which a 1/2-inch iron rod with "LSI" cap found at the beginning of a right-of-way transition from the west right-of-way line of said North Lake Creek Parkway to the south right-of-way line of Avery Ranch Boulevard (150' Right-of-way) bears, N33°04'19"W, a distance of 554.44 feet;

THENCE, leaving the west right-of-way line of said North Lake Creek Parkway and the east line of said Lot 1, in part over and across said Lot 1, and in part over and across Hema Drive (60' Right-of-way), S01°44'11"E, a distance of 435.82 feet to a calculated point for a point of curvature and **POINT OF BEGINNING** hereof, said point being in the south right-of-way line of said Hema Drive, and being in the north line of Lot 2, Block C of said Avery Lakeline;

THENCE, with the south right-of-way line of said Hema Drive and the north line of said Lot 2, the following two (2) courses and distances:


- 1) Along the arc of a curve to the right, whose radius is **970.00** feet, whose arc length is **213.24** feet and whose chord bears **N36°28'43"E**, a distance of **212.81** feet to a calculated point for a point of tangency hereof, and
- 2) **N42°46'35"E**, a distance of **44.34** feet to a calculated point for a point of curvature hereof, said point being the beginning of a right-of-way transition from the south right-of-way line of said Hema Drive to the west right-of-way line of said North Lake Creek Parkway;

THENCE, continuing with the right-of-way transition from said Hema Drive to said North Lake Creek Parkway, and with the northeasterly line of said Lot 2, along the arc of a curve to the right, whose radius is **25.00** feet, whose arc length is **22.85** feet and whose chord bears **N76°24'08"E**, a distance of **22.07** feet to a calculated point for an angle point hereof;

THENCE, leaving the right-of-way transition from said Hema Drive to said North Lake Creek Parkway, and leaving the northeasterly line of said Lot 2, over and across said Lot 2, **S40°27'12"W**, a distance of **274.47** feet to the **POINT OF BEGINNING** and containing 0.0726 Acre (3,165 Square Feet) of land, more or less.

NOTE:

All bearings are based on the Texas State Plane Coordinate System, Grid North, Central Zone (4203), all distances were adjusted to surface using a combined scale factor of 1.000077918. See attached sketch (reference drawing: 00822_Zoning Exhibit-4.dwg)



Jason Ward, RPLS #5811
4Ward Land Surveying, LLC

10/30/2020





Exhibit A



AVERY RANCH BOULEVARD
(150' R.O.W.)
 (DOC. NO. 2005102680, O.P.R.W.C.T.)

LOT 1, BLOCK A
 AVERY LAKELINE
 DOC. NO. 2020023739
 O.P.R.W.C.T.
OWNER:
 ASCENSION SETON
 DOC. NO. 2020029508
 O.P.R.W.C.T.

P.O.C.
 GRID N: 10,149,579.72
 GRID E: 3,094,060.37

N33°04'19"W
 554.44'
 (N33°04'24"W
 554.44')

[A]

S01°44'11"E 435.82'

HEMA DRIVE
(60' R.O.W.)

[B]

LOT 2, BLOCK C
 AVERY LAKELINE
 DOC. NO. 2020023739
 O.P.R.W.C.T.
OWNER:
 ASCENSION SETON
 DOC. NO. 2020029508
 O.P.R.W.C.T.

P.O.B.
 GRID N: 10,149,144.14
 GRID E: 3,094,073.57

C1
 S40°27'12"W 274.47'
 L1
 C2

ZONING EXHIBIT
 0.0726 ACRE(S)
 3,165 SQUARE FEET

0.0726 ACRE
ZONING EXHIBIT
City of Austin,
Williamson
County, Texas



PO Box 90876, Austin Texas 78709
 WWW.4WARDLS.COM (512) 537-2384
 TBPLS FIRM #10174300

Date:	10/30/2020
Project:	00822
Scale:	1" = 100'
Reviewer:	FM
Tech:	CC
Field Crew:	WC/MM
Survey Date:	JULY 2020
Sheet:	1 OF 2


CURVE TABLE					
CURVE #	LENGTH	RADIUS	DELTA	BEARING	DISTANCE
C1	213.24'	970.00'	12°35'45"	N36°28'43"E	212.81'
C2	22.85'	25.00'	52°22'35"	N76°24'08"E	22.07'

LINE TABLE		
LINE #	DIRECTION	LENGTH
L1	N42°46'35"E	44.34'

LEGEND	
	ZONING BOUNDARY
	EXISTING PROPERTY LINES
	1/2" IRON ROD WITH "LSI" CAP FOUND
	CALCULATED POINT
P.O.B.	POINT OF BEGINNING
P.O.C.	POINT OF COMMENCEMENT
R.O.W.	RIGHT-OF-WAY
DOC. NO.	DOCUMENT NUMBER
O.P.R.W.C.T.	OFFICIAL PUBLIC RECORDS, WILLIAMSON COUNTY, TEXAS
(.....)	RECORD INFORMATION PER DOC. NO. 2020023739

**[A]
NORTH LAKE
CREEK PARKWAY
(64' R.O.W.)**

**[B]
LINNAEA LANE
(60' R.O.W.)**



Jason Ward 10/30/2020

NOTES:

1) ALL BEARINGS ARE BASED ON THE TEXAS STATE PLANE COORDINATE SYSTEM, GRID NORTH, CENTRAL ZONE, (4203), NAD83 (CORS), ALL DISTANCES WERE ADJUSTED TO SURFACE USING A COMBINED SCALE FACTOR OF 1.000077918.


2) SEE ATTACHED METES AND BOUNDS DESCRIPTION.

**0.0726 ACRE
ZONING EXHIBIT
City of Austin,
Williamson
County, Texas**



PO Box 90876, Austin Texas 78709
WWW.4WARDLS.COM (512) 537-2384
TBPLS FIRM #10174300

Date:	10/30/2020
Project:	00822
Scale:	N/A
Reviewer:	FM
Tech:	CC
Field Crew:	WC/MM
Survey Date:	JULY 2020
Sheet:	2 OF 2



ZONING

ZONING CASE#: C14-2020-0127

Exhibit B



SUBJECT TRACT

PENDING CASE

ZONING BOUNDARY

1" = 400'

This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries.

This product has been produced by CTM for the sole purpose of geographic reference. No warranty is made by the City of Austin regarding specific accuracy or completeness.



Created: 11/5/2020