HISTORIC LANDMARK COMMISSION

APPLICATION FOR A CERTIFICATE OF APPROPRIATENESS JULY 6, 2022 HR-2022-075037 HILDRETH-FLANAGAN-HEIERMAN HOUSE

3909 AVENUE G

PROPOSAL

Construct a swimming pool.

PROJECT SPECIFICATIONS

Install a swimming pool, deck, and patio in side yard. Replace existing fence and plant privacy hedges around the pool area.

ARCHITECTURE

The house's 1990 National Register nomination describes it as follows:

[...] 2-story frame dwelling that was built in 1902. As is sometimes seen on contemporaneous houses, the dwelling retains the features of Victorian-era housing coupled with details from the Classical Revival style. The house remains virtually unaltered and is in good condition. A massive 2-story dwelling with a generally square plan, the house rests on a pier-and-beam foundation. The primary (east) facade is dominated by a 2-tier porch featuring Doric columns and turned-wood balustrades suggestive of the Classical Revival style popular in Texas during the early 20th century. A projecting 2- tiered portico a t the south end of the porch marks the entry bay. Fenestration includes a single doorway with transom and double-hung wood sash with 1/1 lights. Polygonal projecting bays on the side (north) elevation alleviate the regular massing. Along with the complex roofscape of steeply pitched hipped and gable roof forms, these features are more typica l of Victorian-er a dwellings. Interior corbelled chimneys of buff-colored brick extend from the north and south slopes of the hipped roof. Modest changes that do not adversely affect the dwelling's historic integrity include a 2- story addition on the rear (west) elevation and installation of metal awnings over the windows and the entry bay of the porch.¹

DESIGN STANDARDS

The City of Austin's <u>Historic Design Standards</u> (March 2021) are based on the Secretary of the Interior's Standards for Rehabilitation and are used to evaluate projects at historic landmarks. The following standards apply to the proposed project:

Sites and streetscapes

1. Vegetation, topography, and landscaping

1.3 If the property had a grassy, open front lawn when constructed, maintain that context. Do not replace the lawn with paving or gravel.

The proposed pool and surrounding deck and fenced area do not maintain the landmarked building's landscape context.

2. Walls and fences

2.4 If constructing a new street-side fence or site wall, design it so that the materials, style, and scale are compatible with and differentiated from the architectural style and period of the building and are in keeping with historic fence styles and heights in the historic district. a. New front fences must be no more than 4' high and have a high degree of transparency. The proposed 4' fence is an appropriate height, but the proposed privacy hedges do not retain a high degree of transparency in order to shield the pool from public view.


Summary


The project does not meet most of the applicable standards.

STAFF RECOMMENDATION

Refer the application to the Architectural Review Committee if the Commission feels that the pool and associated sitework compromise its integrity.

¹ "Hildreth-Flanagan-Heierman House." National Register of Historic Places Registration Form. 1990. https://atlas.thc.texas.gov/NR/pdfs/90001184/90001184.pdf





CASE#: HR 22-075037

LOCATION; 3909 AVENUE G

This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries.

1"= 250'

This product has been produced by CTM for the sole purpose of geographic reference. No warranty is made by the City of Austin regarding specific accuracy or completeness.

